

**BEFORE THE
PENNSYLVANIA PUBLIC UTILITY COMMISSION**

Re: Letter Of Notification Of PPL Electric :
Utilities Corporation, Filed Pursuant To 52 :
Pa. Code Chapter 57 Subchapter G, With :
Respect To The Blue Mountain #1 & #2 :
138 kV Transmission Tap Lines in Moore :
Township, Northampton County, :
Pennsylvania :

Docket No. A-2010-_____

LETTER OF NOTIFICATION

TO THE PENNSYLVANIA PUBLIC UTILITY COMMISSION:

PPL Electric Utilities Corporation (“PPL Electric”), hereby files, pursuant to 52 Pa. Code §57.72(d), this Letter of Notification to request that the Pennsylvania Public Utility Commission (“Commission”) approve the siting and construction of the Blue Mountain #1 & #2 138 kV Transmission Tap Lines (“Blue Mountain Taps”), which will consist of approximately 150 feet of new 138 kV transmission line and will connect the existing Siegfried–Jackson #1 & #2 138 kV Transmission Line to the proposed Blue Mountain 138-12 kV Substation (“Blue Mountain Substation”) to be constructed in Moore Township, Northampton County, Pennsylvania. In support thereof, PPL Electric states as follows:

I. INTRODUCTION AND OVERVIEW

1. This Letter of Notification is filed by PPL Electric, a public utility that provides electric distribution, transmission, and provider of last resort services in Pennsylvania subject to the regulatory jurisdiction of the Commission.

2. PPL Electric's address is Two North Ninth Street, Allentown, Pennsylvania 18101.

3. PPL Electric's attorneys are:

David B. MacGregor (Bar I.D. #28804)
Post & Schell, P.C.
Four Penn Center
1600 John F. Kennedy Boulevard
Philadelphia, PA 19103-2808
Voice: 215.587.1197
Fax: 215.320.4879
E-mail: dmacgregor@postschell.com

John H. Isom (Bar I.D. #16569)
Christopher T. Wright (Bar I.D. # 203412)
Post & Schell, P.C.
17 North Second Street
12th Floor
Harrisburg, PA 17101-1601
Voice: 717.612.6032
Fax: 717.731.1985
E-mail: jisom@postschell.com
E-mail: cwright@postschell.com

Paul E. Russell (Bar I.D. #21643)
Associate General Counsel
PPL Services Corporation
Two North Ninth Street
Allentown, PA 18101
Voice: 610.774.4254
Fax: 610.774.6726
E-mail: perussell@pplweb.com

PPL Electric's attorneys are authorized to receive all notices and communications regarding this Letter of Notification.

4. PPL Electric furnishes electric service to approximately 1.4 million customers throughout its certificated service territory, which includes all or portions of twenty-nine counties and encompasses approximately 10,000 square miles in eastern and central Pennsylvania. PPL Electric is a "public utility" and an "electric distribution company" as

defined in Sections 102 and 2803 of the Pennsylvania Public Utility Code, 66 Pa.C.S. §§ 102, 2803.

5. PPL Electric owns approximately 5,000 miles of transmission lines operating at 69 kV (kilovolts) or higher, approximately 330 substations with a capacity of 10 MVA (megavolt amperes) or more, and approximately 43,000 miles of distribution lines operating at less than 69 kV.

6. This Letter of Notification includes the following accompanying attachments:

- Attachment 1 Necessity Statement.
- Attachment 2 Engineering Description.
- Attachment 3 Environmental Assessment.
- Attachment 4 PPL Electric Design Criteria and Safety Practices.
- Attachment 5 PPL Electric Field Management Program.
- Attachment 6 List of Involved Governmental Agencies, Municipalities, and Other Public Entities.

7. PPL Electric proposes to initially install one new 12 kV distribution line that will be connected to the new Blue Mountain Substation to relieve loading and increase reliability and operating flexibility in the Moore Township area. To accomplish this reinforcement, PPL Electric proposes to construct the Blue Mountain Taps, which will extend approximately 150 feet in length and connect the existing Siegfried–Jackson #1 & #2 138 kV Transmission Line to the proposed Blue Mountain Substation in Moore Township, Northampton County, Pennsylvania. The Blue Mountain Taps, together with the new 12 kV distribution line and the Blue Mountain Substation, is required to improve reliability of service and meet increasing demand in the Moore Township area.

8. Due to the small size of the transmission lines necessary and the presence of other transmission facilities in the area, it is anticipated that the proposed Blue Mountain Taps will have minimal incremental impacts on the area.

9. The proposed Blue Mountain Taps will be constructed entirely on the site for the proposed Blue Mountain Substation, which is owned in fee by PPL Electric.

10. The estimated cost for the Blue Mountain Taps is approximately \$489,000. Construction is scheduled to commence March, 2011 to meet a required in-service date of November, 2011.

11. The proposed Blue Mountain Taps will be located entirely in Moore Township, Northampton County. The Blue Mountain Taps were reviewed with representatives of the Township, County and their planning commissions and none of them have any objection to the Blue Mountain Taps.

II. PROJECT SUMMARY

12. Both the Blue Mountain Substation and Blue Mountain Taps will be located entirely on land owned in fee by PPL Electric. An aerial plot plan is provided at the end of Attachment 2 to this Letter of Notification. The plot plan depicts the location of the existing and proposed facilities.

13. The proposed Blue Mountain Taps will be approximately 150 feet in length. The Taps will connect the existing Siegfried-Jackson #1 & #2 138 kV Transmission Line with the proposed Blue Mountain Substation. The purpose of the Blue Mountain Taps, together with the proposed Blue Mountain Substation and associated 12 kV distribution line, is to provide an additional source of supply to distribution customers located in the Moore Township area.

14. The Blue Mountain Taps and Blue Mountain Substation are needed because the present distribution facilities that supply PPL Electric's distribution customers in that area are projected to exceed the normal planning guidelines for line loading in the winter of 2010-2011 based on PPL Electric's Reliability Principles and Practices Manual ("RP&P"). The Blue Mountain Taps and Blue Mountain Substation will relieve thermal overloading, reduce the number of customers served from the existing distribution line, reduce the overall length of the existing distribution line and its branches, and resolve reliability issues associated with the existing distribution line serving that area.

15. Presently, PPL Electric's distribution customers in this area are served from the Northampton 138-12 kV Substation. The Northampton 138-12 kV Substation has two 138-12 kV transformers energized from the Allentown-Siegfried #1 and #2 138 kV Transmission Line. The Northampton 138-12 kV Substation supplies four 12 kV distribution lines, including the Northampton 31-2 12 kV distribution line.

16. Approximately 2,000 customers are served by the Northampton 31-2 12 kV distribution line. The Northampton 31-2 12 kV distribution line is projected to exceed the normal planning guidelines in PPL Electric's RP&P in the winter of 2010-2011. The normal ratings of the 336 kcmil (thousands of circular mils)¹ aluminum conductors, such as the Northampton 31-2 12 kV distribution line, is 10 MVA. The projected peak load on the distribution line forecasted for the winter of 2010-2011 is 10.1 MVA. Overloading the Northampton 31-2 12 kV distribution line could result in conductor damage or failure.

17. The Northampton 31-2 12 kV distribution line currently exceeds PPL Electric's RP&P guidelines for the number of customers per feeder. The RP&P provides that no more than

¹ A circular mil is the cross-sectional area of a wire one mil in diameter, where 1 kcmil = 0.5067 mm².

1,300 customers should be served from a 12 kV circuit. However, the Northampton 31-2 12 kV distribution line presently serves approximately 2,000 customers. As a result of the overloading, the existing distribution line cannot accommodate any additional load growth.

18. The overall length of the Northampton 31-2 12 kV distribution line and its 12 kV branches is approximately 96 miles. This length exceeds the PPL RP&P guideline of 50 miles of line length per feeder. The Northampton 31-2 12 kV distribution line has limited transfer capability because it is tied to only one other circuit. However, this other circuit presently serves approximately 1,300 customers and cannot accommodate any additional customer load under the PPL RP&P. This limited transfer capability can increase the duration of outages. As a result of the large number of customers experiencing multiple outages per year, the Northampton 31-2 12 kV distribution line has repeatedly been among the worst performing circuits on the PPL Electric system.

19. To alleviate these problems, PPL Electric plans to construct the new Blue Mountain Substation. PPL Electric plans to construct and install a new 12 kV distribution line that will be connected to the Blue Mountain Substation to serve customer load in the Moore Township area to relieve loading and increase reliability and operating flexibility. The Blue Mountain Substation and new 12 kV distribution line will reduce peak loading on the existing Northampton 31-2 12 kV distribution line by approximately 5.2 MVA. The new 12 kV facilities will reduce the number of customers served by the existing Northampton 31-2 12 kV distribution line to within the limits of the PPL Electric RP&P guidelines.

20. The Blue Mountain Substation will be supplied from the existing Siegfried-Jackson #1 & #2 138 kV Transmission Line. The Blue Mountain Taps proposed herein will connect the Blue Mountain Substation with the Siegfried-Jackson #1 & #2 138 kV Transmission

Line. The Blue Mountain Taps will be designed as a double-circuit 138 kV transmission tap lines that will extend approximately 150 feet from the existing Siegfried-Jackson #1 & #2 138 kV Transmission Line to the proposed Blue Mountain Substation. Initially, only the Blue Mountain Tap #1 will be constructed. The Blue Mountain Tap #2 will be constructed when future load increases make it appropriate to maintain service reliability. The proposed Blue Mountain Taps are depicted in the aerial plot plan provided at the end of Attachment 2 to this Letter of Notification.

21. The Blue Mountain Taps initially will require one steel mono-pole, which will be approximately 110 feet in height and will be mounted on a concrete foundation. A second, shorter steel mono-pole will be added when the second Tap is installed.²

22. The proposed Taps will each consist of three power conductors and one overhead ground wire. The power conductors will be 556.5 kcmil, 24/7 strand ACSR.³ The overhead ground wires will be 3/8-inch steel and will provide lightning protection for the proposed Taps.

23. The Blue Mountain Taps will be designed to comply with, and will generally surpass, the applicable minimum standards in the National Electrical Safety Code (NESC).

24. The total estimated cost to design and construct the proposed project is approximately \$2.1 million, which includes \$1.3 million for the new Blue Mountain Substation, \$489,000 for the Blue Mountain Taps, and \$300,000 for distribution work.

25. Construction is scheduled to commence in March 2011 to meet a required in-service date of November 2011.

² The future Blue Mountain Tap #2 will tap the far side of the existing Siegfried-Jackson #1 & #2 138 kV Transmission Line. The second pole is shorter so that the conductors of the Blue Mountain Tap #2 will be low enough to pass underneath the conductors of the Siegfried-Jackson #1 & #2 138 kV Transmission Line.

³ Aluminum conductor steel reinforced.

26. The proposed Blue Mountain Taps and Blue Mountain Substation will be located in Moore Township, Northampton County. The Blue Mountain Taps and Blue Mountain Substation will be constructed entirely on a 7.93-acre parcel owned in fee by PPL Electric.

27. Because the proposed Blue Mountain Taps will be only 150 feet in length and will be installed in the vicinity of existing transmission lines as depicted in the aerial plot plan at the end of Attachment 2 to this Letter of Notification, it is anticipated that the Blue Mountain Taps will have minimal incremental impacts on the area. The 7.93-acre site for the proposed Blue Mountain Substation is traversed by the existing Siegfried-Jackson #1 & #2 138 kV Transmission Line. The site is zoned as a Limited Conservation District, under which substations are listed as a "Special Exception Use." A proposed subdivision is located across from the site for the proposed Blue Mountain Substation. Two existing homes are located nearby, with the closest being approximately 500 feet from the proposed substation. Visual impacts to the existing and future homes will be mitigated by landscaping the site after the project is completed.

28. Accompanying this Letter of Notification is a separately bound volume containing Attachments 1-6, which provide additional information about the Blue Mountain Taps. This Letter of Notification and accompanying Attachments, which are incorporated herein by reference, contain all the information required by 52 Pa. Code § 57.72(d)(4).

III. LETTER OF NOTIFICATION

29. PPL Electric is proceeding by means of a Letter of Notification, instead of a full Application, pursuant to the Commission's regulations at 52 Pa. Code § 57.72(d). The Blue Mountain Taps qualify for use of a Letter of Notification because the tap lines will be less than two miles in length.

30. The Necessity Statement for the Blue Mountain Taps is provided as Attachment 1 accompanying this Letter of Notification. As explained in greater detail therein, the purpose of the Blue Mountain Taps is to improve the reliability of service and to reduce load on the existing distribution facilities in the vicinity of Moore Township, Northampton County.

31. In determining the need for the Blue Mountain Taps, PPL Electric considered one alternative electrical solution or functional configuration. As an alternative functional configuration to the Blue Mountain Taps and Blue Mountain Substation, PPL Electric considered building a new radial distribution line from the Little Gap 69-12 kV Substation. This alternative would require approximately 3.7 miles of new distribution line, which would have to be built over the Blue Mountain and cross the Appalachian Trail. This functional configuration would require upgrades to the Little Gap 69-12 kV Substation to accommodate the additional line and terminal. However, the construction of a new radial line over the heavily wooded Blue Mountain would not be a long term solution to the existing reliability problem in this area. Further, these facilities would only be temporary because projected load growth in the area in the future would require the installation of a new substation to meet the projected increase in demand. As a result, PPL Electric rejected this alternative functional configuration because the proposed Blue Mountain Taps and Blue Mountain Substation provide additional reliability and operating flexibility, allow for a better long-term plan for the entire area, and avoid the investment in facilities that would be useful only temporarily.

32. The proposed Blue Mountain Taps will not create any unreasonable risk of danger to the public health or safety. The Blue Mountain Taps will be designed, constructed, operated, and maintained in a manner that meets or surpasses all applicable NESC minimum standards and

all applicable legal requirements. Descriptions of NESC standards, PPL Electric's design criteria, and PPL Electric's safety practices are provided in Attachment 4 hereto.

33. The Engineering Description of the Blue Mountain Taps is provided in Attachment 2 accompanying this Letter of Notification.

34. The proposed Blue Mountain Taps will be located entirely on the site for the Blue Mountain Substation, which is owned in fee by PPL Electric. As a result, no additional rights-of-way are necessary for the proposed Blue Mountain Taps.

35. No communication towers, pipelines, or other utilities will be affected by the proposed Blue Mountain Taps. The nearest airport is approximately 6.97 miles southeast of the Blue Mountain Substation site. PPL Electric will contact the PennDOT Bureau of Aviation and the Federal Aviation Administration to ensure that the proposed Blue Mountain Taps will not be a hazard to flight operations.

36. The proposed Blue Mountain Taps were reviewed with the Pennsylvania Historical and Museum Commission (PHMC). The PHMC has determined that, due to the absence of historical sites and the small project size, no further archaeological investigations are required.

37. The proposed Blue Mountain Taps will not affect any unique geological, scenic, or natural areas. No national natural landmarks, parks, or recreational facilities are located near the project area. The Devils Potato Patch, an Outstanding Geological Feature of Pennsylvania, is located approximately 3.12 miles from the project area. However, no impact to this feature is anticipated due to its distance from the project area and the small size of the project.

38. The Blue Mountain Taps will not cross any wetlands or other aquatic resources. PPL Electric will also acquire and comply with any required soil erosion and sedimentation control permit conditions.

39. No tree clearing is required for the proposed Blue Mountain Taps. However, to the extent that any tree clearing becomes necessary, PPL Electric will apply its “Specifications for Initial Clearing and Control of Vegetation on or Adjacent to Electric Right-of-Way Through Use of Herbicides, Mechanical, and Hand Clearing Techniques” to mitigate any impacts.

40. PPL Electric has consulted with state and federal agencies to obtain information regarding endangered and threatened species in close proximity to the Blue Mountain Taps. Both the United States Fish and Wildlife Service and the Pennsylvania Fish and Boat Commission noted the potential presence of bog turtles (*Glyptemys muhlenbergii*) in wetlands near the project location. As a result, PPL Electric retained the services of Richard Mellon, Mellon Biological Service to investigate. Mr. Mellon reported that no wetlands were found in close proximity to the project and therefore, there will be no impact on bog turtles. Mr. Mellon’s report and findings were forwarded to the United States Fish and Wildlife Service. PPL Electric will clear the conflict prior to the start of construction.

41. The Blue Mountain Taps were reviewed with representatives of Northampton County, Lehigh Valley Planning Commission, Moore Township Board of Supervisors, and Moore Township Planning Commission. These entities have no objection to the Blue Mountain Taps.

42. Attachment 6 accompanying this Letter of Notification contains a list of the involved governmental agencies, municipalities, and other public entities. Copies of this Letter

of Notification are being served on the agencies listed in Attachment 6 in accordance with 52 Pa. Code § 57.72(d)(3).

43. Attachment 5 accompanying this Letter of Notification explains PPL Electric's standards for Magnetic and Field Management.

44. As soon as practicable after the filing of this Letter of Notification and the assignment by the Commission of a docket number, PPL Electric will publish notice of the filing in newspapers of general circulation in the area of the proposed Blue Mountain Taps. Such notice will contain: (a) the date this Letter of Notification was filed with the Commission; (b) a brief description of the Blue Mountain Taps and their location; (c) locations where the complete Letter of Notification may be reviewed by the public; and (d) an instruction that the interested parties should contact, within 15 days, Rosemary Chiavetta, Secretary, at the Commission's Harrisburg address.


45. This Letter of Notification is filed on the date set forth below. As provided in 52 Pa. Code § 57.72(d)(5), the Commission will review and, by order, approve or disapprove this Letter of Notification. If the Commission approves this Letter of Notification, the proposed Blue Mountain Taps will be constructed as proposed herein without the formal application process set forth at 52 Pa. Code §§ 57.71, *et seq.*

IV. CONCLUSION

WHEREFORE, PPL Electric Utilities Corporation respectfully requests that the Pennsylvania Public Utility Commission approve the siting and construction of the Blue Mountain #1 and #2 138 kV Tap Lines in Moore Township, Northampton County, Pennsylvania, that is explained above and in the Attachments hereto.

Respectfully submitted,

Paul E. Russell (ID # 21643)
Associate General Counsel
PPL Services Corporation
Office of General Counsel
Two North Ninth Street
Allentown, PA 18106
Phone: 610-774-4254
Fax: 610-774-6726
E-mail: perussell@pplweb.com



David B. MacGregor (ID # 28804)
Post & Schell, P.C.
Four Penn Center
1600 John F. Kennedy Boulevard
Philadelphia, PA 19103-2808
Phone: 215-587-1197
Fax: 215-320-4879
E-mail: dmacgregor@postschell.com

John H. Isom (ID # 16569)
Christopher T. Wright (ID # 203412)
Post & Schell, P.C.
17 North Second Street
12th Floor
Harrisburg, PA 17101-1601
Phone: 717-731-1970
Fax: 717-731-1985
E-mail: jisom@postschell.com
E-mail: cwright@postschell.com

Of Counsel:

Post & Schell, P.C.

Date: 9/21/2010


Attorneys for PPL Electric Utilities Corporation

VERIFICATION

:

I, David G. DeCampli, being the President of PPL Electric Utilities Corporation, hereby state that the facts above set forth are true and correct to the best of my knowledge, information and belief and that I expect that PPL Electric Utilities Corporation to be able to prove the same at a hearing held in this matter. I understand that the statements herein are made subject to the penalties of 18 Pa. C.S. § 4904 relating to unsworn falsification to authorities.

Date: 9/15/10


David G. DeCampli



Before the
Pennsylvania Public Utility Commission

**BLUE MOUNTAIN #1 & #2
138 kV TAP LINE**

**Attachments in Support of the
Letter of Notification**

Application Docket No. _____

Submitted by: PPL Electric Utilities Corp.

SUMMARY

This filing is submitted by PPL Electric Utilities Corporation (PPL Electric) pursuant to the Pennsylvania Public Utility Commission's (PUC) regulations at 52 Pa. Code §§ 57.71 through 57.77 for PUC approval to site and construct the Blue Mountain #1 & #2 138 kV Transmission Tap Line. The proposed project is located on land owned in fee by PPL Electric in Moore Township, Northampton County. The proposed project was reviewed with both the County and the Township and neither have any objection to the proposed project.


The proposed tap line will provide the source of electrical supply to the new Blue Mountain 138 - 12 kV Substation. The substation and associated 12 kV distribution facilities are required to meet the increasing demand for electricity and improve the reliability of service in Moore Township, Northampton County and vicinity.

The estimated cost to design and construct the proposed 138 kV tap line is \$489,000. The project has a scheduled construction start date of March 2011 in order to meet the required in-service date of November 2011.

This document, which describes the need for the project and discusses the engineering and siting analysis for the proposed construction, consists of the following attachments:

- Attachment 1 - Necessity Statement
- Attachment 2 - Engineering Description
- Attachment 3 - Environmental Assessment
- Attachment 4 - PPL Design Criteria and Safety Practices
- Attachment 5 - PPL Electric Magnetic Field Management Program
- Attachment 6 - List of Involved Governmental Agencies, Municipalities and Other Public Entities

PPL ELECTRIC UTILITIES SERVICE TERRITORY



Attachment 1

ATTACHMENT 1
BLUE MOUNTAIN #1 & #2 138 kV TAP LINE
NECESSITY STATEMENT

TABLE OF CONTENTS

<u>SECTION</u>	<u>TOPIC</u>	<u>PAGE</u>
A.	INTRODUCTION.....	1
B.	EXISTING SYSTEM.....	2
C.	DEFINITION OF THE PROBLEM.....	2
D.	PROPOSED SOLUTION.....	2
E.	FUNCTIONAL ALTERNATIVES.....	3

LIST OF FIGURES

FIGURE 1	FUNCTIONAL ONE-LINE DIAGRAM OF EXISTING TRANSMISSION FACILITIES.....	4
FIGURE 2	FUNCTIONAL ONE-LINE DIAGRAM OF PROPOSED TRANSMISSION FACILITIES.....	5
FIGURE 3	FUNCTIONAL ONE-LINE DIAGRAM OF EXISTING DISTRIBUTION FACILITIES.....	6
FIGURE 4	FUNCTIONAL ONE-LINE DIAGRAM OF PROPOSED DISTRIBUTION FACILITIES.....	7
MAP 1	PPL ELECTRIC TRANSMISSION FACILITY MAP	ATTACHMENT 1 MAP POCKET

ATTACHMENT 1
BLUE MOUNTAIN #1 & #2 138 kV TAP LINE
NECESSITY STATEMENT

A. INTRODUCTION

PPL Electric is requesting PUC approval to construct a double-circuit 138 kV transmission tap line. Initially, only one circuit will be constructed. The second circuit will be constructed when the increased demand for electricity requires its addition to maintain reliability of service to customers. The proposed Blue Mountain #1 & #2 138 kV Tap Line will extend approximately 150 feet from the Siegfried-Jackson #1 & #2 138 kV Transmission Line to the new PPL Electric-owned Blue Mountain 138 - 12 kV Substation. The proposed facilities are required to provide more reliable service to customers in the Moore Township area.

The estimated cost to design and construct the proposed tap line is approximately \$489,000. Construction is scheduled to begin in March 2011 to meet a required in-service date of November 2011. The required in-service date is defined as the date the proposed facility needs to be placed in service to prevent equipment overloads that have the potential to damage existing facilities, and, thereby, cause the interruption of service to customers.

A PPL Electric system map showing existing transmission facilities with a design voltage of 35 kV or greater is included in the map pocket at the end of Attachment 1. This filing addresses only the existing and proposed 138 kV system in the Moore Township area.


Substation and the Blue Mountain 138 kV Tap Line. One new 12 kV circuit will initially be installed. The new Blue Mountain 138 - 12 kV Substation and the new 12 kV distribution circuit will allow transfer of load to relieve the projected overloading on the Northampton 31-2 12 kV Line. The Blue Mountain Substation and new 12 kV distribution line will reduce peak loading on the existing Northampton 31-2 12 kV distribution line by approximately 5.2 MVA. The new 12 kV circuit will reduce the number of customers served by the Northampton 31-2 12 kV Line to within the limits of the PPL Electric RP&P guidelines. In addition, the new substation will provide an additional source for load transfers between distribution circuits, which will improve the reliability and operating flexibility in the Moore Township area.

The total estimated cost of this solution is approximately \$2,110,000 which includes \$1,321,000 for the new substation, \$489,000 for the transmission, and \$300,000 for distribution work.


E. FUNCTIONAL ALTERNATIVE

An alternative to building the new substation and transmission line would be to build a new radial distribution line from the Little Gap 69-12 kV Substation. This would require approximately 3.7 miles of new distribution line, which would have to be built over the Blue Mountain and cross the Appalachian Trail. However, the construction of a new line over the heavily wooded Blue Mountain would not be a long term solution to the existing reliability problem in this area. As a result, PPL Electric rejected this alternative because the preferred alternative described in Section D above, provides sufficient additional capacity and greater long-term reliability benefits.


FIGURE 1
FUNCTIONAL ONE-LINE DIAGRAM OF EXISTING
TRANSMISSION FACILITIES




**FIGURE 2
FUNCTIONAL ONE-LINE DIAGRAM OF PROPOSED
TRANSMISSION FACILITIES**



**FIGURE 3
FUNCTIONAL ONE-LINE DIAGRAM OF EXISTING DISTRIBUTION
FACILITIES**




**FIGURE 4
FUNCTIONAL ONE-LINE DIAGRAM OF PROPOSED
DISTRIBUTION FACILITIES**



SUBSTATION LISTING

1 WEST WILLIAMSPORT	15 CRACKERSPORT	301 CENTER CITY
2 FAIRFIELD	16 SCHNECKSVILLE	302 NEW KINGSTOWN
3 MONTGOMERY	17 HEMLOCK	303 REAMSTOWN
4 VARDEN	18 MT. ALLEN	304 DUPONT
5 HONESDALE	19 PRINCE	305 HUMBLDIT
6 JERSEY SHORE	20 WAKEFIELD	306 CEDAR AVE.
7 LOGANTON	21 COOPERSBURG	307 INDIAN ORCHARD
8 VALMONT	22 WEST CARLISLE	308 NOTTINGHAM
9 LIMESTONE	23 BENVENUE	309 NORTH COOLBAUGH
10 NORTHUMBERLAND	24 HEGINS	310 LETORT
11 REED	25 YATESVILLE	311 EAST MOUNTAIN
12 WRIGHT	26 CENTRAL ALLENTOWN	312 JERMYN
13 ST. JOHNS	27 OBERLIN	313 BLOOMSBURG
14 FREELAND	28 STRASBURG	314 MIFFLINTOWN
15 GILBERT	29 ATGLEN	315 RIDGE ROAD
16 CHERRY HILL	30 BROOKSIDE	316 SUSQUEHANNA
17 SUSQUEHANNA 230KV	31 WILLIAMSTOWN	317 T-10 SW. YD.
18 TAMANEND	32 CHRISTIANS	318 KIMBLE
19 WHITE HILL	33 E. PETERSBURG	319 OTTER CREEK
20 PALMERTON	34 VERNERSVILLE	320 STEEL CITY
21 HAMILTON	35 N. BETHLEHEM	321 MCGOVERNSVILLE
22 HUNTER	36 W. ALLENTOWN	322 ROBESONIA
23 FAIRVIEW	37 FLEMINGTON	323 SFOGELSVILLE
24 MONTBOUR PUMP	38 MECKESVILLE	324 ELROY
25 MT. CARMEL	39 DIMERSVILLE	325 BUSHKILL
26 KELLY	40 MILLERSVILLE	326 WALLENPAUPACK
27 SPORTING HILL	41 SHILLINGTON	327 ELK MOUNTAIN
28 WANDY CITY	42 DUKE	328 JACK FROST
29 GREENWOOD	43 MCALISTERVILLE	329 HARWOOD 230/69KV
30 MOWRY	44 NEWFUNDLAND	330 HARWOOD CTG
31 ALTAUNTON	45 MARLIN	331 HARWOOD 69/12KV
32 HAMIL	46 WEST BERWICK	332 NAZARETH
33 ASHFIELD	47 KEYSER AVENUE	333 ALBURTIS
34 SOUTH SLATINGTON	48 MICKLEYS	334 FRACKVILLE
35 SOUTH MIDDLEBURG	49 EAST ALLENTOWN	335
36 WALKER	50 PINE RIDGE	336 ELIMSPORT
37 FRAILY	51 DALMATIA	337 ALLENWOOD
38 MORGANTOWN	52 PENNSBORO	338 JACK FROST
39 GRYPT	53 NORTH COLUMBIA	339 GRATZ
40 CRESSONA	54 HUGHESVILLE	340 HOCKERSVILLE
41 SOUTH WHITEHALL	55 SOUTH ALLENTOWN	341 BLOOMING GROVE
42 EAST TOMICKEN	56 MONROE	342 MONROE
43 BEAR GAP	57 LACKAWANNA #	343 LACKAWANNA #
44 SALISBURY	58 JACKSON	344 STANTON
45 SOUTH MILTON	59 EAST PALMERTON	345 JACKSON
46 HETZELBERG	60 ELIZABETHTOWN	346 EAST PALMERTON
47 LYKENS	61 ENOLA	347 SIEGFRIED
48 UPPER HANOVER	62 TERRE HILL	348 HOESACK 230/69KV
49 RICHLAND	63 BUCK	349 HOESACK 500KV
50 MACADA	64 MT. BETHEL	350 CONESTOGA
51 ROCKVILLE	65 RICHFIELD	351 MANDR
52 THOMPSONTOWN	66 SCRANTON	352 CLINTON
53 PAXTON	67 SWIN LAKES	353 EXCHANGE
54 COCALICO	68 HARLEIGH	354 MILTON
55 EAST ELIZABETHTOWN	69 TAPTON	355 DAUPHIN
56 WARWICK	70 WARREN CREEK	356 QUARRY SUB.
57 EARL	71 DRWIGSBURG	357 STEELTON
58 HEMPFIELD	72 EAST TEXAS	358 JUNIATA 500/230KV
59 EAST LANCASTER	73 CANDELS	359 JUNIATA 230/69KV
60 KINZER	74 LINDEN	360 CUMBERLAND
61 MT. NEBO	75 MT. JOY	361 DONEGAL
62 MT. POCONO	76 MINST. BRAIL	362 JENKINS 230/69KV
63 PENNS	77 LAKE NAOMI	363 JENKINS CTG
64 GOULDSBORO	78 LANARK	364 WILKES-BARRE
65 DILLERVILLE	79 MONTOURSVILLE	365 BUXMONT
66 GIRARD MANDR	80 PORT CARBON	366 SOUTH AKRON 230/138/69KV
67 KENMAR	81 MILLBURN	367 SOUTH AKRON 69/12KV
68 GOWEN CITY	82 WILFORD	368 SOUTH MANHEIM 69/12KV
69 ELLIOT HEIGHTS	83 TREICHLERS	369 SOUTH MANHEIM 230/69KV
70 ROHRERSTOWN	84 ROSEVILLE	370 ENGLISIDE
71 MACUNGIE	85 RUTHERFORD	371 COLUMBIA
72 EAST HAZLETON	86 HARTLAND	372 DANVILLE
73 WAGNERS	87 PARRISH	373 SUNBURY
74 EAST CARBONDALE	88 POINT NEW HOLLAND	374 HUMMELS WHARF
75 EYNDON	89 LINCOLN	375 LYCOMING
76 MINDOKA	90 MIDDLETON	376 LOCK HAVEN CTG
77 OLD FORGE	91 STATE HILL	377 LOCK HAVEN 69/12KV
78 FOUNTAIN SPRINGS	92 MILLVILLE	378 HUMMELSTOWN
79 SULLIVAN TRAIL	93 TINKER	379 WEST SHORE
80 SWATARA	94 LAKEVILLE	380 MONTAGE
81 HEPBURN	95 NORTH MANHEIM	381 SOUTH FARMERSVILLE
82 HATFIELD	96 HATFIELD	382 WOODSVILLE
83 HERSCHEY	97 S. HERSCHEY	383 FISHBACH
84 FRANCONIA	98 S. WILLIAMSPORT	384 BERKS
85 EMMAUS	99 FIGELSVILLE	385 MONTOUR
86 MORGAN	100 WINDSOR	386 SUBURBAN YARD
87 HROOP	101 W. WILLOW	387
88 CHAPMAN	102 WESTGATE	388
89 SUBURBAN	103 DELA	389 MACK
90	104 SUMMERDALE	390 WILLIAMSPORT
91	105 DORNEYVILLE	391 HARRISBURG
92	106 BOHEMIA	392 ELDRED
93	107 WHITE HAVEN	393
94	108 LAURELTON	394 MILLWOOD
95	109 LINGLESTOWN	395 TELFORD
96	110 PICCONI FARMS	396 TWIN VALLEY
97	111 HICKORY RUN	397 DEVONSHIRE
98	112 BLOOMING GLEN	398 JESSUP
99	113 SHERMANS DALE	399 BELTZVILLE
100	114 LARRY'S CREEK	400 HAWLEY
101	115 SEDERSVILLE	401 EFFORT MOUNTAIN
102	116 ROSEMONT	402 COPPERSTONE
103	117 QUARRVILLE	403 RED FRONT
104	118 LAWNTON	404 APPENZELL
105	119 TITZ	405 BLUE MOUNTAIN
106	120 RENOVO	
107	121 WALNUT	
108	122 WATSON	
109	123 TRELVERTOWN	
110	124 LAVING	
111	125 SPRING	
112	126 COLONIAL PARK	
113	127 WEST LANCASTER	
114	128 MADISONVILLE	
115	129 NEFFSVILLE	
116	130 BEAVERTOWN	
117	131 BELMONT	
118	132 LAKE HARMONY	
119	133 GEORGETOWN	
120	134 SCOTT	
121	135 N. HARRISBURG	
122	136 MOUNT ROCK	
123	137 GREENLAND	
124	138 LANDISVILLE	
125	139 GREEN PARK	
126	140 SELINSGRIVE	
127	141 SUMNER	
128	142 AUBURN	
129	143 ROHRERSBURG	
130	144 DERRY	
131	145 EAST GREENVILLE	
132	146 WEST DAMASCUS	
133	147 NEW COLUMBIA	
134	148 FARMERSVILLE	
135	149 GREENFIELD	
136	150 NORTH STRAUSSBURG	
137	151 TANNERSVILLE	
138	152 ELIZABETHVILLE	
139	153 WYOMISSING	
140	154 EXETER	
141	155 MARIETTA	



INTERCONNECTIONS

PS PUBLIC SERVICE ELECTRIC AND GAS CO. OF N.J.
 ME METROPOLITAN EDISON CO. (FIRST ENERGY)
 PE PHILADELPHIA ELECTRIC CO. (PECO ENERGY)
 BC BALTIMORE GAS AND ELECTRIC CO.
 SH SAFE HARBOR WATER POWER CORPORATION
 UP THE UNITED GAS IMPROVEMENT CO. - LUZERNE ELECTRIC DIVISION
 PN PENNSYLVANIA ELECTRIC CO. (FIRST ENERGY)
 JC JERSEY CENTRAL POWER AND LIGHT CO. (FIRST ENERGY)

- COMBUSTION TURBINE
- HYDRE ELECTRIC
- COMBINATION
- FIRM SALES
- SUBSTATION / SWITCHING STATION
- STEAM ELECTRIC
- NON-UTILITY GENERATION
- INDEPENDENT POWER PRODUCERS

- 500KV OPERATION
- 230KV OPERATION
- 138KV OPERATION
- 69KV OPERATION

NO.	DATE	ACCT.	DESCRIPTION	RRC	RWM	KBK
68	7/9/10	165202	INDICATE WEST HEMPFIELD-PRINCE #1 & #2 RECONSTRUCTION			
67	4/13/10	169983	ADDED MIDDLETOWN JUNCTION-COPPERSTONE & COPPERSTONE-NORTH LANBAN 230KV LINE.			
70	3/13/10	169008	ADDED BLUE MOUNTAIN #1 & #2 138KV TAP			
69	7/9/10	165202	INDICATE WEST HEMPFIELD- PRINCE #1 & #2 RECONSTRUCTION			

ACCT - 805201
 SCALE - NONE
 BY - CDW

APPROVED: G. HAKUN III
 DATE: 7/1/05
 PPL ELECTRIC UTILITIES

PPL DRAWING NO. **D191830**
 SHEET NO. **1** REV. **70**

REVIEWED: JLL, RWM, KBK
 BY: JLL, RWM, KBK

PLAN & PROFILE NO. LOCATION CODES TRANSMISSION MAP NO. SORTS

PPL E.U. FORM 4897 (7/03)

PC CAD

Attachment 2

ATTACHMENT 2
BLUE MOUNTAIN #1 & #2 138 kV TAP LINE
ENGINEERING DESCRIPTION

TABLE OF CONTENTS

<u>SECTION</u>	<u>TOPIC</u>	<u>PAGE</u>
A.	DESCRIPTION OF PROPOSED LINE RELOCATION.....	1
B.	MAGNETIC FIELD MANAGEMENT.....	3
C.	RIGHT-OF-WAY STATUS.....	3

LIST OF TABLES

TABLE 1	DESIGN MINIMUM CONDUCTOR CLEARANCES.....	2
TABLE 2	CONDUCTOR THERMAL RATING.....	2

LIST OF FIGURES

FIGURE 1	PROPOSED DOUBLE-CIRCUIT 138 kV TAP STRUCTURE.....	4
FIGURE 2	PROPOSED 138 kV SWITCH STRUCTURE	5

MAP

AERIAL EXHIBIT.....	ATTACHMENT 2 MAP POCKET
---------------------	----------------------------

ATTACHMENT 2
BLUE MOUNTAIN #1 & #2 138 kV TAP LINE
ENGINEERING DESCRIPTION

A. DESCRIPTION OF PROPOSED LINE RELOCATION

PPL Electric proposes to install a double-circuit 138 kV transmission tap line from its existing Siegfried – Jackson #1 & #2 138 kV Transmission Line to the proposed Blue Mountain 138 – 12 kV Substation. Initially, only one circuit will be constructed. The second circuit will be constructed when the increased demand for electricity requires its addition to maintain customer reliability. The proposed tap line will be located in Moore Township, Northampton County. Refer to the Aerial Exhibit at the end of Attachment 2 which depicts the location of these facilities.

The proposed tap line will be approximately 150 feet long. One double-circuit steel tap pole, approximately 110 feet in height will be installed on a concrete foundation. A second, shorter pole will be added in the future when load increases mandate the addition of the second circuit.¹ These poles will be installed in the existing Siegfried – Jackson Line. The proposed tap line initially will consist of three power conductors (single-circuit operation) and one overhead ground wire. The power conductors will be 556.5 KCMIL (thousands of circular mils)² 24/7 strand ACSR.³ The 3/8-inch steel overhead ground wire will provide lightning protection for the proposed tap line. Two new 138 kV switches will be installed in the existing Siegfried – Jackson Line to provide enhanced operating flexibility. Figures 1 and 2 are photographs of structures similar to the ones that will be installed for the proposed tap line.

¹ The future second circuit will tap the far side of the existing Siegfried – Jackson #1 & #2 138 kV Transmission Line. The second pole is shorter so that the conductors of the second circuit will be low enough to pass underneath the conductors of the Siegfried – Jackson #1 & #2 138 kV Transmission Line.

² A circular mil is the cross-sectional area of a wire one mil in diameter, where 1 kcmil = 0.5067 mm².

³ Aluminum conductor steel reinforced.

This new 138/69 kV line will be designed according to and will generally surpass minimum National Electrical Safety Code standards. Additional design criteria and safety rules practiced by PPL Electric are included in Attachment 4. The minimum conductor to ground clearance will be 30 feet which occurs at a maximum conductor temperature of 125°C. The design minimum conductor ground clearances and conductor thermal ratings are as follow:

TABLE 1
DESIGN MINIMUM CONDUCTOR CLEARANCES
FOR 556.5 KCMIL 24/7 STRANDING ACSR*

<u>Condition</u>	<u>Double-Circuit Design Clearance-to-Ground</u>
Normal load, average weather (16°C ambient temperature)	31.0 Feet
Predicted extreme thermal load (125°C conductor temperature)	30.0 Feet
Predicted NESC extreme wind load (16°C ambient temperature)	31.0 Feet
Predicted extreme weather conditions (1-inch ice, 4 lbs. wind, -18°C)	31.0 Feet

*Clearances based on a maximum tension of 3,000 lbs. at 1 inch ice, 4 lbs. wind, -18°C and a ruling span of 150 feet.

TABLE 2
CONDUCTOR THERMAL RATING
556.5 KCMIL 24/7 STRANDING ACSR
(257°F) 125°C MAXIMUM CONDUCTOR TEMPERATURE

<u>Condition</u>	<u>Ambient Temperature °C</u>	<u>Wind Speed Knots</u>	<u>Ampacity Amps</u>
Summer Normal	35	0	815
Winter Normal	10	0	926
Summer Emergency	35	1.5	1041
Winter Emergency	10	1.5	1163

B. MAGNETIC FIELD MANAGEMENT

PPL Electric's Magnetic Field Management Program is summarized in Attachment 5 and applied to reconstruction and new line projects. In order to lower magnetic field exposures, the program generally prescribes the use of line design that provides 5 feet higher ground clearances and reverse phasing new double-circuit lines where it is feasible to do so at low or no cost. The implementation of additional modifications will be considered, provided those modifications can be made at low or no cost.

For this project, reverse phasing cannot be utilized to reduce magnetic field levels because, initially, only one circuit is being constructed. PPL Electric will evaluate reverse phasing when the second circuit is added in the future.

C. RIGHT-OF-WAY STATUS

The proposed tap line will be constructed entirely on the proposed substation site. PPL Electric owns the substation site in fee and, therefore, no new additional right-of-way is required for the project.

PROPOSED DOUBLE-CIRCUIT 138 kV TAP STRUCTURE




FIGURE 1




Note: Structure color will be the same as the structure shown in Figure 2.

PROPOSED 138 kV SWITCH STRUCTURE



FIGURE 2

THIS DRAWING IS THE PROPERTY OF PPL ELECTRIC UTILITIES AND CONTAINS PROPRIETARY AND CONFIDENTIAL INFORMATION WHICH MUST NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT WRITTEN AUTHORIZATION FROM PPL ELECTRIC UTILITIES.



ACCT- 170116		BLUE MOUNTAIN #1 & #2	
SCALE- 1"=30'		138kV TAPS	
BY-		AERIAL EXHIBIT	
REVIEWED	TOWNSHIP OF MOORE	DATE	NORTHAMPTON COUNTY, PA.
	APPROVED	7/21/10	PPL ELECTRIC UTILITIES
PPL DRAWING NO.	SHEET NO.	REV.	
		1	0

NO.	DATE	ACCT.	REVISION	BY	REVIEWED	APPROVED



PPL

Attachment 3

ATTACHMENT 3
BLUE MOUNTAIN #1 & #2 138 kV TAP LINE
ENVIRONMENTAL ASSESSMENT

TABLE OF CONTENTS

<u>SECTION</u>	<u>TOPIC</u>	<u>PAGE</u>
A.	INTRODUCTION.....	1
B.	LAND USE.....	1
C.	CULTURAL RESOURCES.....	2
D.	NATURAL FEATURES.....	2
E.	THREATENED AND ENDANGERED SPECIES.....	3

ATTACHMENT 3
BLUE MOUNTAIN #1 & #2 138 kV TAP LINE
ENVIRONMENTAL ASSESSMENT

A. INTRODUCTION

PPL Electric is requesting PUC approval to site and construct a double-circuit 138 kV transmission tap line. The proposed tap line will be designed and constructed for future double circuit operation, although initially, only one circuit will be constructed. The second circuit will be constructed when increased demand for electricity requires its addition to maintain reliability of service to customers. The proposed line is approximately 150 feet long and will provide service to the proposed Blue Mountain 138 – 12 kV Substation.

The proposed project was reviewed with representatives of Moore Township and Northampton County, and neither the Township nor the County has any objection. A list of involved governmental agencies, municipalities, and other public entities is presented in Attachment 6.

B. LAND USE

Both the proposed tap line and substation are located on approximately 7.93 acres of land owned by PPL Electric. The property is located in the southeastern quadrant formed by the intersection of Delps Road and North Mink Road in Moore Township, Northampton County. The property is zoned as a Limited Conservation District and substations are listed as a “Special Exception Use”. The source transmission line for the proposed substation crosses the property, resulting in a short, 150-foot tap into the substation.

A proposed subdivision is located across Delps Road from the substation site. Two existing homes are located nearby, the closest being approximately 500 feet

from the proposed substation. Visual impacts to the existing and future homes will be mitigated by landscaping the site after the project is completed.

No communication towers, pipelines, or other utilities will be affected by the proposed project. The nearest airport, Slatington Airport, is approximately 6.97 miles east southeast of the project area. PPL Electric will file the appropriate documentation with both the Federal Aviation Administration and the PennDOT Bureau of Aviation to ensure the proposed tap line will not be a hazard to the airport's flight operations.

C. CULTURAL RESOURCES

This project was reviewed with the Pennsylvania Historical and Museum Commission (PHMC). PHMC has determined that, based upon their survey files, which include both archaeological sites and standing structures, there are no National Register eligible or listed historic or archaeological properties in the area of this proposed project (File No. ER 2009-1026-077-A).

D. NATURAL FEATURES

Devils Potato Patch, an Outstanding Geological Feature of Pennsylvania, is located approximately 3.12 miles from the project area. No impacts are anticipated due to its distance to the project area and the small size of the project. No national natural landmarks, parks, or recreational facilities are located near the project area. No tree clearing is required. The proposed tap line will not cross any wetlands or other aquatic resources. As required, PPL Electric will acquire and adhere to the terms and conditions of any required soil erosion and sedimentation control plans.

E. **THREATENED AND ENDANGERED SPECIES**

PPL Electric has coordinated with certain state and federal agencies to obtain information regarding endangered and threatened plant and animal habitat in close proximity to the project area. Both the United States Fish and Wildlife Service and the Pennsylvania Fish and Boat Commission note the potential presence of bog turtles (*Glyptemys muhlenbergii*) in wetlands near the project location. PPL Electric has retained the services of Richard Mellon, Mellon Biological Service to investigate. Mr. Mellon reports that no wetlands were found in close proximity to the project and therefore, there will be no impact on bog turtles. Mr. Mellon has forwarded a report with his findings to the United States Fish and Wildlife Service. PPL Electric will clear the possible conflict prior to the start of construction.

SUPPORTING ATTACHMENTS

ATTACHMENT 4 – PPL Electric Design Criteria and Safety Practices

ATTACHMENT 5 – Magnetic Field Management at PPL Electric

ATTACHMENT 6 – List of Involved Governmental Agencies, Municipalities, and Other
Public Entities

Attachment 4

ATTACHMENT 4

PPL DESIGN CRITERIA AND SAFETY PRACTICES

The National Electrical Safety Code (NESC) is a set of rules to safeguard people during the installation, operation, and maintenance of electric power lines. The NESC contains the basic provisions considered necessary for the safety of employees and the public. Although it is not intended as a design specification, its provisions establish minimum design requirements. PPL Electric Utilities Corp. (PPL) has developed design specifications and safety rules which meet or surpass all requirements specified by the NESC.

Engineering Design Criteria and Parameters

The NESC includes loading requirements and clearances for the design, construction, and operation of power lines. The "loads" on conductors and supporting structures are the mechanical forces that develop from the weight of the conductors, the weight of ice on the conductors, plus wind pressure on the conductors and supporting structures. Loading requirements are the loads on the conductors and structures that are anticipated assuming certain ice and wind conditions. Loading requirements always contain "safety factors" to allow for unknown or unanticipated contingencies. The clearances and loading requirements contained in the NESC were developed to ensure public safety and welfare.

PPL transmission line design standards meet or surpass the NESC standards. For example, the relative order of grades of construction for conductors and supporting structures is B, C, and N; Grade B being the highest. According to the NESC standards, construction Grades B, C, or N may be used for transmission lines (except at crossings of railroad tracks and limited access highways where Grade B construction is specified). However, PPL designs all of its transmission lines for Grade B construction. The use of Grade B design and construction specifies enhancements such as larger-minimum crossarm dimensions, larger-minimum conductor size, and increased safety factors.

Another example is the design parameters utilized to account for ice and wind loadings on the overhead ground wire (OHGW) and power conductors. The NESC standard ice and wind design magnitudes for the PPL territory are 0.5 inch thickness of radial ice combined with four pounds per square foot horizontal wind pressure (equivalent to 40-mile per hour wind velocity). The conductor sags and tensions used in line designs are the result of various ice and wind combinations, depending on the elevation at the line location and line design voltage. The conductor sags and tensions used in the design of all PPL transmission lines are at least 0.5-inch ice combined with eight pounds wind pressure (equivalent to 57 miles per hour wind velocity). This means that PPL lines are designed to operate safely and reliably during inclement weather even more severe than assumed by the NESC. In addition, PPL transmission lines are designed with more clearance to the ground than required by the NESC. The tables below compare PPL and NESC ground clearances for lines of various voltages.

138 kV

<u>Surface Underneath Conductors</u>	<u>Vertical Clearance to Ground</u>	
	<u>NESC Standard</u>	<u>PPL Design</u>
Roads, streets, alleys	21 Ft.	30 Ft.
Other land traversed by vehicles (such as cultivated field, forest, etc.)	21 Ft.	30 Ft.
Spaces accessible to pedestrians only	17 Ft.	30 Ft.
Railroad tracks	31 Ft.	35 Ft.

230 kV

<u>Surface Underneath Conductors</u>	<u>Vertical Clearance to Ground</u>	
	<u>NESC Standard</u>	<u>PPL Design</u>
Roads, streets, alleys	23 Ft.	32 Ft.
Other land traversed by vehicles (such as cultivated field, forest, etc.)	23 Ft.	32 Ft.
Spaces accessible to pedestrians only	19 Ft.	32 Ft.
Railroad tracks	31 Ft.	36 Ft.

500 kV

<u>Surface Underneath Conductors</u>	<u>Vertical Clearance to Ground</u>	
	<u>NESC Standard</u>	<u>PPL Design</u>
Roads, streets, alleys	28 Ft.	53 Ft.
Other land traversed by vehicles (such as cultivated field, forest, etc.)	28 Ft.	53 Ft.
Spaces accessible to pedestrians only	24 Ft.	53 Ft.
Railroad tracks	38 Ft.	53 Ft.

A relay protection system is used to protect the public safety and welfare as well as equipment and the transmission system. Relay protection is installed for all transmission lines to automatically de-energize the line in the unlikely event that the line or supporting structure fails and the line contacts the ground.

Periodic Maintenance Program on All Transmission Lines

To ensure continued public safety and integrity of service, a periodic maintenance and inspection program is implemented for every transmission line. The program is administered through the use of helicopter patrols, with supplemental foot and structure

climbing patrols. A number of helicopter patrols are performed on all lines annually. The two-man helicopter crew flies parallel, to the left, and above the line so that the observer can look for signs of line damage or deterioration and observe clearances between vegetation and conductors. The observations are included in a report that is forwarded to the appropriate department for corrective action.

Foot and structure climbing patrol programs for a transmission line begin approximately three to five years after the line is energized, unless a helicopter patrol reports a need for earlier action. The frequency of foot patrols varies from once every year to once every several years depending on line type and age.

An assigned foot patroller checks right-of-way conditions, including access roads, bridges, pole washouts, tower footers, vegetation height and clearance to conductors, pole and tower deterioration and, with the use of binoculars, insulators, and condition of hardware.

Identified problems are included in a report that is forwarded to the appropriate department for corrective action.

A scheduled line outage is required to perform an overhead patrol because of "hands-on" inspection of hardware. Overhead patrols are conducted on a schedule determined by line age, operating record, and observed general condition. The necessary repairs are also done during the inspection outage.

Personnel Safety Rules

The following are a few of the PPL safety rules that demonstrate the Company's concern for employee safety:

- Work procedures have been developed to allow work to be performed on energized facilities in a safe manner. When lines or apparatus are removed from service to be worked on, the Energy Control Process system is applied. This system provides that a red tag must be physically placed on the control handle of the de-energized equipment. The red tag may be removed only after proper authorization to energize the equipment. Various other tags are used for limited operations and informational purposes.

Employees will not apply or remove a tag or change the status of tagged equipment unless authorized.

- Temporary safety grounds are used on de-energized facilities for employee safety during maintenance, construction, or reconstruction work. Safety grounds are wires connecting the de-energized facility to an electrical ground. If the facility should be energized, the safety grounds will divert the current directly to ground and reduce the likelihood of personal injury. The conductor size and attachment clamps of temporary safety grounds must be capable of conducting anticipated fault currents. Rubber gloves, rubber sleeves, and additional rubber protective equipment are used as required when applying or removing temporary safety grounds to or from the lines or apparatus to be grounded. An approved nonconductive working stick of sufficient length to allow workers to maintain the following required minimum clearances is used to test that the line has been de-energized and to apply temporary safety grounds:

<u>Voltage-kV</u>	<u>Minimum Clearance</u>
138	3'-7"
230	5'-3"
500	11'-3"

Before applying grounds, a test is done to confirm that the line is de-energized. The voltage test device is checked before and after use to assure reliability. When ground pins are used to establish proper ground points, they are driven to a depth of not less than four feet as near vertical as possible.

- Poles or structures are inspected and examined for structural integrity before climbing. If there is any reason to believe that a pole is unsafe, it is stabilized before work is performed. Appropriate safety gear in the form of body belts, safety straps, hard hats, gloves, etc., is worn by linemen during line work activity.

Attachment 5



**MAGNETIC
FIELD
MANAGEMENT**
PPL Electric Utilities
Corporation

ATTACHMENT 5

DECEMBER 2004

TABLE OF CONTENTS

INTRODUCTION	1
DEVELOPMENT OF PPL EU's MAGNETIC FIELD MANAGEMENT PROGRAM.....	6
VARIABLES THAT AFFECT MAGNETIC FIELDS	6
Effect of Phase Current on Magnetic Fields	6
Effect of Conductor Configuration on Magnetic Fields	7
Effect of Distance from the Magnetic Field Source	7
SUMMARY OF PPL EU's MAGNETIC FIELD MANAGEMENT PROGRAM.....	8
MAGNETIC FIELD MANAGEMENT PROGRAM GUIDELINES	9
Overhead Lines	9
New or Rebuilt Transmission Lines	9
Reconductoring or Adding Additional Circuits to Existing Transmission Lines	14
Distribution Lines	14
Underground Transmission Lines	15
CHARTS.....	16

INTRODUCTION

At PPL Electric Utilities Corp. (PPL EU), magnetic field management means investigating and implementing methods at low or no cost to reduce magnetic fields in new or rebuilt transmission and distribution lines. This document explains PPL EU's Magnetic Field Management Program, which is part of PPL EU's larger Electric and Magnetic Fields (EMF) policy.

PPL EU's View

Some people are worried that electric and magnetic fields are harming their health. Others think the scientific research does not show a problem at all, and still others believe there's just too much scientific uncertainty to draw any conclusions.

Here's what we do know now. Various panels of scientists that have reviewed the EMF research generally have drawn two main conclusions. First, the large body of evidence does not demonstrate that EMF are harmful. Second, additional research is recommended to explore questions raised in some studies.

Given these conclusions, PPL EU is taking a reasoned approach in responding to the EMF issue. PPL EU's approach to the EMF issue consists of five elements:

- Providing EMF information to customers and employees
- Providing magnetic field measurements
- Establishing and implementing a magnetic field management program to reduce magnetic fields in new or rebuilt facilities when it can be done at no, or low, cost
- Integrating EMF in the public involvement process that PPL EU undertakes in the siting of transmission lines
- Have supported additional research

EMF Are All Around Us

Electric and magnetic fields occur in nature and in all living things. The earth, for instance, has a magnetic field, which makes the needle on a compass point north.

Electric fields and magnetic fields of a different type also surround every wire that carries electricity. In everyday life, these EMF arise from several basic sources, including power lines, electrical appliances, home and building wiring, other utility lines and cables, and currents flowing on water pipes. Though they often occur together, EMF are made up of two separate components:

Electric Fields

Electric fields are produced by the voltage—or electrical pressure—on a wire. The higher the voltage, the higher the electric field. As long as a wire is energized—has voltage present—an electric field is present (see Figure 1). In other words, an appliance, or an electric power line, doesn't actually have to be turned on to create an electric field. It just has to be plugged in. Electric fields diminish with distance and can be blocked or partially shielded by objects such as trees and houses.

Magnetic Fields

Magnetic fields are created by the current or flow of electricity through a wire. Generally speaking, the higher the current, the higher the magnetic field. Because they only occur when current is flowing, magnetic fields are present only when the power is turned on (see Figure 1). Magnetic fields also diminish with distance, but—unlike electric fields—are not blocked by common objects. In recent years, public and scientific interest has turned toward the magnetic field component of EMF because of some scientific studies regarding these fields.

Figure 1




Figure 2









Magnetic field strengths decrease with distance Magnetic fields are measured in milligauss		Source: "EMF In Your Environment", U.S. Environmental Protection Agency 1992		
		At 6 inches	At 1 foot	At 2 feet
Clothes dryer		2 to 10	* to 3	*
Microwave oven		100 to 300	1 to 200	1 to 30
Toaster		5 to 20	* to 7	*
Power drill		100 to 200	20 to 40	3 to 6
Can opener		500 to 1500	40 to 300	3 to 30
Mixer		30 to 600	5 to 100	* to 10
Hair dryer		1 to 700	* to 70	* to 10
Color television		Data not available	* to 20	* to 8

FIGURE 2 * The magnetic field measurement at this distance from the operating appliance could not be distinguished from background measurements taken before the appliance had been turned on.

Measuring Magnetic Fields

Magnetic fields usually are measured in a unit called a milligauss. Magnetic field levels found in the living areas of homes typically range from less than 1 milligauss to about 4 milligauss according to the U.S. Environmental Protection Agency. They can be higher in some cases. The levels next to appliances can exceed 1,000 milligauss (1 gauss). Figures 2 and 3 show how the strength of the field falls off as you move away from the source, just as the heat of a campfire grows weaker as you walk away from it. For overhead power lines, the strength of the magnetic fields is dependent upon a number of factors that will be explained later. Those factors produce a magnetic field that drops off rapidly as you move away from the power line.

Figure 3

Sample Magnetic Field Levels in Milligauss				
Type of Overhead Power Line	Distance from the line			
	Under the line	50 ft.	100 ft.	200 ft.
220 kV and 500 kV	5-400	5-250	1-75	0.5-20
69 kV and 138 kV	3-80	0.5-2.5	0.1-10	0.1-3
12 kV and below	0.4-20	0.1-1	-	-

The magnetic field values provided in this table represent a general range of values associated with the types of overhead power lines listed and are provided for illustration. There will be circumstances in which there will be magnetic field levels above or below the range of values provided due to variations in such factors as height of the wires, current flow and so on.

DEVELOPMENT OF PPL EU's MAGNETIC FIELD MANAGEMENT PROGRAM

One element of our response to EMF concerns expressed by some of our customers is PPL EU's Magnetic Field Management Program. The program was initiated in March 1991 because PPL EU believes it makes good sense, as a matter of policy, to respond to the concerns expressed by some of our customers and to reduce magnetic fields in new and rebuilt facilities where it can be done with either no-cost or low-cost design changes.

This document updates the original program which has been revised several times since 1991. These guidelines were developed by PPL EU's EMF Working Group.

VARIABLES THAT AFFECT MAGNETIC FIELDS

Magnetic fields from transmission and distribution lines are a function of a number of design variables. The following parameters affect the magnetic field levels produced by transmission and distribution lines:

- Current
- Height of conductors above ground
- Configuration of conductors
- Distance from the line

EFFECT OF PHASE CURRENT ON MAGNETIC FIELDS

At power frequencies (i.e., 60 hertz), the magnetic field level is a function of the current or flow of electricity through a wire. Keeping all other parameters the same, the magnetic field is proportional to the current. Hence, if the current increases by 25 percent, the resulting magnetic field level will increase by 25 percent.

The overall load current on any line varies with the demand for power. It's usually highest during daytime hours and lowest at night. There also are weekly, monthly, seasonal and yearly variations.

The difference in the currents between each phase in a multiphase line also can affect the magnetic field. This difference is called phase unbalance. For a constant load, a statistical analysis of this phase unbalance can be made to determine its effect on the magnetic field. Close to the line, there is very little effect. However, the phase unbalance slows the rate at which the magnetic field decreases with distance from the line.

EFFECT OF CONDUCTOR CONFIGURATION ON MAGNETIC FIELDS

In the transmission and distribution of power, utilities like PPL EU presently use both three-phase and single-phase lines. Each phase on a three-phase power line has either a single conductor or a bundle of two or more conductors. In a three-phase system, the ground-level magnetic field is a result of the fields produced by the currents in each of the phases. Placing the three phases as close together as possible (compaction) creates some field cancellation, and the ground-level magnetic field is reduced. However, appropriate phase separation is required for the reliable operation of the line. In addition, the arrangement of the phases can create some; field cancellation and reduction of the ground-level magnetic field.

EFFECT OF DISTANCE FROM THE MAGNETIC FIELD SOURCE

Magnetic field strength diminishes with the vertical and lateral distances from the magnetic field source. Increasing the height of the conductors above ground is useful for magnetic field reduction at ground level, but may result in increased structure costs and increased aesthetic impact of the structures. Another possible method of increasing the distance to the magnetic field source is to increase the right-of-way requirements. By keeping buildings off increased rights of way, thereby requiring the public to live and work further away from lines, exposure to magnetic fields produced by the lines can be reduced. Increases in right of way are not always practical and may increase costs significantly, however.

SUMMARY OF PPL EU's MAGNETIC FIELD MANAGEMENT PROGRAM

Under its Magnetic Field Management Program, PPL EU has changed the way it builds and rebuilds some of its transmission and distribution lines. These design changes reduce magnetic field levels (assuming balanced circuit loadings and phase currents) by up to 69 percent in most of the company's new transmission lines. These guidelines now are being applied to new and reconstructed transmission facilities, based on this program.

The distribution component of the program focuses on 12 kV lines, the company's standard distribution voltage. It concentrates on the three-phase, primary 12 kV lines, since these are the most heavily loaded facilities and often are located in densely populated areas. The guidelines in this program are being applied to these three-phase, primary 12 kV lines.

A maximum 3-5 percent change in estimated cost was used as the limit for the guidelines since this value is consistent with low cost, is within estimating accuracy and is likely to have little impact on overall line costs.

The magnetic field calculations used in this document for the design of PPL EU's overall magnetic field management plan assume balanced load conditions among the phases and a fixed level of current, not necessarily representative of specific transmission or distribution lines. These levels were calculated using the Electric Power Research Institute's ENVIRO computer program. Under actual operating conditions, the magnetic field levels that result may vary due to such things as actual load per circuit, overall current on each phase conductor and the electrical configuration and operation of each line.

MAGNETIC FIELD MANAGEMENT PROGRAM GUIDELINES

The guidelines for magnetic field management are noted below, with discussion points for each.

OVERHEAD LINES

NEW OR REBUILT TRANSMISSION LINES

1. **Balance transmission circuit loads and phase currents as much as possible.**
 - PPL EU should continue to make every effort to balance loadings between the two circuits of a double circuit line when planning new or rebuilt facilities to maximize the effects of reverse phasing.
 - PPL EU should continue the practice of balancing single-phase loads across the three phases of the distribution system. (Unbalanced phase currents on the distribution system are reflected through to the transmission system.)
 - Unbalanced phase currents result in higher magnetic fields that do not drop off as quickly with distance as do the fields resulting from balanced phase currents.
 - For a 5 percent phase current unbalance, the magnetic field 50 feet from the centerline of a single circuit 138 kV line could be more than twice the value than if the same line had balanced phase circuits.
 - Balanced phase currents on each three-phase distribution circuit also reduce magnetic fields from the distribution circuits themselves. In addition, they reduce magnetic fields on the transmission system from which the distribution system circuits are supplied and connected through substations.
 - Apart from magnetic field considerations, balanced phase currents on each three-phase distribution circuit also reduce line losses and improve the system voltage.

2. **Continue with the present practice of using long-span construction as the PPL EU 138/69 kV standard**

- Structure designs for short-span and long-span construction are illustrated on Charts I and II, respectively.
 - Short-span design does not significantly reduce magnetic fields when compared to long-span design even though it is more compact than long-span design. Comparison of the magnetic field values from Chart III indicates essentially the same values. Therefore, short-span design should not be used solely to reduce magnetic fields.
 - PPL EU will continue to use long-span construction for 138/69 kV double-circuit lines and for single-circuit/future-double-circuit lines.
 - For single-circuit/future-double-circuit lines, PPL EU will continue to install two conductors on the top positions and one in the middle position as shown in Chart IV.
 - This arrangement minimizes magnetic fields as shown in Chart V by placing the three initial conductors higher on the structure, which increases the ground clearances, and by placing the conductors in a triangular configuration.

3. **Compact design structures are not a low-cost alternative and should be used for magnetic field reduction only in special applications.**

Chart VI illustrates the compact design structure.

- The compact design increases the initial installation costs by 79 percent when compared to the long-span design but reduces the magnetic field from 9 mG to 3 mG (about 67 percent) at the edge of the 100-foot-wide right of way as shown on Chart III.

4. **Reverse phase new or rebuilt double-circuit transmission lines for all voltage levels.**

- Reverse phasing was adopted by PPL EU in March 1991 for double-circuit 138/69 kV transmission lines and in April 1992 for all other double circuit transmission lines. Reverse phasing is shown in Chart VII. Reverse phasing will reduce the magnetic fields when the current flow on both circuits is in the same

direction. Calculated values contained here are based on balanced and equal phase currents on both circuits.

- Reverse phasing reduces the magnetic field of a double circuit 138 kV single pole transmission line from 29 mG to 9 mG (about 69 percent) at the edge of the 100-foot-wide right of way as shown on Chart III.
- Reverse phasing reduces the magnetic field of a double circuit 230 kV single pole transmission line from 49 mG to 16 mG (about 67 percent) at the edge of the 150-foot-wide right of way as shown on Chart VIII.
- Reverse phasing reduces the magnetic field of a double-circuit 500 kV single pole transmission line from 37 mG to 21 mG (about 43 percent) at the edge of the 200-foot-wide right of way as shown on Chart IX.
- When new or rebuilt double-circuit lines require tapping existing double-circuit lines, PPL EU will review the existing lines to determine if reverse phasing can be provided at low cost.
- Computer modeling is required to develop the optimum phasing and overall conductor arrangements for lines added to, or rebuilt in, multiple-line corridors.
 - Merely adding a reverse-phase double-circuit line to an existing transmission line corridor or reverse phasing a rebuilt line in the multiple-line corridor will not necessarily produce lower magnetic field levels at the edge of the corridor right of way.
 - The corridor must be computer modeled with all the lines, existing phase conductor locations and currents. Then, magnetic field calculations must be made varying the phase arrangements of the new or reconstructed line to determine the appropriate phasing arrangement.
 - Current flow direction on a line also must be considered. For example, a reverse-phased line should have the current flowing in the same direction on both circuits. If the current flow is in the opposite direction for one circuit, reverse phasing will not produce the lowest magnetic field and another phase arrangement that produces lower fields may need to be utilized.

5. Increase the minimum ground clearance for all new transmission lines.

138/69 kV Transmission Lines

- Increasing the minimum line design ground clearance from 25 feet to 30 feet may add up to about 5 percent to the installed cost of a new double-circuit single pole 138/69 kV line. For a given project, such cost may be substantially less, however. In fact, PPL EU frequently uses higher-than-minimum ground clearances due to such features as road crossings, line crossings and site-specific terrain. With long-span reverse-phase design, the magnetic field is reduced from 9 mG to 7 mG (about 22 percent) at the edge of a 100-foot-wide right of way as shown in Chart X.
 - In the actual design of transmission lines to include higher minimum ground clearances, there may be limited segments (such as highway crossings, severe slopes and transmission line crossing locations) where National Electrical Safety Code (NESC) minimum ground clearances may need to be used. The NESC minimum ground clearances are less than the increased ground clearance discussed previously.

230 kV Transmission Lines

- Increasing the minimum line design ground clearances from 27 feet to 32 feet may add up to about 5 percent to the cost of a single-circuit single-pole line (current standard). For a given project, such cost may be substantially less, however. In fact, PPL EU frequently uses higher-than-minimum ground clearances due to such features as road crossings, line crossings and site-specific terrain. By increasing the clearances, the magnetic field is reduced from 30 mG to 28 mG (about 7 percent) at the edge of a 150-foot-wide right of way.
- Increasing clearances from 27 feet to 32 feet could theoretically add up to about 2.8 percent to the cost of a double-circuit single-pole line (current standard) and reduce the magnetic field of a reverse-phase line from 16 mG to 15 mG (about 6 percent) at the edge of a 150-foot-wide right of way. Chart XI is a summary of this data.
- Studies are required for each new 230 kV line to determine optimum structure types, ground clearances, configurations and designs to reduce field levels. Such

studies could include analysis of reduction measures such as additional minimum ground clearances, increasing conductor tensions, using reduced phase spacing (a "Delta" configuration on a single-circuit line), installing the second circuit initially, and/or adding a second set of conductors that are reverse phased and operated in parallel with the first set (bundled/split phase).

500 kV Transmission Lines

- Increasing ground clearances from 33 feet to 53 feet may add up to about 4.5 percent to the cost of a single-circuit "H-frame" line (current standard). For a given project, such cost may be substantially less, however. In fact, PPL EU frequently uses higher-than-minimum ground clearances due to such features as road crossings, line crossings and site-specific terrain. By increasing the clearances, the magnetic field is reduced from 42 mG to 35 mG (about 17 percent) at the edge of a 200-foot-wide right of way.
- Increasing ground clearances from 33 feet to 53 feet could theoretically add up to 2.8 percent to the cost of a double-circuit "H-frame" line (current standard) and reduces the magnetic field of a reverse-phase line from 21 mG to 16 mG (about 24 percent) at the edge of a 200-foot-wide right of way. Chart XII is a summary of this data.
- Studies are required for each new 500 kV line to determine optimum structure types, ground clearances, configurations and designs to reduce field levels. Such studies could include analysis of reduction measures such as additional minimum ground clearances, increasing conductor tensions, using reduced-phase spacing (a "Delta" configuration on a single circuit line), installing the second circuit initially, and/or adding a second set of conductors that are reverse phased and operated in parallel with the first set (bundled/split phase).

RECONDUCTORING OR ADDING ADDITIONAL CIRCUITS TO EXISTING TRANSMISSION LINES

When reconductoring or adding additional circuits to existing transmission lines, PPL EU will evaluate low-cost or no-cost options for magnetic field management on a case-by-case basis.

When reconductoring existing transmission lines or adding additional circuits, low-cost alternatives may not exist; however, the following steps will be taken:

- For a single-circuit line, the use of a Delta arrangement or other modifications on the existing structure, with reduced-phase spacing, will be evaluated.
- For double-circuit lines, application of reverse phasing may reduce the magnetic field under the line and within the right of way and will be evaluated.
- For single- and double-circuit lines, evaluate using higher conductor tensions that can increase the minimum line design ground clearance.

DISTRIBUTION LINES

At the 12 kV distribution level, new main three-phase lines will continue to be constructed with five feet of additional ground clearance.


- Main lines are the most heavily loaded sections of a distribution line and therefore have the highest magnetic fields associated with them.
- Increasing the ground clearance by five feet reduces the magnetic field under the line from 14 mG to 11 mG using the standard eight-foot crossarm design. These values are based on increasing pole heights from 45 feet to 50 feet and a typical operating current of 300 amps per phase.
- Chart XIII is a summary of this data. Increasing ground clearance by five feet could theoretically add about 5 percent to the cost of a typical distribution line.

UNDERGROUND TRANSMISSION LINES

Underground transmission lines are required due to environmental or land use factors or restrictions on available clearances, PPL EU will evaluate options for magnetic field management techniques on a case-by-case basis.


- The phase arrangement that produces the lowest field will be determined.
- The depth of burial of the line will be determined considering the cost of excavation and the location of other buried utilities in the area.
- The use of steel pipe ferromagnetic shielding that reduces magnetic fields will be evaluated.

Short-Span Construction



- **More compact design**
- **Should not be used solely to reduce magnetic fields**
- **Typical conductor data:**
 - 1 3/8" HS steel overhead ground wire - 7.3 feet sag
 - 6-556.5 KCMIL 24/7 ACSR power conductors - (PARAKEET) 10.0 feet sag
 - Average span - 400 feet

Long-Span Construction Remains PPL EU 138 kV Standard




- Lower cost alternative
- Reduces magnetic fields due to higher structures
- Typical conductor data:
 - 1 3/8" HS steel overhead ground wire - 17.3 feet sag
 - 6-556.5 KCMIL 24/7 ACSR power conductors - (PARAKEET) 23.0 feet sag
 - Average span - 600 feet

**138/69 kV REVERSE-PHASE TRANSMISSION LINES
CALCULATED MAGNETIC FIELDS AT 400 AMPERES**


TYPE CONSTRUCTION	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
SHORT SPAN (CHART I)	30
SHORT SPAN (REVERSE PHASE)	8
LONG SPAN (CHART II)	29
LONG SPAN (REVERSE PHASE)	9
COMPACT (CHART VI)	14
COMPACT (REVERSE PHASE)	3

The edge of right of way is 50 feet from the line centerline.
The 400 ampere phase current is balanced between phases.
Calculations are based on a minimum ground clearance of 25 feet.
LONG SPAN, SHORT SPAN and COMPACT are double-circuit lines.


Typical Single-Circuit Structure Designs



Top/Middle



Vertical



Top/Middle/Bottom


——— initial single circuit
- - - - future second circuit

**138/69 kV SINGLE CIRCUIT TRANSMISSION LINES
CALCULATED MAGNETIC FIELDS AT 400 AMPERES**

TYPE CONSTRUCTION	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
TOP/MIDDLE/BOTTOM	20
VERTICAL	17
TOP/MIDDLE	12


The edge of right of way is 50 feet from the line centerline.
The 400 ampere phase current is balanced between phases.
Calculations are based on a minimum ground clearance of 25 feet.

Compact Design Structure



- Minimize magnetic fields due to compact design
- Not a low-cost alternative
- Typical conductor data:
 - 1 3/8" HS steel overhead ground wire - 9.0 feet sag
 - 6-556.5 KCMIL 24/7 ACSR power conductors - (PARAKEET) 9.0 feet sag
 - Average span - 300 feet

Reverse Phasing of Double-Circuit Transmission Lines



From: $\longrightarrow \longrightarrow \longrightarrow \longrightarrow$ To:

Reverse phasing also can be one of the following phase arrangements:

A	B		B	A		B	C		C	A		C	B
C	C	or	C	C	or	A	A	or	B	B	or	A	A
B	A		A	B		C	B		A	C		B	C

**230 kV REVERSE-PHASE TRANSMISSION LINES
CALCULATED MAGNETIC FIELDS AT 800 AMPERES**

TYPE CONSTRUCTION	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
DOUBLE CIRCUIT POLE	49
DOUBLE CIRCUIT POLE (REVERSE-PHASE)	16

The edge of right of way is 75 feet from the line centerline.
The 800 ampere phase current is balanced between phases.
Calculations are based on a minimum ground clearance of 27 feet.

**500 kV REVERSE-PHASE TRANSMISSION LINES
CALCULATED MAGNETIC FIELDS AT 1100 AMPERES**

TYPE CONSTRUCTION	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
DOUBLE CIRCUIT POLE	37
DOUBLE CIRCUIT POLE (REVERSE PHASE)	21

The edge of right of way is 100 feet from the line centerline.
The 1,100 ampere phase current is balanced between phases.
Calculations are based on a minimum ground clearance of 33 feet.

**INCREASED 138/69 kV MINIMUM GROUND CLEARANCE
CALCULATED MAGNETIC FIELDS AT 400 AMPERES**

TYPE CONSTRUCTION	MINIMUM GROUND CLEARANCE FEET	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
SINGLE CIRCUIT TOP/MIDDLE	25	12
SINGLE CIRCUIT TOP/MIDDLE	30	10
LONG SPAN	25	29
LONG SPAN	30	26
LONG SPAN (REVERSE PHASE)	25	9
LONG SPAN (REVERSE PHASE)	30	7

The edge of right of way is 50 feet from the line centerline.
The 400 ampere phase current is balanced between phases.

**INCREASED 230 KV MINIMUM GROUND CLEARANCE
CALCULATED MAGNETIC FIELDS AT 800 AMPERES**

TYPE CONSTRUCTION	MINIMUM GROUND CLEARANCE FEET	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
SINGLE CIRCUIT TOP/MIDDLE	27	30
SINGLE CIRCUIT TOP/MIDDLE	32	28
DOUBLE CIRCUIT POLE	27	49
DOUBLE CIRCUIT POLE	32	46
DOUBLE CIRCUIT POLE (REVERSE PHASE)	27	16
DOUBLE CIRCUIT POLE (REVERSE PHASE)	32	15

The edge of right of way is 75 feet from the line centerline.
The 800 ampere phase current is balanced between phases.

**INCREASED 500 kV MINIMUM GROUND CLEARANCE
CALCULATED MAGNETIC FIELDS AT 1,100 AMPERES**

TYPE CONSTRUCTION	MINIMUM GROUND CLEARANCE FEET	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
SINGLE CIRCUIT "H" STRUCTURE	33	42
SINGLE CIRCUIT "H" STRUCTURE	53	35
DOUBLE CIRCUIT POLE	33	37
DOUBLE CIRCUIT POLE	53	31
DOUBLE CIRCUIT POLE (REVERSE PHASE)	33	21
DOUBLE CIRCUIT POLE (REVERSE PHASE)	53	16

The edge of right of way is 100 feet from the line centerline.
The 1,100 ampere phase current is balanced between phases.

**12 kV DISTRIBUTION LINES
CALCULATED MAGNETIC FIELDS AT 300 AMPERES**

TYPE CONSTRUCTION	POLE HEIGHT FEET	MAGNETIC FIELD IN MILLIGAUSS*	
		AT CENTERLINE	AT 30 FEET FROM CENTERLINE
STANDARD CROSSARM	45	14	7
STANDARD CROSSARM	50	11	6

* Field level under the line at mid-span based on 300 amps, balanced loading, one meter above ground level.

Attachment 6

ATTACHMENT 6

LIST OF INVOLVED GOVERNMENTAL AGENCIES, MUNICIPALITIES AND OTHER PUBLIC ENTITIES RECEIVING APPLICATIONS

1. Pennsylvania Historical and Museum Commission
Bureau for Historic Preservation
Commonwealth Keystone Building, Second Floor
400 North Street
Harrisburg, Pennsylvania 17120-0053
Attn: Mr. Douglas C. McLearn, Chief
2. Pennsylvania Department of Transportation
Commonwealth Keystone Building
400 North Street, 8th Floor
Harrisburg, Pennsylvania 17120
Attn: The Honorable Allen D. Biehler, P.E., Secretary
3. Department of Environmental Protection
P.O. Box 2063
Market Street State Office Building
Harrisburg, Pennsylvania 17105-2063
Attn: Office of Field Operations
4. Northampton County
Northampton County Government Center
669 Washington Street
Easton, PA 18042
Attn: Mr. John Stoffa, County Executive
5. Lehigh Valley Planning Commission
961 Marcon Boulevard, Suite 301
Allentown, PA 18109
Attn: Mr. Michael Kaiser, AICP, Executive Director
6. Moore Township Board of Supervisors
2491 Community Drive
Bath, PA 18014
Attn: Mr. Maynard Campbell, Chair
7. Moore Township Planning Commission
2491 Community Drive
Bath, PA 18014
Attn: Mr. Jason Harhart, Planning Director and Zoning Officer