

Richard G. Webster, Jr.

Director

Rates and Regulatory Affairs

Telephone 215.841.4000 ext 5777 Fax 215.841.6208 www.exeloncorp.com dick.webster@exeloncorp.com

PECO Energy Company 2301 Market Street, S15 Philadelphia, PA 19103

Mail To: 8699 Philadelphia, PA 19101-8699

January 31, 2011

RECEIVED

JAN 31 2011

PA PUBLIC UTILITY COMMISSION SECRETARY'S BUREAU

FedEx

Rosemary Chiavetta, Secretary Pennsylvania Public Utility Commission Commonwealth Keystone Building 400 North Street Second Floor Harrisburg, Pennsylvania 17120

Re: PUC Docket No. L-00030161

Rulemaking Re Amending Electric Service Reliability Regulations at

52 Pa. Code Chapter 57

Dear Secretary Chiavetta:

In accordance with Electric Service Reliability Regulations at 52 Pa. Code Chapter 57, enclosed are an original and six copies of PECO's 2010 Quarterly Reliability Report for the period ending December 31, 2010.

Because portions of the report contain sensitive and proprietary information, PECO is filing two versions of the report, one public and one proprietary. PECO requests that the proprietary report, which has been separated and clearly marked with a "Confidential and Proprietary" header on each page, be kept confidential, pursuant to Commission Order of March 20, 2006.

If you have questions regarding this matter, please call me at 215-841-5777.

Sincerely,

cc: Office of Consumer Advocate


Received

Office of Small Business Advocate

enclosures

SAN/amm

PECO Energy Company Quarterly Reliability Report For Period Ending December 31, 2010



RECEIVED

JAN 31 2011

PA PUBLIC UTILITY COMMISSION SECRETARY'S BUREAU

February 1, 2011

PECO Energy ("PECO")

Quarterly Reliability Report for the Period Ending December 31, 2010 filed with the Pennsylvania Public Utility Commission.

<u>Submitted per Rulemaking Re: Amending Electric Service, Docket No. L-00030161 Reliability Regulations</u> at 52 Pa.Code Chapter 57

Section 57.195(e)(1) "A description of each major event that occurred during the preceding quarter, including the time and duration of the event, the number of customers affected, the cause of the event and any modified procedures adopted in order to avoid or minimize the impact of similar events in the future."

No Major events occurred during the 4th quarter.

Section 57.195(e)(2) "Rolling 12-month reliability index values (SAIFI, CAIDI, SAIDI, and if available, MAIFI) for the EDC's service territory for the preceding quarter. The report shall include the data used in calculating the indices, namely the average number of customers served, the number of sustained customer interruptions, the number of customers affected, and the customer minutes of interruption. If MAIFI values are provided, the report shall also include the number of customer momentary interruptions."

PECO Customers	Sustained Customer Interruptions	Sustained Customer Hours	Momentary Customer Interruptions	Sustained Customer Minutes	SAIFI	CAIDI	SAIDI	MAIFI
1,679,193	1,823,663	3,836,377	1,170,659	230,182,628	1.09	126	137	0.70

^{*}Data reflects 12 months ending 12/31/2010

PECO Benchmarks and Rolling 12-Month Standards								
	SAIFI	CAIDI	SAIDI	MAIFI				
Benchmark	1.23	112	138	N/A				
Rolling 12-Month Standard	1.48	134	198	N/A				

SAIFI and SAIDI are currently below the standard and benchmark, CAIDI is above the benchmark but below the standard established on May 7, 2004. No benchmark or standard was established for MAIFI.

Section 57.195(e)(3) "Rolling 12-month reliability index values (SAIFI, CAIDI, SAIDI, and if available, MAIFI) and other pertinent information such as customers served, number of interruptions, customer minutes interrupted, number of lockouts, and so forth, for the worst performing 5% of the circuits in the system. An explanation of how the EDC defines its worst performing circuits shall be included."

PECO's worst performing 5% circuits for 2010 were selected based on a weighted score combining customer interruptions, customer hours, SAIFI and SAIDI, due to outages on each circuit in a 12 month period. This measure is oriented toward contributions to system SAIFI, SAIDI and CAIDI, and local areas with high outage frequency or duration. In addition, circuits with a history of repeat appearance on worst performing lists were selectively included in the 5% list.

Worst circuits and the rolling 12-month reliability index values requested are shown in Appendix A.

Section 57.195(e)(4) "Specific remedial efforts taken and planned for the worst performing 5% of the circuits as identified in paragraph (3)."

Remedial efforts taken or planned to date for PECO's worst performing 5% of circuits are shown in Appendix B.

Section 57.195(e)(5) "A Rolling 12-month breakdown and analysis of outage causes during the preceding guarter, including the number and percentage of service outages, the number of customers interrupted, and customer interruption minutes categorized by outage cause such as equipment failure, animal contact, tree related, and so forth. Proposed solutions to identified service problems shall be included."

	12 Months	Ending Dece	ember 31, 2010)		
Cause	Service Outages	% of Service Outages Customer Interruptions		% of Customer Interruptions	Customer Minutes	
Animal	1,079	8.1%	33,488	1.8%	2,559,856	
Contact/Dig-In	156	1.2%	18,356	1.0%	1,314,627	
Equipment Failure	4,839	36.5%	725,048	39.7%	76,086,251	
Lightning	468	3.5%	62,786	3.4%	6,629,170	
Other	2,338	17.6%	220,583	12.1%	21,196,186	
T&S	30	0.2%	71,682	3.9%	3,356,130	
Unknown	593	4.5%	75,105	4.1%	8,198,872	
Vegetation-Broken/Uprooted	2,072	15.6%	394,457	21.6%	71,854,004	
Vegetation-Ingrowth	1,348	10.2%	137,102	7.5%	30,792,188	
Vehicles	326	2.5%	86,506	4.7%	8,218,454	

^{*}The data supplied is the number of interrupted customers for each interruption event summed for all events, also known as customer interruptions. A customer interrupted by three separate trouble cases represents three customer interruptions, but only one customer interrupted.

The largest contributors to customer interruptions were equipment failure and tree-related interruptions. The leading groups within the equipment failure category were aerial equipment and underground equipment. Most customer interruptions caused by trees came from broken branches and tree trunks or uprooted trees (74% of vegetation outages), as opposed to ingrowth (26% of vegetation outages). PECO has continued with the significant supplemental vegetation management program it began in 2006 to prune or remove trees between cycles of it's regularly scheduled vegetation management program.

Section 57.195(e)(6). "Quarterly and year to date information on progress toward meeting transmission and distribution inspection and maintenance goals /objectives" (For First, Second and Third Quarter reports only)."

Data not required for 4th quarter report

Section 57.195(e)(7). "Quarterly and year-to-date information on budgeted versus actual transmission and distribution operation and maintenance expenditures in total and detailed by the EDC'S own functional account code or FERC account code as available." (For first, second and third quarter reports only.)

Data not required for 4th quarter report

Section 57.195(e)(8). "Quarterly and year-to-date information on budgeted versus actual transmission and distribution capital expenditures in total and detailed by the EDC'S own functional account code or FERC account code as available." (For first, second and third quarter reports only.)

Data not required for 4th quarter report

Section 57.195(e)(9). "Dedicated staffing levels for transmission and distribution operation and maintenance at the end of the quarter, in total and by specific category (e.g., lineman, technician and electrician)."

PECO's full-time trade staff as of December 31, 2010 was as follows:

Aerial Lineman	385			
Underground Lineman (Include UTS)	54			
Transmission / Substation Mechanics, Operators	107			
Energy Technicians	99			
Aerial Foreman	62			
Underground Foreman (Includes UTS)	18			
Transmission / Substation Foreman	30			
Total	755			

Contact Persons:

J. Coffman
Director, Engineering
(215) 841-4201
jearl.coffman@peco-energy.com

Dick Webster
Director, Rates and Regulatory
(215) 841-5777
dick.webster@peco-energy.com

Appendix A
Rolling 12- month reliability index values for 5% worst performing circuits

CIRCUIT	CUSTOMERS ON CIRCUIT	12 Month Rolling Gircuit SAIFI		12 Month Rollingt Circuit SAIDI	12"Month Rolling Gircuit MAIFI	42 Month Rolling Customers Interrupted	12 Month Rölling Customer Hours	Momentary
KERBAUGH_005	1435	0.15	128	19	0.00	217	463	0
KERBAUGH_009	984	0.06	697	45	0.00	63	732	0
LANDENBERG_000	551	4.61	55	254	0.40	2542	2330	222
LENAPE_341	981	2.41	255	613	0.13	2361	10026	128
LENAPE_344	1823	3.11	55	171	4.84	5668	5201	8830
LENAPE_351	1611	5.42	158	859	9.66	8734	23061	15564
LINE 1099	2259	0.76	148	112	0.44	1708	4201	986
LINE_1100CL	1405	3.27	89	292	0.66	4599	6832	924
LINE_2200CR	763	2.96	123	364	0.57	2255	4628	434
LINE_2241	1456	0.56	104	58	0.00	813	1408	0
LINE 2445	489	1.49	168	250	0.00	728	2039	0
LINE_300CR	2314	0.79	117	92	1.67	1833	3565	3867
	350	2.04	92	187	0.00	713	1093	0
LINE_4600PB	6	3.00	422	1266	0.00	18	1093	0
LINE_518	216		55	107	0.44	416		0 96
LINE_7200WH	· 	1.93		115	0.00		385	
LINE_734	115	1.13	102			130	221	0
LINFIELD_000	857	0.53	115	60	0.00	450	863	4
LINTON_342	2901	1.45	197	284	0.01	4194	13747	21
LYNDELL_000	202	1.48	239	354	2.00	299	1193	404
MACDADE_137	2070	1.04	144	150	0.46	2161	5191	949
MALL_058	59	4.00	240 166	958	0.00	236	942	0
MALVERN_001	728	2.96		492 948	1.49	2153	5971	1082 893
MARKLEY_133	1260 727	2.98	318 118	281	2.00	3754 1736	19915 3410	1455
MARPLE_138	526	2.95	154	456	1.00	1553	3996	526
MARSHALLTON_002 MEDIA_011	578	1.48	77	113	0.99	853	1092	573
MONROE_004	415	$\frac{1.48}{2.81}$	104	294	3.02	1168	2033	1255
MONROE 005	552	0.36	238	84	4.00	196	776	2208
NEWLINVILLE 343	2459	5.13	67	346	4.29	12605	14161	10541
NEWLINVILLE_344	2649	0.98	91	89	4.64	2597	3924	12288
NEWLINVILLE_351	1321	1.20	99	119	1.34	1587	2616	1766
NEWLINVILLE 353	2341	2.30	59	135	2.84	5384	5275	6648
NORRISTOWN 009	994	3.39	88	300	0.00	3368	4966	1
NORTH WALES 344	1706	0.87	183	160	0.39	1492	4553	673
OLIVE 001	971	0.97	159	154	1.00	944	2498	971
OLIVE_004	461	0.18	245	44	2.01	83	340	926
PARKESBURG 001	510	2.11	87	182	2.00	1074	1549	1018
PEACH_BOTTOM_361	256	6.95	175	1217	0.39	1780	5193	99
PENCOYD_133	1262	1.03	271	279	2.00	1301	5871	2526
PERKIOMEN_354	2942	1.28	93	120	0.77	3767	5860	2264
PLYMOUTH_148	1750	0.76	80	61	0.45	1327	1772	790
MONROE_004	415	2.81	104	294	3.02	1168	2033	1255
PULASKI_135	2915	2.03	38	76	0.00	5926	3713	0
PULASKI_136	2300	1.10	33	37	0.38	2534	1404	872
RADNOR_131	33	4.76	159	756	3.91	157	416	129
RICHMOND_132	1846	2.40	51	121	0.71	4433	3737	1314
RICHMOND_137	2291	$\frac{-2.40}{0.52}$	35	18	0.66	1192	690	1514

		12 Month	12 Month	12 Month Rolling				
,]'	Rolling	Rolling	Rolling	Rolling	Rolling	Rolling	Momentary
ľ.	CUSTOMERS	Circuit	Circuit	Circuit	Circuit	Customers	Customer	Customers
CIRCUIT	ONCIRCUIT	SAIFI	CAIDI	SAIDI	MAIFI	Interrupted	Hours	Interrupted
RUSHLAND_000	430	6.14	331	2031	1.03	2640	14559	444
SADSBURY_000	631	1.50	61	92	3.97	949	967	2504
SAVILLE_134	2886	0.38	99	38	0.14	1100	1809	394
SOLEBURY_001	500	3.12	337	1050	3.17	1559	8750	1585
SPROUL_001	497	1.47	113	167	0.00	732	1381	2
STREET_000	335	4.06	123	500	0.99	1361	2789	333
SUNNYBURN_002	347	6.35	166	1055	0.00	2203	6101	1
SUSQUEHANNA_341*	0	0.00	0	0	0.00	0	0	0
TABOR_136	3486	0.13	384	50	0.00	454	2903	0
TOKENA_002	238	3.45	86	296	1.63	822	1173	388
TREVOSE_138	1210	2.18	88	192	0.00	2632	3868	0
TROOPER_001	554	2.74	395	1084	0.00	1520	10005	1
TURK_000	601	2.03	260	528	0.00	1222	5287	0
WAGONTOWN_000	597	2.05	40	82	8.02	1226	818	4788
WALLACE_000	231	2.36	136	320	1.44	545	1231	332
WARMINSTER_142	1848	2.92	61	178	0.31	5397	5475	582
WAWA_000	401	2.25	240	539	0.00	903	3604	0
WAYNE_134	676	5.88	76	449	1.94	3972	5062	1311
WHITEMARSH_133	1291	3.50	154	539	1.98	4519	11604	2562
WICKER_001	380	6.61	101	669	4.06	2510	4234	1543
WILLOWDALE_002	469	2.19	372	817	0.04	1029	6385	17
WORTH_000	343	0.14	226	32	0.99	49	185	339

The data supplied is the number of interrupted customers for each interruption event summed for all events, also known as customer interruptions. If a customer is interrupted by three separate trouble cases, they represent three customer interruptions, but only one customer interrupted.

^{*}Note: All customers in Pennsylvania formerly supplied by the Susquehanna 341 circuit have been transferred to a new PECO circuit. Susquehanna 341 continues to supply customers in Maryland.

Appendix B

Remedial efforts taken and planned for 5% worst performing circuits as of 12/31/10

AVONDALE_001

Chester County

Completed:

Inspected selected areas of circuit for vegetation issues and corrected as needed

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspect/ Test recloser operation

Upgraded fuses

Planned:

Remedial efforts completed

BALA 045

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Installed additional fusing

Replaced lightning protection

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and corrected as needed

Planned:

Remedial efforts completed

BELLEVUE_133

Bucks County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Installed aerial cable

Installed (2) 3 phase reclosers

Upgraded secondary wire

Installed compact single phase recloser

Installed additional lightning protection

Planned:

Remedial efforts completed

BELLEVUE 134

Bucks County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Replaced URD cable

Planned:

Remedial efforts completed

BETHAYRES_002

Montgomery County

Completed

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Upgraded secondary wires

Planned:

BLUE_GRASS_144

Philadelphia County

Completed

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Installed additional fusing

Upgraded cable insulation

Completed regularly schedule tree clearance

Completed reliability corrective work orders

Planned

Remedial efforts completed

BRISTOL_012

Bucks County

Completed

Inspected selected areas of circuit for vegetation issues and corrected as needed

Inspected circuit visually and with thermographic camera

Upgraded secondary wires

Completed reliability corrective work orders

Installed (2) 3 phase reclosers

Planned

Remedial efforts completed

BRYAN 001

York County

Completed

Inspected selected areas of circuit for vegetation issues and corrected as needed

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Completed regularly schedule tree clearance

Installed additional fuse

Installed 1 phase recloser

Installed 3 phase recloser

Planned

Remedial efforts completed

BYBERRY 162

Bucks County

Completed

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Installed addition fuses

Installed animal protection

Installed additional lightning protection

Upgraded fuses

Planned

CHALFONT_001

Bucks County

Completed

Upgraded transformer

Installed additional lightning protection

Inspected selected areas of circuit for vegetation issues and corrected as needed

Replaced underground cable

Completed reliability corrective work orders

Planned

Remedial efforts completed

CHANDLER_000

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Inspected recloser operation

Upgraded lightning protection

Planned:

Remedial efforts completed

CHARLTON _000

Chester County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Installed lightning protection

Inspected selected areas of circuit for vegetation issues and corrected as needed

Planned:

Remedial efforts completed

CHESTNUT_HILL_031

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Installed additional fusing

Planned:

Remedial efforts completed

CHICHESTER_134

Delaware County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Installed additional fusing

Installed additional lightning protection

Inspected selected areas of circuit for vegetation issues and corrected as needed

Planned:

CLAY_342

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Installed additional fuses

Inspected selected areas of circuit for vegetation issues and corrected as needed

Installed lightning protection

Planned:

Remedial efforts completed.

COLWYN_133

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Completed reliability corrective work orders

Upgraded lightning protection

Upgraded wildlife protection

Inspect /Test recloser operation

Planned:

Remedial efforts completed.

CONCORD_351

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Install 3 phase recloser

Inspect/Test recloser operation

Install faulted circuit Indicators

Planned:

Remedial efforts completed.

CRESCENTVILLE_136

Philadelphia County

Completed

Installed additional fusing

Upgraded lightning protection

Inspected circuit visually and with thermographic camera

Completed regularly scheduled tree clearance

Completed reliability corrective work orders

Installed 2-3 phase reclosers

Installed additional fusing

Planned

CROSS_000

Bucks County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed (2) 3 phase reclosers

Planned:

Remedial efforts completed

CROYDON_132

Bucks County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed.

CRUM_LYNNE_138

Delaware County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Upgraded animal protection

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional fuses

Planned:

Remedial efforts completed

DALEVILLE_342

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed 2- three phase reclosers

Planned:

Remedial efforts completed

DAVISVILLE_003

Montgomery County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Replaced switch

Planned:

DUTTON_001

Delaware County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Upgraded transformer

Installed additional lightning protection

Installed additional fuses

Planned

Remedial efforts completed

ELKINS_PARK 011

Montgomery County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Tested/ Inspected recloser operation

Upgraded secondary wire

Completed regularly schedule tree clearance

Inspected selected areas of circuit for vegetation issues and corrected as needed

Installed 2-three phase reclosers

Planned:

Remedial efforts completed

EMILIE_132

Bucks County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Completed reliability corrective work orders

Installed wildlife protection

Installed additional fusing

Installed compact single phase recloser

Installed 3 phase recloser

Planned:

Remedial efforts completed

EMILIE_133

Bucks County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Upgraded secondary wire

Installed lightning protection

Installed 3 phase recloser and tie

Planned:

FIN 001

York County

Completed

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Upgraded lightning protection

Performed regularly schedule tree clearance

Install 3 phase recloser on supply line

Inspected selected areas of circuit for vegetation issues and corrected as needed

Planned

Remedial efforts completed.

FLINT_144

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Performed regularly scheduled tree clearance

Upgraded fuse coordination

Installed additional fuses

Upgraded transformer

Inspected selected areas of circuit for vegetation issues and corrected as needed

Planned:

Remedial efforts completed

FOX_CHASE_133

Philadelphia County

Completed:

Completed regularly scheduled tree clearance.

Performed regularly scheduled tree clearance

Installed additional fuses

Inspected selected areas of circuit for vegetation issues and corrected as needed

Upgraded lightning protection

Planned:

Remedial efforts completed

HAGYS_004

Delaware County

Completed:

Performed regularly scheduled tree clearance

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Installed additional lightning protection

Inspect selected areas of circuit for vegetation issues and corrected as needed

Planned:

Remedial efforts completed

HEATON 139

Montgomery County

Completed:

Installed additional fuses

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and corrected as needed

Upgraded transformer

Planned:

HEATON_164

Bucks County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed.

HEATON 169

Montgomery County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Upgraded transformer

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed three phase recloser

Planned:

Remedial efforts completed

ISLAND ROAD 136

Philadelphia County

Completed

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Installed additional fuses

Upgraded lightning protection

Planned:

Remedial efforts completed

JENKINTOWN_139

Montgomery County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Installed additional fusing

Upgraded secondary wire

Installed faulted circuit indicators

Installed 3-single phase reclosers

Replaced underground cable

Installed faulted circuit indicators

Installed additional animal protection

Upgraded aerial cable

Planned:

Remedial efforts completed

Planned:

JENKINTOWN_140

Montgomery County

Completed:

Completed reliability corrective work orders

Installed sectionalizing devices

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Performed regularly schedule tree clearance

Test/Inspect recloser operation

Installed additional fuses

Planned:

Remedial efforts completed

JENNERSVILLE 341

Chester County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Replaced switch

Installed additional lightning protection

Planned:

Remedial efforts completed

KAOLIN_001

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Added lightning protection to supply circuit

Inspected selected areas of circuit for vegetation issues and corrected as needed

Planned:

Remedial efforts completed.

KAOLIN 003

Chester County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Upgraded fuses coordination

Inspect/Test recloser operation

Planned:

Remedial efforts completed.

KEMBLE_002

Chester County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Installed wildlife protection

Installed additional fuses

Planned:

KENNETT_SQUARE_001

Chester County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and corrected as needed

Upgraded transformer

Planned:

Remedial efforts completed

KENNETT_SQUARE_003

Chester County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Completed reliability corrective work orders

Planned:

Remedial efforts completed

KENNETT_SQUARE_005

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed.

KERBAUGH 005

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and corrected as needed

Inspected circuit visually and with thermographic camera

Upgraded transformers

Installed additional fuses

Upgraded lightning protection

Planned:

Remedial efforts completed

KERBAUGH 009

Philadelphia County

Completed:

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Installed additional fusing

Upgraded lightning protection

Completed reliability corrective work orders

Performed regularly scheduled tree clearance

Planned:

LANDENBERG_000

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed 1 phase recloser

Planned:

Remedial efforts completed.

LENAPE 341

Chester County

Completed:

Completed reliability corrective work orders

Performed regularly schedule tree clearance

Test/Inspect recloser operation

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed-3 phase recloser

Planned:

Remedial efforts completed

LENAPE_344

Chester County

Completed:

Completed reliability corrective work orders

Performed regularly schedule tree clearance

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed 3 phase recloser

Planned:

Remedial efforts completed

LENAPE_351

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed single-phase recloser

Performed regularly schedule tree clearance

Installed additional fuses

Installed additional lightning protection

Installed three-phase recloser

Tested/Inspected recloser operation

Planned

LINE 1099

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Installed wildlife protection

Installed 3 phase recloser

Installed lightning protection

Installed additional fusing

Planned:

Remedial efforts completed

LINE_1100CL

Chester County

Completed:

Installed additional lightning protection

Installed wildlife protection

Test/ Repair switch

Checked/Repaired switch operation

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed 2-3-phase reclosers

Planned

Remedial efforts completed.

LINE_2200CR

Chester County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional fuses

Planned

Remedial efforts completed.

LINE_2241

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned

Remedial efforts completed

LINE 2445

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and corrected as needed

Replaced underground cable

Installed switch

Planned:

LINE_300CR

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Test/Repair switch

Installed 3 phase recloser and tie recloser

Planned

Remedial efforts completed. .

LINE_4600PB

Chester County

Completed:

Completed reliability corrective work orders

Checked / Repaired recloser operation

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned

Remedial efforts completed

LINE 518

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned

Remedial efforts completed.

LINE_7200WH

Montgomery County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Performed regularly scheduled tree clearance

Planned

Remedial efforts completed

LINE 734

Philadelphia County

Completed:

Completed reliability corrective work orders

Performed regularly schedule tree clearance

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional lightning protection

Planned

LINFIELD 000

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional fuses

Upgraded lightning protection

Planned

Remedial efforts completed

LINTON 342

Bucks County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Upgrade lightning protection

Planned:

Remedial efforts completed

LYNDELL-000

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Installed additional fuses

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional lightning protection

Planned

Remedial efforts completed

MACDADE_137

Delaware County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Replaced aerial wire

Upgraded aerial wire

Planned:

Remedial efforts completed

MALL_058

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and corrected as needed

Planned:

Upgraded transformer/ underground wires

MALVERN 001

Chester County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and corrected as needed

Installed 3 phase recloser

Upgraded transformer

Installed additional fuses

Planned:

Remedial efforts completed

MARKLEY 133

Montgomery County

Completed:

Inspected circuit visually and with thermographic camera

Installed wildlife protection

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and corrected as needed

Install 3 phase recloser and tie

Installed single phase recloser

Test/Inspect recloser operation

Planned:

Remedial efforts completed

MARPLE_138

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Installed additional lightning protection

Upgraded lightning protection

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed

MARSHALLTON-002

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed 2-three-phase reclosers

Upgraded fuse coordination

Planned:

Remedial efforts completed

MEDIA 011

Delaware County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Performed regularly schedule tree clearance

Inspected selected areas of circuit for vegetation issues and corrected as needed

Installed 3 phase recloser

Planned

MONROE 004

Delaware County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional lightning protection

Installed additional fuses

Upgraded primary wire

Performed regularly schedule tree clearance

Installed additional wildlife protection

Planned:

Remedial efforts completed

MONROE 005

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Upgraded transformer

Installed compact single phase recloser

Planned:

Remedial efforts completed

NEWLINVILLE 343

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Installed compact single phase recloser

Installed single-phase recloser

Planned:

Remedial efforts completed.

NEWLINVILLE 344

Chester County

Completed

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Upgraded lightning protection

Upgraded fuses

Complete reliability corrective work orders

Install single phase recloser

Planned

NEWLINVILLE 351

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional lightning protection

Inspect/test recloser operation

Planned:

Remedial efforts completed.

NEWLINVILLE_353

Chester County

Completed

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed.

NORRISTOWN 009

Montgomery County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Upgrade transformer

Planned:

Remedial efforts completed

NORTH WALES 344

Montgomery County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Installed (2) three -phase recloser

Planned:

Remedial efforts completed

OLIVE 001

Chester County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Installed 3 phase recloser

Planned:

OLIVE_004

Chester County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Installed additional lightning protection

Installed additional fuses

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed

PARKESBURG_001

Chester County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Install 3-phase recloser

Planned:

Remedial efforts completed

PEACH_BOTTOM_361

York County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Performed regularly schedule tree clearance

Test/Inspect recloser operation

Planned:

Remedial efforts completed.

PENCOYD_133

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Installed animal protection

Upgraded fuses

Upgrade underground wires

Planned:

Remedial efforts completed

PERKIOMEN 354

Montgomery County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Installed (3) single phase recloser

Replaced switch

Installed additional lightning protection

Installed 3 phase recloser

Planned:

PLYMOUTH 148

Montgomery County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Install 3 phase recloser

Upgraded wildlife protection

Inspected selected areas of circuit for vegetation issues and correct as needed

Install 3 phase recloser

Planned:

Remedial efforts completed

PULASKIE_135

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Installed additional fusing

Upgraded lightning protection

Inspected selected areas of circuit for vegetation issues and corrected as needed

Planned:

Remedial efforts completed

PULASKIE_136

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Installed additional fusing

Inspected selected areas of circuit for vegetation issues and corrected as needed

Planned:

Remedial work completed

RADNOR 131

Delaware County

Completed:

Completed reliability corrective work orders

Performed regularly schedule tree clearance

Inspected circuit visually and with thermographic camera

Inspect selected areas of circuit for vegetation issues and correct as needed

Install additional fuses

Planned:

Remedial work completed

RICHMOND_132

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Replaced cable

Performed regularly schedule tree clearance

Installed additional fuses

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

RICHMOND_137

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Install additional fuses

Performed regularly schedule tree clearance

Installed (2) three phase reclosers

Upgraded transformers

Planned

Remedial efforts completed.

RODGERS_131

Bucks County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed

RUSHLAND_000

Bucks County

Completed

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Upgraded transformers

Inspected selected areas of circuit for vegetation issues and correct as needed

Tested/Inspected recloser operation

Planned:

Remedial efforts completed.

SADSBURY_000

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Install 3 phase recloser

Install additional lightning protection

Inspect selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial work completed

SAVILLE_134

Delaware County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional fusing

Install single phase recloser

Planned:

SOLEBURY_001

Bucks County

Completed:

Install additional fuse

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Upgrade primary wire

Upgraded fuse coordination

Planned

Remedial work completed

SPROUL_001

Delaware County

Completed

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Planned:

Remedial efforts completed

STREET_000

Chester County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Upgrade transformer

Performed regularly schedule tree clearance

Installed 2- three phase reclosers

Installed compact single phase recloser

Installed additional fuses

Planned:

Remedial work completed

SUNNYBURN_002

York County

Completed

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Upgraded aerial cable

Performed regularly schedule tree clearance

Upgraded transformer

Installed additional lightning protection

Planned:

SUSQUEHANNA_341

York County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Performed regularly schedule tree clearance

Replaced switch

Installed additional lightning protection

Planned:

Remedial work completed

TABOR_136

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional fuses

Planned:

Remedial efforts completed

TOKENA_002

Chester County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Upgraded lightning protection

Planned

Remedial efforts completed.

TREVOSE_138

Bucks County

Completed:

Completed reliability corrective work orders

Install compact single phase recloser

Upgraded secondary wire

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional animal protection

Upgraded secondary wire

Planned:

Remedial efforts completed

TROOPER_001

Montgomery County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial work completed

TURK 000

Bucks County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional fusing

Upgraded fusing

Planned:

Remedial efforts completed.

WAGONTOWN 000

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Upgraded transformer

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed

WALLACE_000

Chester County

Completed:

Completed reliability corrective workorders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional fuses

Planned:

Remedial efforts completed

WARMINSTER_142

Bucks County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Installed 3- single phase reclosers

Upgraded fuses

Installed wildlife protection

Upgraded aerial wire

Planned

Remedial efforts completed.

WAWA 000

Delaware County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Installed additional lightning protection

Performed regularly schedule tree clearance

Inspected selected areas of circuit for vegetation issues and correct as needed

Upgraded lightning protection

Installed additional lightning protection

Planned

Remedial work completed

WAYNE_134

Delaware County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed 6 single phase reclosers

Performed regularly schedule tree clearance

Planned:

Remedial efforts completed.

WHITEMARSH 133

Montgomery County

Completed:

Completed reliability corrective work orders

Installed wildlife protection

Installed 3- single phase reclosers

Upgraded aerial wire

Performed regularly schedule tree clearance

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrlect as needed

Installed 2-three-phase reclosers

Planned:

Remedial work completed

WICKER 001

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned

Remedial efforts completed

WILLOWDALE_002

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned

Remedial work completed

WORTH 000

Bucks County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Install additional fuses

Installed 3 phase recloser

Planned:

Appendix C

New Business Connections

This work category includes all the facility work required to add a new customer or to increase the load to an existing customer. The facility work will include the facilities required to directly connect the customer to the system and the upgrade/replacement of any existing facility to serve the requested additional load.

Capacity Expansion

This work category includes only capacity work generated by the system design engineer to prevent system failure and to assure the delivery of voltage as specified in the tariff. The addition of new substations and substation enlargements for future load growth will also be included in this project.

System Performance

This work category includes projects designed to upgrade, modify or improve the performance of the distribution system. Also included in this category are indirect costs in support of all categories and one-time accounting adjustment items.

Facility Relocation

This work category includes all requests for relocation of PECO facilities including municipal as well as customer related relocation requests.

Maintenance

This work category includes work performed to repair and restore equipment to its normal state of operation, along with planned preventive maintenance work such as visual and thermographic inspections and tree trimming around transmission and distribution lines.

Storm Funds

Incremental costs (primarily; overtime, contractors, mutual assistance, and meals) incurred while responding to major storms (storms that meet customer outage and duration criteria).