

Legal Department

Exelon Business Services Company
2301 Market Street/523-1
P.O. Box 8699
Philadelphia, PA 19101-8699

Telephone 215.841.4000
Fax 215.568.3389
www.exeloncorp.com

John C. Halderman
Associate General Counsel
Direct Dial: 215-841-4263
Direct Fax: 215-841-4474
john.halderman@exeloncorp.com

March 29, 2011

Rosemary Chiavetta, Secretary
Pennsylvania Public Utility Commission
P. O. Box 3265
Harrisburg, PA 17105-3265


RE: Pipeline Easement Agreement – Installation of a Sanitary Force Main, Lower
Pottsgrove Township, Montgomery County

Dear Ms. Chiavetta:

Enclosed for filing and approval pursuant to §507 of the Public Utility Code are two
copies of a Pipeline Easement Agreement regarding the above-referenced matter.

Kindly advise me of the Commission's approval thereof. Enclosed for your convenience
is a self-addressed U.S. postage paid envelope.

Very truly yours,



John C. Halderman

JCH/as
enclosures

cc: Lori Dougherty

RECEIVED
2011 MAR 31 AM 11:28
P. U. C.
SECRETARY'S BUREAU

RECEIVED

2011 MAR 31 AM 11:29

PIPELINE EASEMENT AGREEMENT

PA. P.U.C. SECRETARY
THIS EASEMENT AGREEMENT (this "Agreement") made this 14th day of March 2011, by and between PECO ENERGY COMPANY, a Pennsylvania corporation (the "Grantor") and LOWER POTTS GROVE TOWNSHIP (the "Grantee").

BACKGROUND

A. Grantor is the owner, in fee, of a certain parcel of ground situate in Lower Pottsgrove Township, Montgomery County, Pennsylvania (the "Property"), used for the transmission and distribution of electricity.

B. Grantee has requested that Grantor grant Grantee the right to install a sanitary force main under and across so much of the Property as lies within a twelve and half (12.5) foot wide strip of ground.

NOW, THEREFORE, Grantor, for and in consideration of the sum of NINE THOUSAND TWO HUNDRED AND EIGHTY DOLLARS (\$9,280.00), the receipt whereof is hereby acknowledged, insofar as it has the power, title and authority so to do, hereby grants unto Grantee the right, liberty and privilege to lay, construct, install, use, operate, maintain, repair, renew, remove, and replace one (1) sixteen (18) inch diameter sanitary force main together with appurtenances (the "Pipeline") in, under, across and through so much of the Property of Grantor, situate in Lower Pottsgrove Township, Montgomery County, Pennsylvania, as lies within a twelve and a half (12.5) foot wide strip of ground (the "Easement Area"), bounded and described in accordance with plan as Exhibit "A", attached hereto and made part hereof.

TOGETHER with the right of ingress and egress to, from and over the Easement Area as reasonably necessary for the exercise of the rights granted herein.

UNDER and SUBJECT, nevertheless, to certain conditions, easements and restrictions as appear of record or to which a survey or personal inspection might otherwise reveal; ALSO UNDER AND SUBJECT to the express conditions hereinafter set forth, the faithful performance of which constitutes an essential part of the consideration hereof:

1. (a) Grantee acknowledges that Grantor's business includes the construction, installation, maintenance, operation and use of structures, fixtures, facilities and instrumentation, with appurtenances (the "Grantor's Facilities"), now or which may hereafter be constructed on, over, under and across the Property and Easement Area, which are used or useful for the generation, conversion, transmission or distribution of electricity, gas and communications.

(b) Grantee agrees to comply with all requirements of any of the constituted public authorities and with the terms of any federal, state or local laws or

regulations applicable to Grantee's use of the Easement Area (collectively, "Laws"), and save Grantor harmless from penalties, fines, damages or costs (including without limitation reasonable attorney's fees) resulting from Grantee's failure to do so.

(c) Grantor reserves the right to use the Easement Area for its corporate purposes at all times and to grant easements, leases or other rights upon the Easement Area for any purposes that do not interfere with the use of the Pipeline. If the Pipeline interferes with Grantor's use of the Property for Grantor's corporate purposes, Grantee agrees to relocate the Pipeline at its sole cost and expense, within a reasonable period following notice from Grantor to do so. Grantor, subject to such internal approvals as Grantor may require, shall provide Grantee with such alternate right of way within the Property as may be reasonably required for such relocation. Grantee reserves the right as Grantor deems necessary to cut down, trim and remove any trees, brush or other vegetation that interferes with or potentially interferes with Grantor's Facilities.

2. (a) Grantee shall lay, construct, install, use, maintain, repair, renew, remove, replace and operate the Pipeline at its sole cost and expense, in a good and workmanlike manner and in conformity with all Laws, and with the Construction Standards and the Approved Plans, as defined in Section 13, doing as little damage as possible to the Property and Easement Area.

(b) Grantee shall, upon completion of any work done, (1) restore the Property and Easement Area to a condition at least equal to that existing prior to such work including, but not limited to properly filling, tamping, seeding and re-seeding the surface, refilling following any subsequent settlement due to any excavation made for the Pipeline and re-grading in order to maintain the drainage pattern existing prior to the construction of the Pipeline. Any drainage problems created by Grantee shall be corrected at its sole cost and expense without additional use of the Property, (2) remove all material and debris and re-establish Grantor's right-of-way roads or trails to their original condition and (3) repair and put into good condition or replace if necessary, at its sole cost and expense, and to the satisfaction of Grantor, any and all property and improvements of Grantor damaged by the construction or installation of the Pipeline including, but not limited to, fences and shrubbery. Any such repairs or replacement required for Grantor's Facilities shall be performed by Grantor at Grantee's sole cost and expense.

(c) Grantee shall maintain the Pipeline at its sole cost and expense in accordance with applicable Laws and good utility practice.

3. Grantee shall exercise particular care in laying, constructing, installing, using, maintaining, repairing, renewing, removing or replacing the Pipeline to avoid interference, contact with or damage to Grantor's Facilities. Grantee will not cause or permit any material, boom, crane or similar mechanical equipment, nor any part thereof,

to come within: (a) thirty-five (35) feet (10.7 meters) of a 500 kV conductor; (b) twenty-five (25) feet (7.7 meters) of a 230 kV conductor; (c) twenty (20) feet (6.1 meters) of a 133 kV conductor; (d) fifteen (15) feet (4.6 meters) of a 69 kV conductor and (e) twelve (12) feet (3.7 meters) of any electric conductor less than 69 kV without Grantor's prior approval as hereinafter provided in Section 15. Grantee shall not permit equipment to operate within five (5) feet of any tower foundations, poles or anchor guys supporting said towers or poles. The Pipeline shall be constructed at least twenty-five (25) feet away from any tower leg or structure and at least ten (10) feet from any wood poles or anchors supporting Grantor's Facilities. No excavation shall be made closer than twenty-five (25) feet to Grantor's transmission towers or structures without specific written approval by Grantor.

4. Grantee shall adhere at all times to current occupational safety and health regulations (OSHA) and Pennsylvania Department of Labor and Industry Regulations, or regulations of any other agency having jurisdiction, regarding the safe operation of cranes, booms and hoists or other equipment in the vicinity of energized conductors. If Grantee uncovers or damages any electric transmission line grounding leads or counterpoise wire or damages any of Grantor's Facilities, Grantee shall immediately notify Grantor's Transmission & Substations Work Dispatcher as provided in Section 15 and any damage to Grantor's Facilities shall be repaired or replaced by Grantor at Grantee's sole cost and expense. Grantee or its contractors shall not touch, handle or attempt to repair any exposed and/or severed grounding leads or counterpoise wire or other Facilities. Grantee is responsible to inform equipment operators of the nature and location of underground facilities in the Easement Area.

5. (a) If Grantee requests Grantor's approval to operate equipment closer to conductors than permitted in Section 3, and provided Grantor can accommodate such request, Grantor's Facilities must be de-energized and grounded prior to the start of any construction operation which shall require any part of such equipment to be positioned closer to Grantor's Facilities than provided in Section 3. Grantee shall not permit any equipment or material to contact a de-energized conductor. Grantee must notify Grantor's Transmission & Substations Work Dispatcher, as provided in Section 15, at least seven (7) months prior to any work requiring Grantor's Facilities to be de-energized. If such request can be accommodated a schedule shall be developed by Grantor to allow for Grantee's construction, if feasible. Grantee shall reimburse Grantor for any costs including, but not limited to, additional generating costs as determined by Grantor as a result of such de-energizing of Grantor's Facilities. If an emergency occurs during the period Grantor's Facilities are de-energized and Grantor's Facilities are required to maintain its system operation, Grantee must make Grantor's Facilities available for use within one (1) hour of notification.

(b) Notwithstanding anything herein to the contrary, Grantor is under no obligation whatsoever to de-energize or relocate any of Grantor's Facilities to

accommodate the Pipeline including its installation, maintenance, removal or replacement.

6. Grantee shall use special care not to disturb or undermine Grantor's Facilities in any manner whatsoever. Grantee shall not interfere with or block Grantor's access to Grantor's Facilities or the Property at any time and when necessary shall properly plank excavations to facilitate Grantor's access with men, equipment and vehicles.

7. Grantee shall not store or use explosives on the Easement Area or the Property for the construction, installation, maintenance, renewal, removal or replacement of the Pipeline.

8. No buildings, storage sheds, trailers, equipment, dirt, rock or materials of any type are permitted to be stored on the Property or the Easement Area at any time. Grantee shall not park equipment or vehicles on the Easement Area or Property at any time except when actually performing work permitted hereunder on the Easement Area. Grantee is granted the right to construct the Pipeline and no other rights or permission for any other use of the Property and the Easement Area is granted hereunder.

9. (a) If cathodic protection systems are to be installed, Grantee shall furnish engineering plans or drawings of cathodic protection systems for Grantor's review and approval prior to installation. Cathodic protection tests shall be performed on the completed Pipeline by and at the expense of Grantee, and Grantee shall provide Grantor with written results of such tests within thirty (30) days following installation of the cathodic protection system.

(b) Grantee shall use special care to avoid leakage at pipe joints or seepage into open ditches during the construction, installation, use, maintenance, repair, renewal, removal or replacement of the Pipeline which might lead to undermining Grantor's Facilities.

(c) If a leak or spill occurs from the Pipeline, Grantee agrees to immediately commence and complete cleanup operations and satisfy all requirements of Grantor, the Environmental Protection Agency and any other governmental agency for the cleanup of the leak or spill and further agrees to assume full responsibility for the costs of the cleanup.

(d) The Pipeline shall have a minimum cover as approved or as specified by Grantor. Grantee is aware Grantor intends to traverse over the Pipeline with vehicles generally weighing 38,000 pounds per axle and the Pipeline shall be installed accordingly. Grantor does not warrant that any approved or specified cover will protect the Pipeline.

(e) Manholes shall not extend above grade unless otherwise approved by Grantor.

(f) Grantee shall install and maintain, at its expense, permanent markers for the Pipeline at strategic locations longitudinally and where the Pipeline enters and leaves the Easement Area and at all angles in the Pipeline. The markers must be approved by Grantor prior to their installation which Grantee agrees to complete no later than six (6) months following completion of the Pipeline in the Easement Area.

10. Grantee assumes all risk of loss, injury or damage to the Pipeline or personal property and all risk of injury or death to its employees, contractors, workmen, or any other person or persons from any causes whatever, including but not limited to claims for injuries to employees of Grantor, Grantee or their contractors or subcontractors. To the fullest extent permitted by applicable law, Grantee shall at all times hereafter indemnify, defend and save harmless Grantor, its officers, directors, employees, agents, contractors, invitees and affiliates ("Grantor Parties"), from and against any and all claims, actions, liability, damages, costs and expenses (including attorneys' fees) in connection with loss of life, personal injury, or damage to property caused to any person in or about the Property and the Easement Area (including but not limited to claims for injuries to employees of Grantor, Grantee or their contractors or subcontractors) or arising out of the occupancy or use of the Easement Area by Grantee or occasioned wholly or in part by the act or omission of Grantee, its employees, agents, contractors, invitees, and affiliates regardless of the concurrent negligence of Grantor Parties unless attributable to the sole negligence of the Grantor Parties. In furtherance of the foregoing and not by limitation thereof, Grantee hereby waives any defense Grantee may otherwise have under applicable workers' compensation laws.

11. (a) In addition to the indemnifications contained in Section 10, but not in limitation thereof, Grantee agrees to carry and maintain Commercial General Liability Insurance (with coverage consistent with ISO Form CG0001 (12/04) providing bodily injury, property damage and personal/advertising injury coverage (including but not limited to coverage for claims against Grantor for injuries to employees of Grantee or its contractors or subcontractors) with a combined single limit of not less than Four Million Dollars (\$4,000,000) per occurrence and shall include blanket contractual liability coverage for Grantee's obligations under this Agreement with an insurance company or companies acceptable to Grantor during the construction, installation, maintenance, repair, renewal, removal or replacement of the Pipeline. Grantee shall furnish Grantor with evidence of such insurance in the form of a policy or certificate of insurance. The policy or certificate shall name Grantor, its officers, agents and employees, as additional insured, be primary insurance for all purposes, contain cross-liability provisions, and provide for a waiver of all rights of subrogation which Grantee's insurance carrier may have against Grantor.

(b) The policy or certificate shall be forwarded to Grantor prior to commencing any work on the Easement Area, and contain a provision that Grantor be notified with at least ten (10) days prior notice in the event of cancellation of the insurance.

(c) Insurance coverage provided by Grantee or its contractors or subcontractors under this Agreement shall not include any of the following: any claims made insurance policies; any self-insured retention or deductible amount greater than Two Hundred Fifty Thousand Dollars (\$250,000) unless approved in writing by Grantor; any endorsement limiting coverage available to Grantor which is otherwise required by this Agreement; and any policy or endorsement language that (1) negates coverage to Grantor for Grantor's own negligence, (2) limits the duty to defend Grantor under the policy, (3) provides coverage to Grantor only if Grantee is negligent, (4) permits the recovery of defense costs from any additional insured, or (5) limits the scope of coverage for liability assumed under a contract.

12. If any lien is filed against the Property by any contractor of Grantee for work done on the Property, Grantee shall cause same to be discharged or satisfied within fifteen (15) days of service or upon notice of same, whichever shall be sooner. Grantee shall indemnify, defend and hold harmless Grantor against all costs and expenses (including, without limitation reasonable attorneys' fees arising out of any such liens.

13. Prior to performing any work in the Easement Area, Grantee shall submit to Grantor's Real Estate & Facilities Department for review and approval, eight (8) paper copies and one (1) electronic copy of plans prepared in accordance with Grantor's Electric Construction Standard S-7073, a copy of which is attached as Exhibit "B" (or any revisions thereto of successor standards) showing all proposed alterations or improvements to be constructed on the Easement Area ("Grantee's Improvements"). All plans must be drawn to scale with units in feet and submitted in Microstation format referenced to applicable state plane Pennsylvania south coordinates (NAD83 and NAVD88 datum) showing Grantee's Improvements, including without limitation, building location and elevation, light poles, parking areas, roads and other paved areas, proposed grading (including existing grade), drainage facilities, landscaping and other required information, together with the location of Grantor's Facilities. Grantor reserves the right to decline to review drawings submitted without the required information. Grantor will use commercially reasonable efforts to complete its review of Grantee's plans within ninety (90) days of receipt thereof. If Grantor has not completed its review of Grantee's plans and notified Grantee within such 90-day period, Grantee shall have the right to terminate this Agreement. If the plans are disapproved Grantor shall give written notice of the reasons for such disapproval. **GRANTEE SHALL NOT COMMENCE ANY ALTERATIONS OR THE CONSTRUCTION OR INSTALLATION OF GRANTEE'S IMPROVEMENTS UPON THE EASEMENT AREA INITIALLY OR AT**

ANY FUTURE TIME UNTIL GRANTEE HAS RECEIVED WRITTEN APPROVAL FROM GRANTOR OF GRANTEE'S PLANS ("Approved Plans").

14. If it should be deemed necessary by Grantor to take precautionary measures such as, but not limited to, relocating Grantor's Facilities, supplying safety inspectors to insure that any work performed is done in a safe and proper manner, de-energizing conductors, and erecting barricades due to the installation, construction, maintenance, renewal, removal, repair, or replacement of the Pipeline, then Grantee shall pay for any such measures taken by Grantor on a cost plus overhead basis within thirty (30) days of submission of a bill therefor from Grantor. It is understood and agreed that this shall, in no way, relieve Grantee from any liability in connection with the rights herein granted.

15. (a) At least two (2) months prior to the commencement of any construction or other work on the Easement Area or Pipeline (or seven (7) months if it shall be necessary to de-energize Grantor's Facilities) Grantee shall contact Grantor's Work Dispatcher, Transmission & Substations, 1040 Swedesford Road, Berwyn, Pennsylvania, 19312 (Telephone No. 610-648-7920 or 7921) to make arrangements with Grantor's representatives to review Grantee's previously approved plans or drawings to determine what precautionary measures, if any, are required. Grantee shall again contact Grantor's Transmission & Substations Work Dispatcher at least five (5) days prior to beginning any work in the Easement Area as notice that work is to commence and to confirm previously made precautionary measures and other arrangements. **PRIOR APPROVAL OF GRANTEE'S PLANS OR DRAWINGS BY GRANTOR DOES NOT CONSTITUTE NOTICE TO OR APPROVAL BY GRANTOR FOR GRANTEE TO COMMENCE WORK ON GRANTOR'S PROPERTY OR THE EASEMENT AREA. GRANTEE AGREES THAT ABSOLUTELY NO WORK SHALL BEGIN ON THE EASEMENT AREA, INITIALLY OR AT ANY FUTURE TIME, UNLESS GRANTEE HAS MADE PROPER ARRANGEMENTS AND GIVEN THE REQUIRED NOTICE AS AFORESAID.**

(b) The Easement Area and the Property are or may be utilized for underground electric, gas and communication facilities. Grantee shall contact the Pennsylvania ONE CALL SYSTEM (telephone no. 1-800-242-1776) to determine the location of any underground facilities at least five (5) working days prior to performing any work in the Easement Area.

16. (a) Grantee shall pay all real property taxes and other charges and assessments levied upon or assessed against Grantor or the Property caused by the construction or presence of the Pipeline and shall save Grantor harmless from any such taxes, charges and assessments at its sole cost and expense.

(b) Grantee covenants and agrees that no charge or assessment shall be made or imposed upon Grantor or the Property for the cost of installing and

constructing the Pipeline and shall save Grantor harmless from any such charge or assessment at Grantee's sole cost and expense.

17. Construction or installation of the Pipeline shall be completed within ten (10) years from the date of this Agreement. If Grantee fails to complete the construction or installation of the Pipeline or thereafter ceases to use the same, or fails to comply with the covenants, agreements or conditions of this Agreement, then the easement herein granted shall be and become null and void and of no further force and effect, and all rights hereunder shall revert to Grantor. In such event Grantee shall execute and deliver a release to Grantor, in recordable form, abrogating the easement herein granted and remove the Pipeline and restore the Easement Area to good order and condition as set forth in Section 2 (b) within sixty (60) days following notice from Grantor to do so.

18. Grantee may not assign its interest in this Agreement without the prior written approval of Grantor.

19. All notices given by either party shall be in writing served personally upon the other party; sent by United States certified mail, return receipt requested, or sent by a recognized commercial courier service, addressed to the other party at its address as follows:

Grantor:

PECO Energy Company
2301 Market Street
Philadelphia, PA 19103
Attn: Director, Real Estate & Facilities

Grantee:

Lower Pottsgrove Township Authority
2199 Buchert Rd
Pottstown, Pa 19464

20. This Agreement is made under and subject to the lien of the First and Refunding Mortgage dated as of May 1, 1923, of the Counties Gas and Electric Company (to which PECO Energy Company is Successor) to Fidelity Trust Company (to which US Bank, National Association is Successor) as the same has been heretofore and may hereafter be amended and supplemented for the security of the presently outstanding bonds of Grantor and other and additional bonds which may

hereafter be issued and outstanding under said Mortgage as so amended and supplemented.

21. Grantor shall file a copy of this Agreement with the Pennsylvania Public Utility Commission promptly upon the execution hereof, the 33rd day after such filing shall be the effective date hereof, unless prior to such date proceedings are instituted as provided in Section 507 of the Pennsylvania Public Utility Law, Title 66, and in the event of the institution of such proceedings, then this Agreement shall become effective as to Grantor only after approval by the Pennsylvania Public Utility Commission.

22. (a) In the event of a non-monetary default of Grantee under this Agreement, including Grantee's failure to construct the Pipeline in accordance with Approved Plans, Grantor shall have the right to take any and all corrective actions Grantor deems necessary or appropriate to cure the default of Grantee and charge the cost thereof to Grantee.

(b) In addition to any other rights set forth in this Agreement, but without limitation, Grantor may enforce this Agreement by legal or equitable proceedings against the Grantee either to specifically enforce, restrain, or enjoin the violation of any restriction, covenant, condition, agreement, term, representation, or warranty herein contained or to recover damages. Notwithstanding any other provision of this Agreement, it is understood and agreed that the remedies permitted pursuant to this Agreement other than equitable remedies may be inadequate in the case of any breach by Grantee of its obligations contained herein. Accordingly, Grantee agrees that in such instances, Grantor shall be entitled to preliminary injunctive relief from a court of competent jurisdiction without bond or proof of damages, and Grantee shall not plead in defense that there would be an adequate remedy at law.

23. (a) The covenants, agreements and conditions herein contained shall inure to and bind the respective successors and, to the extent permitted, assigns of the parties hereto.

(b) Any amendments or modifications of this Agreement shall be made only in a writing executed by all parties to this Agreement (or their permitted successors and assigns).

(c) This Agreement shall be governed in all respects, including validity, interpretation and effect, by the laws of the Commonwealth of Pennsylvania without giving effect to the conflict of law principles thereof.

(d) This Agreement (including the exhibits hereto), and the other documents and instruments specifically provided for herein and therein contain the entire understanding between the parties concerning the subject matter hereof and thereof and, except as expressly provided for herein, supersede all prior

understandings and agreements, whether oral or written, between them with respect to the subject matter hereof and thereof.

(e) This Agreement may be executed in one or more counterparts, each of which shall be deemed an original, but all of which together shall constitute one and the same instrument.

(f) The parties do not intend to create rights in, or grant remedies to, any third party as a beneficiary of this Agreement or of any duty, covenant, obligation or understanding established under this Agreement, except insofar as such third party may be the beneficiary of an indemnity hereunder.

(g) The failure of a party to insist, in any one or more instances, on performance of any of the terms, covenants and conditions of this Agreement shall not be construed as a waiver or relinquishment of any rights granted hereunder or of the future performance of any such term, covenant or condition, but the obligations of the parties with respect thereto shall continue in full force and effect. No waiver of any provision or condition of this Agreement by a party shall be valid unless in writing signed by such party or operational by the terms of this Agreement. A waiver by one party of the performance of any covenant, condition, representation or warranty of the other party shall not invalidate this Agreement, nor shall such waiver be construed as a waiver of any other covenant, condition, representation or warranty. A waiver by any party of the time for performing any act shall not constitute a waiver of the time for performing any other act or the time for performing an identical act required to be performed at a later time.

(EXECUTED BY THE PARTIES ON THE FOLLOWING PAGE)

EXECUTED the day and year first above written.

PECO ENERGY COMPANY

ATTEST:



Assistant Corporate Secretary

BY:



Director, Real Estate & Facilities


Lower Pottsgrove Township Authority

ATTEST/WITNESS:


Attest/Witness

BY:


James P. Toth



COMMONWEALTH OF PENNSYLVANIA:


COUNTY OF *Philadelphia* : SS.

On this, the *7th* day of *March* 2011, before me, a Notary Public, the undersigned officer, personally appeared M. A. Williams, who acknowledged himself to be Director, Real Estate & Facilities of PECO ENERGY COMPANY, a corporation and that he as such Director, Real Estate & Facilities, being authorized to do so, executed the foregoing instrument for the purposes therein contained, by signing the name of the corporation by himself as Director, Real Estate & Facilities.

IN WITNESS WHEREOF, I hereunto set my hand and official seal.

Suzanne M. Szajnos

Notary Public



COMMONWEALTH OF PENNSYLVANIA:

COUNTY OF Montgomery : SS.
:

On this, the 14th day of March 2011, before me, _____, the undersigned officer, personally appeared James D. Toth known to me (or satisfactorily proven) to be the person(s) whose name is/are subscribed to the foregoing instrument, and acknowledged that he executed the same for the purposes therein contained.

IN WITNESS WHEREOF, I hereunto set my hand and official seal.

Nadine M. Kozak
Notary Public

COMMONWEALTH OF PENNSYLVANIA
Notarial Seal
Nadine M. Kozak, Notary Public
Uwchlan Twp., Chester County
My Commission Expires Aug. 11, 2011
Member, Pennsylvania Association of Notaries

File No. 1063

LD/ld

EXHIBIT "A"
to
PIPELINE EASEMENT AGREEMENT
between
PECO ENERGY COMPANY
and
LOWER POTTS GROVE TOWNSHIP AUTHORITY

"Such one hundred sixty (160) foot wide temporary construction easement shall expire, without the need for any further act or deed by Grantor, upon completion of the initial installation of the Pipeline, but no later than October 1st 2011."

© COPYRIGHT BURSICH ASSOCIATES, INC. 2010
 ALL REPORTS, DOCUMENTS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES AND OTHER DOCUMENTS AND INSTRUMENTS PREPARED BY BURSICH ASSOCIATES, INC. OR INSTRUMENTS OF SERVICE SHALL REMAIN THE PROPERTY OF BURSICH ASSOCIATES, INC. AND THEREFORE SHALL REMAIN ALL COPYRIGHT LAW, STATUTORY AND OTHER RIGHTS RESERVED. INCLUDING THE COPYRIGHT THEREIN. ANY USE, REUSE OR MODIFICATION/ALTERATION AND REPRODUCTION WITHOUT THE EXPRESS WRITTEN CONSENT OF BURSICH ASSOCIATES, INC. IS STRICTLY PROHIBITED. ANY USE, REUSE OR MODIFICATION/ALTERATION BY ANYONE WITHOUT WRITTEN CONSENT SHALL BE DEEMED AN AGREEMENT BETWEEN THE USER AND BURSICH ASSOCIATES, INC. WHICH SHALL INDICATE AND SIGNIFY BURSICH ASSOCIATES, INC. FOR ALL CLAIMS, DAMAGES, LOSSES AND EXPENSES ARISING FROM THE USE THEREOF.






EXHIBIT "A"

<p>BURSICH Sharing your Vision</p>	<p>CLIENT LOWER POTTS GROVE TOWNSHIP AUTHORITY 2199 BUCHERT ROAD POTTS TOWN, PA 19464</p>	<p>PECO EASEMENT EXHIBIT PLAN</p> <p>PORTER ROAD PUMP STATION FORCE MAIN</p>
	<p>SCALE: AS SHOWN REV:</p> <p>DATE: 10/25/10 DRWN BY: AK</p> <p>JOB NO.: 106559 CHKD BY: CEC</p>	<p>LOWER POTTS GROVE TWP. MONTGOMERY CO PENNSYLVANIA</p>
<p>www.bursich.com</p>		<p>DWG NO.: Exhibit01 SHEET: 1 OF 1</p>

**INFORMATION REQUIRED TO EVALUATE PROPOSED
TRANSMISSION LINE RIGHTS-OF-WAY SECONDARY USES
PECO ENERGY COMPANY AND ITS SUBSIDIARIES**

PECO Energy Company (PECO Energy) considers proposed secondary uses of transmission line rights-of-way in accordance with its electric construction standards S-7072, "Secondary Uses for Rights-of-Way Along Electric Transmission Lines" and S-7074, "General Conditions Regulating Approved Secondary Uses for Transmission Line Rights-of-Way of PECO Energy Company and its Subsidiaries" respectively. In order to properly evaluate these proposed secondary uses, PECO Energy requires that certain information be submitted to its Real Estate Department as follows:

1.0 PRELIMINARY PLANS

PECO Energy will accept for review and comment a preliminary sketch or concept plan prepared in advance of formal drawings for the purpose of determining the feasibility of a particular right-of-way use. This plan shall indicate the proposed use and general location in relation to PECO Energy's facilities. Six (6) copies of this preliminary report shall be submitted to PECO Energy Real Estate Department, 2301 Market Street, Philadelphia, PA 19101.

2.0 FINAL DRAWINGS - Submission of the final drawings shall be required before PECO Energy will consider granting final approval of the project and before any work may begin on PECO Energy property. Six (6) copies of the final drawings containing the following information shall be submitted for approval to the PECO Energy Real Estate Department:

- 2.1** Location of all PECO Energy transmission and distribution structures, including identification numbers, poles, guys manholes, and all underground facilities.
- 2.2** Grade elevations at the base of all PECO Energy facilities.
- 2.3** Proposed road and parking lot details including location, type of construction, grade elevations, drainage plans, and the location of any curbs, sidewalks or protective barriers.
- 2.4** The location and height of all proposed street lights.
- 2.5** Where regrading is necessary, include both existing and final grades on the plans.
- 2.6** Where plantings are proposed, the location, number and species shall be specified.
- 2.7** The location, size, and, depth of all proposed underground facilities such as water and sewer lines shall be specified.
- 2.8** All plans shall be drawn to a suitable scale and elevations shall be referenced to U.S. Coast & Geodetic datum or other datum acceptable to PECO Energy.

EXHIBIT "B"

**INFORMATION REQUIRED TO EVALUATE PROPOSED
TRANSMISSION LINE RIGHTS-OF-WAY SECONDARY USES
PECO ENERGY COMPANY AND ITS SUBSIDIARIES
ELECTRIC CONSTRUCTION STANDARDS**

(12/82) Page 1 of 2 Rev. 8/95



PECO ENERGY

S-7073

3.0 **SAFETY** - All plans and drawings, preliminary and final, involving work in the vicinity of PECO Energy electric lines must include the following:

CONTACT WITH POWER LINES CAN RESULT IN DEATH OR SERIOUS BURNS. TREAT ALL OVERHEAD POWER LINES AS ENERGIZED AND POTENTIALLY DANGEROUS. All contractors and subcontractors must obtain copies of PECO Energy Electric Construction Standard S-7070, "Conditions for Working in the Vicinity of Electric Transmission Lines of PECO Energy and Its Subsidiaries" and comply with its provisions.

4.0 **REFERENCES**

4.1 PECO Energy Company Construction Standards

4.1.1 S-7070: "Conditions for Working in the Vicinity of Electric Transmission Lines of PECO Energy and Its Subsidiaries"

4.1.2 S-7072: "Secondary Uses for Rights-of-Way Along Electric Transmission Lines"

4.1.3 S-7074: "General Conditions Regulating Approved Secondary Uses for Transmission Line Rights-of-Way of PECO Energy Company and Its Subsidiaries"

**INFORMATION REQUIRED TO EVALUATE PROPOSED
TRANSMISSION LINE RIGHTS-OF-WAY SECONDARY USES
PECO ENERGY COMPANY AND ITS SUBSIDIARIES
ELECTRIC CONSTRUCTION STANDARDS**

(12/82) Page 2 of 2 Rev. 6/95

S-7073



PECO ENERGY

**CONDITIONS FOR WORKING IN THE VICINITY OF
ELECTRIC TRANSMISSION LINES OF
PECO ENERGY COMPANY AND ITS SUBSIDIARIES**

CONTACT WITH POWER LINES CAN RESULT IN DEATH OR SERIOUS BURNS

**CALL PECO ENERGY AT 610-648-7920 OR 7921 BEFORE WORKING IN THE
VICINITY OF PECO ENERGY ELECTRIC TRANSMISSION LINES**

1.0 DEFINITIONS: As used in this Standard:

- 1.1 PECO Energy means PECO Energy Company and its subsidiaries, including but not limited to Susquehanna Power Company and Susquehanna Electric Company.
- 1.2 Contractor means natural person, firm, business association, company, partnership, corporation, tenant, lessee, grantee or licensee who or which is controlling or performing the job or activity that necessitates the approval and notification required by this standard.
- 1.3 In the vicinity of PECO Energy electric transmission lines means construction or other work activities on or adjacent to rights-of-way or easements that contain PECO Energy electric transmission lines, including but not limited to any use of cranes, booms, hoists, ladders or other equipment or items that might come within the clearance distances set forth in Table I, below.

TABLE I

Clearance Distance to Transmission Lines

<u>Nominal Operating Voltage</u> <u>(volts)</u>	<u>Distance</u>	
	<u>(feet)</u>	<u>(meters)</u>
500,000	35	10.7
230,000	25	7.7
138,000	20	6.1
69,000	15	4.6
34,000 and below	12	3.7

- 2.0 APPROVAL: All contractors engaged in construction or other work activities on PECO Energy rights-of-way must obtain the specific advance written approval of PECO Energy Real Estate Department, 2301 Market Street, Philadelphia, Pa. 19101, Telephone (215) 841-5395.
- 3.0 CONTRACTOR'S DUTY AND RESPONSIBILITY: It is the contractor's duty and responsibility to ensure that all construction or other work activities in the vicinity of PECO Energy electric transmission lines shall be performed in accordance with the latest applicable federal, state and local statutes and regulations governing the safe operation of cranes, booms, hoists, ladders or other equipment and safe work practices of personnel in the vicinity of electric transmission lines.

**CONDITIONS FOR WORKING IN THE VICINITY OF
ELECTRIC TRANSMISSION LINES OF
PECO ENERGY COMPANY AND ITS SUBSIDIARIES
ELECTRIC CONSTRUCTION STANDARDS**

(6/87) Page 1 of 3 Revised 8/95



PECO ENERGY

S-7070

- 4.0 **RESPONSIBILITY FOR SUB-CONTRACTORS:** The prime contractor shall be responsible for supplying copies of the S-7070 to all sub-contractors and determining that the sub-contractors are familiar with the information contained therein.
- 5.0 **NOTIFICATION:** In addition to the advance approval required in paragraph 2, the contractor shall contact PECO Energy in accordance with the following schedule:
- 5.1 As soon as possible, but no less than thirty (30) calendar days before construction or other work activities are to start, if at any time any construction or work activities may or could take place in the vicinity of PECO Energy electric transmission lines, the contractor shall contact the PECO Energy Consumer Energy Services Group, Transmission and Substations (T&S) Expediter, Overhead Transmission Center, 1040 Swedesford Road, Berwyn, Pa. 19312, Telephone 610-648-7920 or 610-648-7921. After this notification, PECO Energy will review the project and coordinate with the contractor on what precautionary safety measures, if any, are appropriate: If transmission line outages are required, the contractor and representatives of the T&S will work together to develop a tentative schedule.
- 5.2 The contractor shall also contact the T&S Expediter at 610-648-7920 or 7921 at least ten (10) working days before construction or other work activity is to begin to confirm scheduling and arrangements.
- 5.3 If at any time during construction or other work activities, a previously unanticipated need for equipment or personnel in the vicinity of PECO Energy electric transmission lines occurs, the contractor shall immediately contact the CMTT Expediter at 610-648-7920 or 7921. Construction or other work activities in the vicinity of PECO Energy transmission lines without prior notice to PECO Energy in accordance with paragraphs 5.a. and 5.b. is potentially dangerous and is absolutely forbidden.
- 5.4 In addition to electric transmission lines, PECO Energy rights-of-way and easements may also contain distribution lines. Contractor shall treat all overhead power lines as energized and potentially dangerous. Contractor shall notify PECO Energy at 610-648-7920 or 7921 if at any time any construction or other work activities may or could take place in the vicinity of any overhead power lines.
- 5.5 In the event of any contact with PECO Energy facilities, the contractor shall call the PECO Energy System Operations at 215-841-5141 as soon as possible.
- 6.0 **OUTAGES:**
- 6.1 PECO Energy shall determine the available time periods for line outages in the event de-energizing conductors is necessary. If the contractor insists on a specific day or time for an outage which results in the use of inefficient generation, the contractor shall reimburse PECO Energy for the additional generating costs, as determined by PECO Energy System Operations Division.

CONDITIONS FOR WORKING IN THE VICINITY OF
ELECTRIC TRANSMISSION LINES OF
PECO ENERGY COMPANY AND ITS SUBSIDIARIES
ELECTRIC CONSTRUCTION STANDARDS

(6/87) Page 2 of 3 Revised 6/95

S-7070



PECO ENERGY

- 6.2 If an emergency occurs on the PECO Energy system during a scheduled line outage period and that line is required to maintain system integrity, the contractor shall, within one hour, make the transmission line available for PECO Energy's use and shall cease work within the vicinity of the line.
- 7.0 **REIMBURSEMENT BY CONTRACTOR:** PECO Energy shall be reimbursed by the contractor for all costs and expenses incurred in implementing any precautionary safety measures.
- 8.0 **BLASTING:** No blasting shall be permitted in the vicinity of transmission line facilities without specific advance written approval by PECO Energy. Notification of intent to blast shall be made in accordance with paragraph 5.b.
- 9.0 **EXCAVATIONS:**
- 9.1 No one shall excavate closer than 25 feet to PECO Energy transmission structures or anchors without specific advance written approval by PECO Energy. Notification of intent to excavate shall be made in accordance with paragraphs 5.a. and 5.b.
- 9.2 Contractors shall comply with the provisions of the Pennsylvania or Maryland One-Call Systems. In Pennsylvania, call 1-800-242-1776. In Maryland, call 1-800-257-7777.
- 10.0 **GROUNDING SYSTEM:** The contractor shall notify CMTT Division in the event he or any sub-contractor uncovers or destroys any transmission line grounding leads. The repairs to this equipment shall be made by PECO Energy personnel at the contractor's expense. Contractors and their personnel shall not touch, handle or attempt to repair any exposed or severed grounding leads.
- 11.0 **STORAGE:** No buildings, storage sheds, trailers, combustible or hazardous materials shall be placed or stored under a transmission line conductor or within 25 feet of a structure.
- 12.0 **CLEAN-UP OPERATIONS:** After completing construction, the contractor shall remove all unused material and debris, re-establish all roads and trails and return the right-of-way to its original condition within thirty (30) calendar days of work completion. The contractor shall notify PECO Energy at the address described in paragraph 5.a. upon completion of the clean-up operations so that PECO Energy may arrange an inspection to assure compliance with these requirements.

**CONDITIONS FOR WORKING IN THE VICINITY OF
ELECTRIC TRANSMISSION LINES OF
PECO ENERGY COMPANY AND ITS SUBSIDIARIES
ELECTRIC CONSTRUCTION STANDARDS**

(6/87) Page 3 of 3 Revised 6/95



PECO ENERGY

S-7070

**GENERAL CONDITIONS REGULATING APPROVED SECONDARY USES
FOR TRANSMISSION LINE RIGHTS-OF-WAY OF
PECO ENERGY COMPANY AND ITS SUBSIDIARIES**

CONTACT WITH POWER LINES CAN RESULT IN DEATH OR SERIOUS BURNS

**CALL PECO ENERGY AT 610-648-7920 OR 610-648-7921 BEFORE WORKING IN THE
VICINITY OF PECO ENERGY ELECTRIC TRANSMISSION LINES**

The following GENERAL CONDITIONS regulate approved secondary uses of PECO Energy transmission line rights-of-way, whether owned in fee or controlled by easement. The acceptable non-transmission line uses are summarized in PECO Energy Electric Construction Standard S-7072, "Secondary Uses for Rights-of-Way Along Electric Transmission Lines."

1.0 UNDERSTANDING

- 1.1** User understands that PECO Energy's business includes construction, installation, maintenance, operation and use of structures, fixtures, facilities and instrumentation, with appurtenances, which now exist or which may hereafter be placed on the right-of-way, which are used or useful for the generation, conversion, transmission or distribution of electricity, or gas or telecommunications services.
- 1.2** User agrees to comply with all requirements of any of the constituted public authorities, and with the terms of any federal or state statute or local ordinance or regulation applicable to the use of the right-of-way, and agrees to indemnify and hold PECO Energy harmless from penalties, fines, costs or damages resulting from User's failure to do so.
- 1.3** User understands that PECO Energy, its successors and assigns, shall have the right to continue to use its rights-of-way for the purposes listed in paragraph 1.1 hereof. PECO Energy reserves the right to require User to relocate or remove any installations, improvements, or plantings. Any relocation or removal shall be accomplished in accordance with the terms and conditions of User's written lease agreement, if applicable, or in accordance with terms and conditions specified by PECO Energy.

2.0 APPROVAL

All proposed secondary uses of PECO Energy rights-of-way shall be subject to the prior written approval of the PECO Energy Real Estate Department, 2301 Market Street, Philadelphia, PA 19101, Telephone (215) 841-5395. All related notifications, submissions and requests for approval, unless otherwise specified, shall be directed to the PECO Energy Real Estate Department.

**GENERAL CONDITIONS REGULATING APPROVED SECONDARY USES
FOR TRANSMISSION LINE RIGHTS-OF-WAY OF
PECO ENERGY COMPANY AND ITS SUBSIDIARIES
ELECTRIC CONSTRUCTION STANDARDS**

12/83 Page 1 of 7 Rev 6/95



PECO ENERGY

S-7074

3.0 SAFETY AND CLEARANCES

CONTACT WITH POWER LINES CAN RESULT IN DEATH OR SERIOUS BURNS. User shall treat all overhead power lines as energized and potentially dangerous. If at any time, construction or other work activities in the vicinity of PECO Energy transmission lines may occur, User and all contractors and subcontractors must obtain from the PECO Energy Real Estate Department the current version of PECO Energy Electric Construction Standard S-7070, "Conditions for Working in the Vicinity of Electric Transmission Lines of PECO Energy Company and its Subsidiaries" and must comply with its provisions. Construction or other work activities in the vicinity of PECO Energy transmission lines without prior notice to PECO Energy in accordance with the S-7070 is potentially dangerous and is absolutely forbidden.

4.0 DRAWINGS

Prior to the start of any construction on the right-of-way, User shall submit to PECO Energy, for its approval, plans prepared in accordance with Electric Construction Standard S-7073, "Evaluation of Proposed Transmission Line Rights-of-Way Secondary Uses."

5.0 RELOCATION

User must obtain the prior written approval of PECO Energy Real Estate Department for any relocation of PECO Energy facilities. Approved relocations shall be performed only by PECO Energy or its agents at User's sole cost and expense.

6.0 INSTALLATION

- 6.1 User agrees that all construction work performed by User or its agents within the right-of-way shall be performed in accordance with accepted engineering practices. User understands that PECO Energy may require the bonding and/or grounding of improvements to eliminate the effects of induced voltage.
- 6.2 User agrees that no charge or assessment for the installation of any underground facility shall be made or imposed upon any part of PECO Energy's right-of-way through which any underground facility passes and User shall save PECO Energy harmless from any such charge or assessment at User's sole cost and expense. PECO Energy shall be permitted to connect to User's facilities without a connection charge.

**GENERAL CONDITIONS REGULATING APPROVED SECONDARY USES
FOR TRANSMISSION LINE RIGHTS-OF-WAY OF
PECO ENERGY COMPANY AND ITS SUBSIDIARIES
ELECTRIC CONSTRUCTION STANDARDS**

12/83 Page 2 of 7 Rev 8/95

S-7074



PECO ENERGY

7.0 EXCAVATIONS

- 7.1 There shall be no construction or excavation within 25 feet of any tower, steel pole structure, wood pole structure or guy anchor without the prior specific written approval of PECO Energy. No construction or excavation shall be permitted in the area between a pole or structure and its associated guy wire anchor. User shall exercise care to prevent cave-ins which could disturb PECO Energy facilities.
- 7.2 User shall comply with the provisions of the Pennsylvania or Maryland One-Call Systems. In Pennsylvania, call 1-800-242-1776. In Maryland, call 1-800-257-7777.
- 7.3 To prevent injuries, User is required to cover all open ditches at night or whenever otherwise unattended.
- 7.4 User agrees that any trenches dug during the installation or subsequent repair of underground facilities shall be properly planked to insure PECO Energy's access across its right-of-way at all times.

8.0 IMPROVEMENTS

User, at User's sole cost and expense, shall install and maintain any public improvements required or necessary for the proposed use, such as sewer or water main extensions, curbs, sidewalks or roadway paving. User also agrees that no charge or assessment shall be made or imposed upon any part of PECO Energy's right-of-way arising or resulting from User's improvements.

9.0 ACCESS

- 9.1 At all times, User shall provide an access route at least 16 feet wide for ingress and egress of PECO Energy vehicles as necessary for the construction and maintenance of its structures and facilities within the right-of-way and adjacent premises, unless this provision is waived in writing by PECO Energy.
- 9.2 When permission is granted by PECO Energy for a highway, road or driveway to cross its right-of-way at an elevation different from the existing elevation of the right-of-way, the construction shall include a ramp from each side of the road to meet the existing right-of-way elevation. Access ramps shall be at least 16 feet wide with a maximum grade of 15%.

10.0 GATES

All fencing within the right-of-way shall include a 16 foot wide gate(s) or wire barricade(s) as described in PECO Energy Electric Construction Standard S-7071, "Right-of-Way Fences, Gates and Barricades."

11.0 LOCKS

PECO Energy shall have the right to install its own lock on any gates within the right-of-way. User shall provide, at its sole cost and expense, a dual/multiple locking system for this purpose.

**GENERAL CONDITIONS REGULATING APPROVED SECONDARY USES
FOR TRANSMISSION LINE RIGHTS-OF-WAY OF
PECO ENERGY COMPANY AND ITS SUBSIDIARIES
ELECTRIC CONSTRUCTION STANDARDS**

12/83 Page 3 of 7 Rev 6/95



PECO ENERGY

S-7074

12.0 EXPLOSIVES

User shall not use or store explosives or flammable materials in any form within the right-of-way.

13.0 DRAINAGE

In order to prevent erosion or other drainage problems and to prevent dirt from being placed above any concrete tower foundations, User shall not alter the grade of the right-of-way except as approved under paragraph four hereof.

14.0 PARKING LOTS AND DRIVEWAYS

PECO Energy shall have the right to use any driveway or parking lot located within the right-of-way without being responsible for any damage caused thereto. User shall construct driveways and parking lots to withstand the weight of vehicles which distribute 38,000 pounds per axle.

15.0 LIMITATION OF DAMAGES FOR PLANTINGS

If required by PECO Energy, User shall remove or relocate plantings blocking access to PECO facilities within 30 days after receiving notice. If prior notice cannot be given or if such removal or relocation is not timely completed, PECO Energy shall gain access to its facilities and compensation for damage to User, if any, shall not exceed pro rata rental for the portion of the right-of-way used by PECO Energy for its corporate purposes.

16.0 UNDERGROUND FACILITIES

16.1 The installation of any underground facilities required by User shall be completed at User's expense, in accordance with the Erosion and Sedimentation Control Regulations of the Pennsylvania Department of Environmental Resources (PA-DER) or any other environmental regulatory agency or governmental agency, and with the minimum possible damage to the ground within the PECO Energy right-of-way.

16.2 Any underground installation shall meet applicable standards for minimum cover unless otherwise specified by PECO Energy. PECO Energy reserves the right to require greater than minimum cover. User is aware PECO Energy intends to cross over underground facilities with vehicles generally weighing 38,000 pounds per axle, and the pipeline(s) shall be installed accordingly. PECO Energy does not warrant that any approved or specified cover will protect the pipeline(s).

16.3 User shall furnish engineering plans of pipeline cathodic protection systems for PECO Energy review and approval prior to installation. Cathodic protection interference tests shall be performed on the completed facility at the expense of User. User shall furnish any other information required by PECO Energy.

**GENERAL CONDITIONS REGULATING APPROVED SECONDARY USES
FOR TRANSMISSION LINE RIGHTS-OF-WAY OF
PECO ENERGY COMPANY AND ITS SUBSIDIARIES
ELECTRIC CONSTRUCTION STANDARDS**

12/83 Page 4 of 7 Rev 6/95

S-7074



PECO ENERGY

16.4 User shall take special care to avoid leakage at pipe joints or seepage into open ditches during the construction, installation, use, maintenance, repair, renewal, removal or replacement of the pipeline(s).

16.4.1 In the event of a leak or a spill involving gasoline, oil or other toxic or hazardous materials or pollutants, User agrees to satisfy all requirements specified by, PECO Energy, the PA DER, the Environmental Protection Agency (EPA), or any environmental regulatory agency or other governmental agency for the cleanup of said leak or spill. User further agrees to assume full responsibility for the cost of the cleanup and any future liability resulting from the leak or spill.

16.5 All proposed pipeline or metallic communication line installations which will longitudinally occupy any transmission line right-of-way for a distance greater than 200 feet must have an inductive interference study completed at User's sole cost and expense and reviewed by PECO Energy prior to construction of the proposed facility.

16.5.1 At a minimum, inductive interference study shall include the following:

16.5.1.1 Induced voltage on the proposed facility at emergency rating of each transmission line (individually) on the right-of-way.

16.5.1.2 Induced voltage on the proposed facility at emergency rating of each distribution line (individually) on the right-of-way.

16.5.1.3 Induced voltage on the proposed facility at emergency rating of all electric lines on the right-of-way.

16.5.1.4 Induced voltage on the proposed facility during a fault (both phase to ground and three phase) on each transmission line on the right-of-way. Faults on the electric transmission lines shall be located at either end of the proposed facility to be installed on the right-of-way and at the middle of the occupation. Fault studies shall also be conducted at any additional locations specified by the PECO Energy engineer.

16.5.1.5 If the proposed facility to be installed on the right-of-way is a bare metal structure (i.e. metal pipe), User shall supply to PECO Energy voltage gradient plots of the area around any transmission structure within 50 feet of the facility. If the voltage gradients around any electric structure increase, User, at its sole cost and expense, must install mitigation prior to the proposed pipeline installation.

**GENERAL CONDITIONS REGULATING APPROVED SECONDARY USES
FOR TRANSMISSION LINE RIGHTS-OF-WAY OF
PECO ENERGY COMPANY AND ITS SUBSIDIARIES
ELECTRIC CONSTRUCTION STANDARDS**

12/83 Page 5 of 7 Rev 6/96



PECO ENERGY

S-7074

16.5.2 Electric transmission and distribution facilities will be added or removed from the right-of-way from time to time. Before PECO Energy adds or removes facilities, the owners of any pipeline or metallic communication line on the PECO Energy right-of-way shall be responsible for completing an initial or revised inductive interference study, submitting it to PECO Energy for review and installing required mitigation, including on PECO Energy's facilities, and at User's sole cost and expense, in a timely manner.

16.5.3 User shall maintain all inductive interference mitigation systems in good operating condition and check for proper operation once each year.

17.0 MARKINGS FOR UNDERGROUND FACILITIES

In order to minimize the number of future dig-ins, User shall be required, as part of any underground installation, to install and maintain at User's expense, permanent markers to identify the location of the underground facility. Pipelines and other similar installations shall be marked where the line enters and exits the right-of-way, at intermediate points along straight runs of pipe and at all angle points where the line changes direction.

18.0 BARRIERS

User shall take precautions to protect PECO Energy structures and facilities, including but not limited to protective barriers. The location of any protective barriers shall be delineated on plans prepared by User and approved by PECO Energy.

19.0 DAMAGE TO PECO ENERGY FACILITIES

User shall be responsible for any damage caused to PECO Energy facilities and shall be required to reimburse PECO Energy for the cost of repairing the damage. All such damage shall be promptly reported to PECO Energy System Operations, (215) 841-5141.

20.0 OUTDOOR ADVERTISING

User shall furnish plans for PECO Energy's prior approval. Plans must show both horizontal and vertical views of User's proposed structure(s) in relationship to PECO Energy facilities.

21.0 INSPECTIONS

User understands and agrees that PECO Energy or its authorized agents have the right to enter the right-of-way at any time for any corporate purpose.

**GENERAL CONDITIONS REGULATING APPROVED SECONDARY USES
FOR TRANSMISSION LINE RIGHTS-OF-WAY OF
PECO ENERGY COMPANY AND ITS SUBSIDIARIES
ELECTRIC CONSTRUCTION STANDARDS**

12/83 Page 6 of 7 Rev 6/95

S-7074



PECO ENERGY

22.0 RESTORATION OF PROPERTY

User agrees upon completion of any work done to: (1) restore the ground to a condition at least equal to that existing prior to such installation, including but not limited to back filling, property tamping and reseeding the surface of the ground above the facilities and, if necessary, refilling and reseeding following any subsequent settlement of the ground in order to maintain the drainage pattern existing prior to such installation; and (2) repair and put into good condition to the satisfaction of PECO Energy, any and all fences and other improvements injured thereby, and landscaping damaged during the course of users work.

23.0 REFERENCES

23.1 PECO Energy Company Electric Construction Standards

23.1.1 S-7070 - "Conditions For Working In the Vicinity of Electric Transmission Lines of PECO Energy Company and Its Subsidiaries"

23.1.2 S-7071 - "Rights-of-Way Fences, Gates and Wire Barricades"

23.1.3 S-7072 - "Secondary Uses For Rights-of-Way Along Electric Transmission Lines"

23.1.4 S-7073 - "Information Required to Evaluate Proposed Transmission Line Rights-of-Way Secondary Uses"

**GENERAL CONDITIONS REGULATING APPROVED SECONDARY USES
FOR TRANSMISSION LINE RIGHTS-OF-WAY OF
PECO ENERGY COMPANY AND ITS SUBSIDIARIES
ELECTRIC CONSTRUCTION STANDARDS**

12/83 Page 7 of 7 Rev 6/95



PECO ENERGY


S-7074

J. Halderman

Exelon®

Business Services
Company

Legal Department
2301 Market Street; S23-1
P.O. Box 8699
Philadelphia, PA 19101-8699



UNITED STATES POSTAL SERVICE
Eagle logo
METRY BOWLS
02 1M \$ 02.58⁰
0004277888 MAR 29 2011
MAILED FROM ZIP CODE 19103

RECEIVED
2011 MAR 31 AM 11:29
P.U.C.
SECRETARY'S BUREAU

Rosemary Chiavetta, Secretary
PA - Public Utility Commission
P.O. Box 3265
Harrisburg, PA 17105