



Before the
Pennsylvania Public Utility Commission

LAKEVILLE 138/69 kV TAP LINE MODIFICATION

**Attachments in Support of the
Letter of Notification**

Application Docket No. _____

Submitted by: PPL Electric Utilities Corp.

SUMMARY


This filing is submitted by PPL Electric Utilities Corporation ("PPL Electric") pursuant to the Pennsylvania Public Utility Commission's ("PUC" or "the Commission") regulations at 52 Pa. Code §§57.71 through 57.77 for PUC approval to construct an additional 70 feet of 138/69 kV transmission tap line outside of PPL Electric's existing Lakeville 69 – 12 kV Substation. The new tap line will provide an attachment point for a mobile substation during maintenance activities. The project is located on land owned in fee by PPL Electric in Paupack Township, Wayne County.

The estimated cost to design and construct this project is \$110,600. Construction is scheduled to begin as soon as possible to support the project's in-service date of November 2011. PPL Electric requests expedited consideration in this matter, in order to meet its in-service date.

This document, which describes the need for the project and discusses the engineering and siting analysis for the proposed construction, consists of the following attachments:

- Attachment 1 - Necessity Statement
- Attachment 2 - Engineering Description
- Attachment 3 - Environmental Assessment
- Attachment 4 - PPL Design Criteria and Safety Practices
- Attachment 5 - PPL Electric Magnetic Field Management Program
- Attachment 6 - List of Involved Governmental Agencies, Municipalities, and Other Public Entities

PPL ELECTRIC UTILITIES SERVICE TERRITORY



Attachment

1

ATTACHMENT "1"
LAKEVILLE 138/69 kV TAP LINE MODIFICATION
NECESSITY STATEMENT

TABLE OF CONTENTS

<u>SECTION</u>	<u>TOPIC</u>	<u>PAGE</u>
A.	INTRODUCTION.....	1
B.	EXISTING SYSTEM.....	2
C.	DEFINITION OF THE PROBLEM.....	2
D.	PROPOSED SOLUTION.....	2
E.	FUNCTIONAL ALTERNATIVES.....	2

LIST OF FIGURES

FIGURE 1	FUNCTIONAL ONE-LINE DIAGRAM OF EXISTING TRANSMISSION SYSTEM.....	3
FIGURE 2	FUNCTIONAL ONE-LINE DIAGRAM OF PROPOSED TRANSMISSION SYSTEM.....	4

MAP

MAP 1	PPL ELECTRIC SYSTEM MAP.....	ATTACHMENT "1" MAP POCKET
-------	------------------------------	---------------------------------

ATTACHMENT "1"
LAKEVILLE 138/69 kV TAP LINE MODIFICATION
NECESSITY STATEMENT

A. INTRODUCTION

PPL Electric is requesting PUC approval to install a 70-foot 138/69 kV tap line on PPL Electric property adjacent to its existing Lakeville 69 – 12 kV Substation. The proposed modification to the tap line will allow for the temporary installation of a mobile substation whenever maintenance of the existing substation is required. The mobile substation will allow maintenance to be performed without interrupting electric service to PPL Electric customers. The proposed tap line will also make possible upgrade of the existing Lakeville Substation to a modified Twin "A" configuration substation¹ without interruption of service when increasing demand makes this conversion appropriate.

The estimated cost to design and construct the proposed tap line is approximately \$110,600. Construction is scheduled to begin as soon as possible to meet a required in-service date of November 2011. The required in-service date is defined as the date the proposed facility needs to be placed in service to meet periodic maintenance schedules without interrupting service to customers.

A PPL Electric system map showing existing transmission facilities with a design voltage of 35 kV or greater is included in the map pocket at the end of Attachment 1. This filing addresses only the existing and proposed 138 kV system in the (Paupack) area.

¹ A Twin-A design is, essentially, two substations built right next to each other. Electrical load can be transferred from one side to the other to restore load in emergencies or to facilitate maintenance of certain electrical equipment.

B. EXISTING SYSTEM

Presently, Lakeville Substation contains two 69 – 12 kV transformers. They are supplied by the existing single-circuit Blooming Grove – Honesdale 138/69 kV line via the existing Lakeville 138/69 kV Tap Line.

C. DEFINITION OF THE PROBLEM

Presently, the Lakeville 69 – 12 kV Substation cannot be de-energized to perform some of the maintenance required to keep the substation operating reliably without interruption of service to customers. The 12 kV distribution ties are insufficient to transfer customer load away from the substation to perform the required maintenance.

D. PROPOSED SOLUTION

To prevent an outage during maintenance activities, PPL Electric is proposing to install a short, 70-foot 138/69 kV tap line outside the existing substation to allow service to be furnished temporarily using a mobile substation. The mobile substation will temporarily carry the customer load during scheduled maintenance activities. It could also be used to restore service during a forced outage.

E. FUNCTIONAL ALTERNATIVE

An alternative to installing this project would be to turn the existing substation into a modified Twin-A design, which would include multiple modifications to the substation and cost approximately \$343,000.




FIGURE 1 - FUNCTIONAL ONE-LINE DIAGRAM OF EXISTING TRANSMISSION SYSTEM




FIGURE 2 - FUNCTIONAL ONE-LINE DIAGRAM OF PROPOSED TRANSMISSION SYSTEM

SUBSTATION LISTING

1	WEST WILLIAMSPORT	151	CRACKERSVILLE	301	CENTER CITY
2	FAIRFIELD	152	HEMLOCK	302	NEW KINGSTOWN
3	MONTGOMERY	153	MT. ALLEN	303	REAMSTOWN
4	VARDEN	154	PRINCE	304	DUPONT
5	HONESDALE	155	WAKEFIELD	305	HUMBOLDT
6	JERSEY SHORE	156	COOPERSBURG	306	CEDAR AVE.
7	VALMONT	157	VERTZVILLE	307	INDIAN ORCHARD
8	RIVER	158	WEST CARLISLE	308	NOTTINGHAM
9	LIMESTONE	159	BENVENUE	309	NORTH COOLBAUGH
10	NORTH HUNTERLAND	160	HEGINS	310	LETORT
11	REED	161	LEOLA	311	EAST MOUNTAIN
12	WRIGHT	162	YATESVILLE	312	JERMYN
13	ST. JOHNS	163	CENTRAL ALLENTOWN	313	BLOOMSBURG
14	FREELAND	164	DBERLIN	314	MIFFLINTOWN
15	GILBERT	165	STRASBURG	315	RIDGE ROAD
16	CHERRY HILL	166	T-10 SW. Y.D.	316	SUSQUEHANNA
17	SUSQUEHANNA 230KV	167	BROOKSIDE	317	KIMBLES
18	TAMANEAD	168	VILLIAMSTOWN	318	CHRISTMANS
19	WHITE HILL	169	E. PETERSBURG	319	HUMMELSBURG
20	PALMERTON	170	VERMERSVILLE	320	JACK FROST
21	HAMILTON	171	N. BETHLEHEM	321	MCGOVERNVILLE
22	HUNTER	172	W. ALLENTOWN	322	ROBSONIA
23	FAIRVIEW	173	FLEMINGTON	323	SFDGELSVILLE
24	MONTOUR PUMP	174	MECKESVILLE	324	ELROY
25	MT. CARMEL	175	DOONERVILLE	325	BUSHKILL
26	KELL	176	MILLERSVILLE	326	WALLENPAUPACK
27	SPRING HILL	177	SHILLINGTON	327	ELK MOUNTAIN
28	MAHANY CITY	178	DUKE	328	JACK FROST
29	GREENWOOD	179	MCALLISTERVILLE	329	HARWOOD 230/69KV
30	MIDWAY	180	WOLFENDLAND	330	HARWOOD CTG
31	ALTA MOUNT	181	MARLIN	331	HARWOOD 69/12KV
32	HAMLIN	182	WEST BERWICK	332	NAZARETH
33	ASHFIELD	183	KEYSER AVENUE	333	ALBURTIS
34	SOUTH SLATINGTOWN	184	EAST ALLENTOWN	334	FRACKVILLE
35	SOUTH MIDDLEBURG	185	PINE RIDGE	335	DALMATIA
36	WALKER	186	PENNSBURD	336	ELIMSPORT
37	FRILEY	187	NORTH COLUMBIA	337	ALLENWOOD
38	WEISS TOWN	188	HUGHESVILLE	338	GRATZ
39	EGYPT	189	SOUTH ALLENTOWN	339	HOCKERSVILLE
40	CRESSONA	190	WEISSPORT	340	BLOOMING GROVE
41	SOUTH WHITEHALL	191	HONEYBROOK	341	MOSCOW
42	SALISBURY	192	ROSSMOYNE	342	MONROE
43	WILMINGTON MILTON	193	NORTH HAMPTON	343	LACKAWANNA #
44	HEIDELBERG	194	WIDORICH	344	STANTON
45	LYKENS	195	FAXON	345	JACKSON
46	UPPER HANDOVER	196	ELIZABETHTOWN	346	EAST PALMERTON
47	RICHLAND	197	ENOLA	347	SIEGFRIED
48	MACADA	198	TERRE HILL	348	HOSENSACK 230/69KV
49	ROCKVILLE	199	BUCK	349	HOSENSACK 500KV
50	THOMPSON TOWN	200	MT. BETHEL	350	CDNE STGA
51	PAXTON	201	RICHFIELD	351	MANOR
52	COCALICO	202	SCRANTON	352	CLINTON
53	EAST ELIZABETHTOWN	203	TWIN LAKES	353	EXCHANGE
54	WARWICK	204	HARLEIGH	354	MILTON
55	EARL	205	FAIRFAX	355	DAUPHIN
56	HEMPFIELD	206	BEAR CREEK	356	QUARRY SUB.
57	EAST LANCASTER	207	DRWIGSBURG	357	STEELTON
58	KINZER	208	EAST TEXAS	358	JUNIATA 500/230KV
59	MT. NEBO	209	CANDENSIS	359	JUNIATA 230/69KV
60	MT. POCONO	210	LINDEN	360	CUMBERLAND
61	PENNS	211	MT. JOY	361	DONEGAL
62	GOULDSBORO	212	WEST BLOOMSBURG	362	JENKINS 230/69KV
63	DILLERSVILLE	213	MINSI TRAIL	363	JENKINS CTG
64	GIRARD MANOR	214	LAKE NAOMI	364	WILKES-BARRE
65	KENMAR	215	ANARK	365	BUXMONT
66	GOWEN CITY	216	MONTOURSVILLE	366	SOUTH AKRON 230/138/69KV
67	ELLIOT HEIGHTS	217	PORT CARBON	367	SOUTH AKRON 69/12KV
68	ROHRERSTOWN	218	BLYTHEBURN	368	SOUTH MANHEIM 69/12KV
69	MACHIGNE	219	MILFORD	369	SOUTH MANHEIM 230/69KV
70	EAST HAZLETON	220	TREICHLERS	370	ENGLISIDE
71	WAGNERS	221	ROSEVILLE	371	COLUMBIA
72	EAST CARBONDALE	222	RUTHERFORD	372	DANVILLE
73	EYND	223	HARTLAND	373	SUNBURY
74	MINDOKA	224	PARRISH	374	HUMMELN WHARF
75	DLD FORGE	225	POINT NEW HOLLAND	375	LYCOMING
76	FOUNTAIN SPRINGS	226	WEST	376	LOCK HAVEN CTG
77	SULLIVAN TRAIL	227	WIDDLTON	377	LOCK HAVEN 69/12KV
78	SWATARA	228	STATE HILL	378	HUMMELSTOWN
79	HEPBURN	229	MILLVILLE	379	WEST SHORE
80	HATFIELD	230	TINKER	380	NONTAGE
81	HERSHEY	231	LAKEVILLE	381	SOUTH FARMERSVILLE
82	S. HERSHEY	232	NORTH MANHEIM	382	WESCOVILLE
83	S. WILLIAMSPORT	233	HATFIELD	383	FISHBACH
84	FOGELSVILLE	234	HERSHEY	384	BERKS
85	WINDSOR	235	S. HERSHEY	385	MONTOUR
86	W. WILLOW	236	S. WILLIAMSPORT	386	SUBURBAN YARD
87	WESTGATE	237	FISHBACH	387	ELLA
88	ELLA	238	WINDSOR	388	SUMMERDALE
89	SUMMERDALE	239	W. WILLOW	389	DORNEYVILLE
90	DORNEYVILLE	240	WESTGATE	390	BOHEMIA
91	BOHEMIA	241	ELLA	391	WHITE HAVEN
92	WHITE HAVEN	242	SUMMERDALE	392	LAURELTON
93	FRANCONIA	243	DORNEYVILLE	393	LINGESTOWN
94	EMMAUS	244	BOHEMIA	394	POCONO FARMS
95	MIRIAM	245	WHITE HAVEN	395	HICKORY RUN
96	THORNTON	246	LAURELTON	396	BLOOMING GLEN
97	WINDSOR	247	LINGESTOWN	397	SHERMANSDALE
98	W. WILLOW	248	POCONO FARMS	398	LARRY'S CREEK
99	CHAPMAN	249	HICKORY RUN	399	SPANGLER HILLS
100	SUBURBAN	250	BLOOMING GLEN	400	E. DANVILLE
101	ELLA	251	SHERMANSDALE	401	DELAND
102	SUMMERDALE	252	LARRY'S CREEK	402	CARBON
103	DORNEYVILLE	253	SPANGLER HILLS	403	SELLERSVILLE
104	BOHEMIA	254	E. DANVILLE	404	MECHANICSBURG
105	WHITE HAVEN	255	DELAND	405	CARLISLE
106	LAURELTON	256	CARBON	406	RED FRONT
107	LINGESTOWN	257	SELLERSVILLE	407	APPENZEL
108	POCONO FARMS	258	MECHANICSBURG	408	NEWPORT
109	HICKORY RUN	259	CARBON	409	HALIFAX
110	BLOOMING GLEN	260	SELLERSVILLE	410	MILLERSBURG
111	SHERMANSDALE	261	MECHANICSBURG	411	MUNCY
112	LARRY'S CREEK	262	CARBON	412	BERWICK
113	SPANGLER HILLS	263	SELLERSVILLE	413	SHENANDOAH
114	E. DANVILLE	264	MECHANICSBURG	414	PINE GROVE
115	DELAND	265	CARBON	415	STROUDSBURG
116	CARBON	266	SELLERSVILLE	416	FREEMANSBURG
117	SELLERSVILLE	267	MECHANICSBURG	417	ALLENTOWN
118	MECHANICSBURG	268	CARBON	418	BINGEN
119	CARLISLE	269	SELLERSVILLE	419	RHEIMS
120	RED FRONT	270	MECHANICSBURG	420	CLEVELAND
121	APPENZEL	271	CARBON	421	LITTLE GAP
122	NEWPORT	272	SELLERSVILLE	422	BRVILLA
123	HALIFAX	273	MECHANICSBURG	423	TUSCARORA
124	MILLERSBURG	274	CARBON	424	BARTINSVILLE
125	MUNCY	275	SELLERSVILLE	425	ALTON PARK
126	BERWICK	276	MECHANICSBURG	426	SALEM
127	SHENANDOAH	277	CARBON	427	NORTH BRIDGEPORT
128	PINE GROVE	278	SELLERSVILLE	428	HAMPDEN
129	STROUDSBURG	279	MECHANICSBURG	429	CAMELBACK
130	FREEMANSBURG	280	CARBON	430	SILVER SPRING
131	ALLENTOWN	281	SELLERSVILLE	431	BRECKNOCK
132	BINGEN	282	MECHANICSBURG	432	BENTON
133	RHEIMS	283	CARBON	433	MCMICHAELS
134	CLEVELAND	284	SELLERSVILLE	434	HUGHES TOWN
135	LITTLE GAP	285	MECHANICSBURG	435	NEWVILLE
136	BRVILLA	286	CARBON	436	POINTE NORTH
137	TUSCARORA	287	SELLERSVILLE	437	MARIETTA
138	BARTINSVILLE	288	MECHANICSBURG	438	
139	ALTON PARK	289	CARBON	439	
140	SALEM	290	SELLERSVILLE	440	
141	NORTH BRIDGEPORT	291	MECHANICSBURG	441	
142	HAMPDEN	292	CARBON	442	
143	CAMELBACK	293	SELLERSVILLE	443	
144	SILVER SPRING	294	MECHANICSBURG	444	
145	BRECKNOCK	295	CARBON	445	
146	BENTON	296	SELLERSVILLE	446	
147	MCMICHAELS	297	MECHANICSBURG	447	
148	HUGHES TOWN	298	CARBON	448	
149	NEWVILLE	299	SELLERSVILLE	449	
150	POINTE NORTH	300	MECHANICSBURG	450	
	MARIETTA				


* - SUBSTATIONS THAT HAVE BEEN RETIRED.
 ** - SITE OF THE EXISTING 230KV SUBSTATION AND PROPOSED 500KV SUBSTATION

INTERCONNECTIONS

PS PUBLIC SERVICE ELECTRIC AND GAS CO. OF N.J.
 ME METROPOLITAN EDISON CO. (FIRST ENERGY)
 PE PHILADELPHIA ELECTRIC CO. (PECO ENERGY)
 BC BALTIMORE GAS AND ELECTRIC CO.
 SW SAFE HARBOR WATER POWER CORPORATION
 UP THE UNITED GAS IMPROVEMENT CO. - LUZERNE ELECTRIC DIVISION
 PN PENNSYLVANIA ELECTRIC CO. (FIRST ENERGY)
 JC JERSEY CENTRAL POWER AND LIGHT CO. (FIRST ENERGY)

- COMBUSTION TURBINE
- HYDRO ELECTRIC
- COMBINATION
- FIRM SALES
- STATION / SWITCHING STATION
- STEAM ELECTRIC
- NON-UTILITY GENERATION
- INDEPENDENT POWER PRODUCERS

- 500KV OPERATION
- 230KV OPERATION
- 138KV OPERATION
- 69KV OPERATION



LAKEVILLE 138/69 KV TAP LINE MODIFICATION

ACCT - 805201	ELECTRICAL SYSTEM MAP		
SCALE - NONE	LAKEVILLE 138/69 KV TAP		
BY - CDW	LINE MODIFICATION		
APPROVED G. HAKUN III	DATE 7/1/05	PPL ELECTRIC UTILITIES	
PPL DRAWING NO. D191830	SHEET NO.	REV.	
		1	79

76	11/30/01	10014288	ADDED MANOR - GRACETON 230KV LINE RECONSTRUCTION	MG	RWM	DG
79	11/31/01	161703	ADDED LAKEVILLE 138/69KV TAP - LINE MODIFICATION	MG	RWM	KBK
78	12/21/01	10013990	ADDED BRUNNER ISLAND W SHORE 230KV LINE REBUILD SINGLE CIR.CUIT TO DB CIRCUIT.	RRC		JW
77	12/28/01	0014966	INDICATE TOBYHANNA #1 & #2 138/69 KV TAP.	RRC		DG
	BY	REVIEWED	APPROVED			

PPL CU FORM 4877 (7/03)

Attachment

2

ATTACHMENT "2"
LAKEVILLE 138/69 kV TAP LINE MODIFICATION
ENGINEERING DESCRIPTION

TABLE OF CONTENTS

<u>SECTION</u>	<u>TOPIC</u>	<u>PAGE</u>
A.	DESCRIPTION OF PROPOSED LINE	1
B.	MAGNETIC FIELD MANAGEMENT.....	3
C.	RIGHT-OF-WAY STATUS.....	3

LIST OF TABLES

TABLE 1	DESIGN MINIMUM CONDUCTOR CLEARANCES.....	2
TABLE 2	CONDUCTOR THERMAL RATINGS	2

MAP

SHEET 1	AERIAL EXHIBIT – DRAWING.....	ATTACHMENT "2" MAP POCKET
---------	-------------------------------	---------------------------------

ATTACHMENT "2"
LAKEVILLE 138/69 kV TAP LINE MODIFICATION
ENGINEERING DESCRIPTION

A. DESCRIPTION OF PROPOSED LINE

PPL Electric proposes to install a 138/69 kV tap line outside the existing Lakeville 69-12 kV Substation. The proposed tap line will provide attachment points for a mobile substation, as well as provide for the future upgrade of the existing Lakeville Substation to a modified Twin-A configuration substation.

The proposed tap line will be approximately 70 feet long. One existing wood pole, approximately 79 feet tall, will be replaced with a steel monopole of similar height. One new steel monopole, also approximately 79 feet tall, will be installed. Both poles will be direct-embedded, guyed monopoles. The proposed tap will consist of three power conductors and one overhead ground wire. The power conductors will be 556.5 kcmil (thousands of circular mils)² 24/7 strand ACSR.³ The 3/8" diameter steel overhead ground wire will provide lightning protection for the proposed tap line.

The proposed line will be designed to meet, and will generally exceed, National Electrical Safety Code ("NESC") standards. Design specifications and safety rules practiced by PPL Electric are included in Attachment 4. The minimum ground clearance for the proposed tap is 50 feet, which will far exceed the NESC required ground clearance of 21 feet, and will exceed the 30-foot minimum ground clearance recommended in PPL Electric's Magnetic Field Management Plan. The designed minimum conductor clearances and conductor thermal ratings are as follows:

² A circular mil is the cross-sectional area of a wire one mil in diameter, where 1 kcmil = 0.5067 mm².

³ Aluminum conductor steel reinforced.

TABLE 1
DESIGN MINIMUM CONDUCTOR CLEARANCES
FOR 556.5 KCMIL 24/7 STRAND ACSR⁴

<u>Condition</u>	<u>Double-Circuit Design Clearance-to-Ground</u>
Normal load, average weather (16°C ambient, 60°F temperature)	50.7'
Predicted extreme thermal load (125°C conductor, 257°F temperature)	50.3'
Predicted NESC extreme wind load conditions (25 lbs., 16°C, 60°F temperature)	50.7'
Predicted extreme weather conditions, 0°F (1-inch ice, 4 lbs. wind, -18°C)	51.0'

TABLE 2
CONDUCTOR THERMAL RATING
556.5 KCMIL 24/7 ACSR
125°C MAXIMUM CONDUCTOR TEMPERATURE

<u>Condition</u>	<u>Ambient Temperature °C</u>	<u>Wind Speed Knots</u>	<u>Ampacity Amps</u>
Summer Normal	35	0	815
Winter Normal	10	0	926
Summer Emergency	35	1.5	1041
Winter Emergency	10	1.5	1163

⁴ Clearances based on a maximum tension of 1488 pounds at 1 inch ice, 4 pounds wind, 0° and a ruling span of 70 feet.

B. MAGNETIC FIELD MANAGEMENT

PPL Electric's Magnetic Field Management Program, summarized in Attachment 5, is applied to new and reconstructed transmission line projects. To reduce magnetic field exposures, the program generally prescribes the use of a line design that provides five feet higher ground clearances, and reverse phasing new double-circuit lines where it is feasible to do so at low or no cost. The implementation of additional modifications will be considered, provided those modifications can be made at low or no cost.

Since the proposed tap line is being designed for single-circuit operation only, reverse phasing cannot be utilized. However, the minimum ground clearance for the proposed tap is 50 feet, which will far exceed the 30-foot minimum ground clearance recommended in PPL Electric's Magnetic Field Management Plan.

C. RIGHT-OF-WAY STATUS

The entire project will be constructed on PPL Electric property. No additional right-of-way is required.



LEGEND


EXISTING TRANSMISSION LINE	
PROPOSED TRANSMISSION LINE	
EXISTING RIGHT-OF-WAY	
EXISTING PROPERTY LINE	
PROPOSED TRANSMISSION POLE	

Property Number	Property Owner
1	PPL ELECTRIC UTILITIES

ATTACHMENT 2

AERIAL EXHIBIT SHEET 1

**LAKEVILLE 138/69 kV TAP -
LINE MODIFICATION**
PAUPACK TOWNSHIP
WAYNE COUNTY, PA.



PREPARED BY:
PPL ELECTRIC UTILITIES CORP.
PPL ELECTRIC UTILITIES



ACCT- SCALE - 1"=200'	LAKEVILLE 138/69 kV TAP LINE MODIFICATION	
BY-		
REVIEWED	PAUPACK TOWNSHIP	WAYNE COUNTY
	APPROVED	DATE
	PPL ELECTRIC UTILITIES	
PPL DRAWING NO.	SHEET NO.	REV.
ATTACHMENT 2	1 of 1	0

NO.	DATE	ACCT.	REVISION	BY	REVIEWED



LOCATION CODES

PC CAD

PPL ELECTRIC UTILITIES/01

PC CAD

Attachment

3

ATTACHMENT "3"
LAKEVILLE 138/69 kV TAP LINE MODIFICATION
ENVIRONMENTAL ASSESSMENT

TABLE OF CONTENTS

<u>SECTION</u>	<u>TOPIC</u>	<u>PAGE</u>
A.	INTRODUCTION.....	1
B.	LAND USE.....	1
C.	CULTURAL RESOURCES.....	2
D.	NATURAL FEATURES.....	2
E.	THREATENED AND ENDANGERED SPECIES.....	3

ATTACHMENT "3"
LAKEVILLE 138/69 kV TAP LINE MODIFICATION
ENVIRONMENTAL ASSESSMENT

A. INTRODUCTION

PPL Electric is requesting PUC approval to site and construct a short, single-circuit tap off of the existing Lakeville 138/69 kV Tap Line to allow PPL Electric to connect a mobile substation at the site of the existing Lakeville 69-12 kV Substation during maintenance activities or forced outages of the substation. To be compatible with the existing Lakeville Tap Line, this modification will be designed and built to operate at 138 kV, although initially, it will be operated at 69 kV. The entire project will be constructed on property owned by PPL Electric, at the site of the existing Lakeville 69-12 kV Substation.

The proposed project was reviewed with representatives of Paupack Township and Wayne County, and neither the Township nor the County has any objection. A list of involved governmental agencies, municipalities, and other public entities is presented in Attachment 6.

B. LAND USE

The Lakeville Substation is located near the intersection of Purdytown Pike (PA 590) and Daniels Road, in Paupack Township, Wayne County. The area surrounding the substation is generally wooded to the north and south, and agricultural to the east and west, with a few scattered homes in the area. Due to its small scale and remote location, PPL Electric anticipates that this project will have no incremental impacts on the area.

One communications tower is located in the area, on a land parcel adjacent to the existing Lakeville Substation. Installation of the Lakeville Substation pre-dates the installation of the communications tower. Therefore, the modification to the

tap line will have no impact on this communications tower. There are no railroads, pipelines or other utilities in the immediate area. Port Florence Airport is the nearest airport to the proposed site. It is approximately 2.4 miles away. Due to the distance from the airport, and the fact that existing topographic and structural features between the proposed project site and the runway are higher than the proposed modifications to the tap line, there will be no hazard to the airport's flight operations and notification to the FAA and PennDOT Bureau of Aviation is not required.

C. CULTURAL RESOURCES

The project was reviewed by the Pennsylvania Historical and Museum Commission ("PHMC"). The PHMC has determined that there are no National Register eligible or listed historic or archaeological sites in the area.⁵ Therefore, there are no anticipated impacts to such resources and no further investigation is required.

D. NATURAL FEATURES

The project, as proposed, will not affect any unique geological, scenic or natural areas. The nearest recreational area to the proposed project location is Lake Wallenpaupack, located over ¾ of a mile to the south and east. The nearest natural landmark is Lake Lacawac, which is located approximately 3.9 miles south of the proposed site. Due to the small scale of the project, and the distance from these natural features, no impact is expected.

No tree clearing is required. The line will not cross any wetlands or other aquatic resources, and access roads are already in-place. PPL Electric will employ its "Specification for Soil Erosion and Sedimentation Control on Transmission Line Rights-of-Way" as applicable.

⁵ PHMC File No. ER 2011-0662-127-A.

E. THREATENED AND ENDANGERED SPECIES

PPL Electric has coordinated with the relevant state and federal agencies to obtain information regarding endangered and threatened species that could occur in the study area. All agencies report that, except for occasional transient species of wildlife, no threatened or endangered plant or animal life is found in the project area.⁶

⁶ PNDI Search ID: 20101209274235.

Attachment

4

LIST OF SUPPLEMENTAL ATTACHMENTS

- ATTACHMENT "4"** PPL Design Criteria and Safety Practices
- ATTACHMENT "5"** PPL Magnetic Field Management Program
- ATTACHMENT "6"** List of Involved Governmental Agencies, Municipalities
and Other Public Entities

ATTACHMENT 4

PPL ELECTRIC DESIGN CRITERIA AND SAFETY PRACTICES

The National Electrical Safety Code (NESC) is a set of rules to safeguard people during the installation, operation, and maintenance of electric power lines. The NESC contains the basic provisions considered necessary for the safety of employees and the public. Although it is not intended as a design specification, its provisions establish minimum design requirements. PPL Electric Utilities Corp. (PPL Electric) has developed design specifications and safety rules which meet or surpass all provisions specified by the NESC.

Engineering Design Criteria and Parameters

The NESC includes loading requirements and clearances for the design, construction, and operation of power lines. The "loads" on conductors and supporting structures are the mechanical forces that develop from the weight of the conductors, the weight of ice on the conductors, plus wind pressure on the conductors and supporting structures. Loading requirements are the loads on the conductors and structures that are anticipated assuming certain ice and wind conditions. Loading requirements always contain "safety factors" to allow for unknown or unanticipated contingencies. The clearances and loading requirements contained in the NESC were developed to ensure public safety and welfare.

PPL Electric transmission line design standards meet or surpass the NESC standards. For example, the relative order of grades of construction for conductors and supporting structures is B, C, and N; Grade B being the highest. According to the NESC standards, construction Grades B, C, or N may be used for transmission lines (except at crossings of railroad tracks and limited access highways where Grade B construction is specified). However, PPL Electric designs all of its transmission lines for Grade B construction. The use of Grade B design and construction specifies such things as larger-minimum crossarm dimensions, larger-minimum conductor size, and increased safety factors.

Another example is the design parameters utilized to account for ice and wind loadings on the overhead ground wire (OHGW) and power conductors. The NESC standard ice and wind design magnitudes for the PPL Electric territory are 0.5 inch thickness of radial ice combined with four pounds per square foot horizontal wind pressure (equivalent to 40-mile per hour wind velocity). The conductor sags and tensions used in line designs are the result of various ice and wind combinations, depending on the elevation at the line location and line design voltage. The conductor sags and tensions used in the design of all PPL Electric transmission lines are at least 0.5-inch ice combined with eight pounds wind pressure (equivalent to 57 miles per hour wind velocity). This means that PPL Electric lines are designed to operate safely and reliably during inclement weather even more severe than assumed by the NESC. In addition, PPL Electric transmission lines are designed with more clearance to the ground than required by the NESC. The tables below compare PPL Electric and NESC ground clearances for lines of various voltages.

138 kV

<u>Surface Underneath Conductors</u>	<u>Vertical Clearance to Ground</u>	
	<u>NESC Standard</u>	<u>PPL Electric Design</u>
Roads, streets, alleys	21 Ft.	30 Ft.
Other land traversed by vehicles (such as cultivated field, forest, etc.)	21 Ft.	30 Ft.
Spaces accessible to pedestrians only	17 Ft.	30 Ft.
Railroad tracks	31 Ft.	35 Ft.

230 kV

Surface Underneath Conductors

Vertical Clearance to Ground
NESC Standard PPL Electric
Design

Roads, streets, alleys	23 Ft.	32 Ft.
Other land traversed by vehicles (such as cultivated field, forest, etc.)	23 Ft.	32 Ft.
Spaces accessible to pedestrians only	19 Ft.	32 Ft.
Railroad tracks	31 Ft.	36 Ft.

500 kV

Surface Underneath Conductors

Vertical Clearance to Ground
NESC Standard PPL Electric
Design

Roads, streets, alleys	28 Ft.	53 Ft.
Other land traversed by vehicles (such as cultivated field, forest, etc.)	28 Ft.	53 Ft.
Spaces accessible to pedestrians only	24 Ft.	53 Ft.
Railroad tracks	38 Ft.	53 Ft.

A relay protection system is used to protect the public safety and welfare as well as equipment and the transmission system. Relay protection is installed for all transmission lines to automatically de-energize the line in the unlikely event that the line or supporting structure fails and the line contacts the ground.

Periodic Maintenance Program on All Transmission Lines

To ensure continued public safety and integrity of service, a periodic maintenance and inspection program is implemented for every transmission line. The program is administered through the use of helicopter patrols, with supplemental foot and structure climbing patrols. A number of helicopter patrols are performed on all lines annually. The two-man helicopter crew flies parallel, to the left, and above the line so that the observer can look for signs of line damage or deterioration and observe clearances between vegetation and conductors. The observations are included in a report that is forwarded to the appropriate department for corrective action.

Foot and structure climbing patrol programs for a transmission line begin approximately three to five years after the line is energized, unless a helicopter patrol reports a need for earlier action. The frequency of foot patrols varies from once every year to once every several years depending on line type and age.

An assigned foot patroller checks right-of-way conditions, including access roads, bridges, pole washouts, tower footers, vegetation height and clearance to conductors, pole and tower deterioration and, with the use of binoculars, insulators, and condition of hardware. Identified problems are included in a report that is forwarded to the appropriate department for corrective action.

A scheduled line outage is required to perform an overhead patrol because of "hands-on" inspection of hardware. Overhead patrols are conducted on a schedule determined by line age, operating record, and observed general condition. The necessary repairs are also done during the inspection outage.

Personnel Safety Rules

The following are a few of the PPL Electric safety rules that demonstrate the Company's concern for employee safety:

- Work procedures have been developed to allow work to be performed on energized facilities in a safe manner. When lines or apparatus are removed from service to be worked on, the Energy Control Process system is applied. This system provides that a red tag must be physically placed on the control handle of the de-energized equipment. The red tag may be removed only after proper authorization to energize the equipment. Various other tags are used for limited

operations and informational purposes. Employees will not apply or remove a tag or change the status of tagged equipment unless authorized.

- Temporary safety grounds are used on de-energized facilities for employee safety during maintenance, construction, or reconstruction work. Safety grounds are wires connecting the de-energized facility to an electrical ground. If the facility should be energized, the safety grounds will divert the current directly to ground and reduce the likelihood of personal injury. The conductor size and attachment clamps of temporary safety grounds must be capable of conducting anticipated fault currents. Rubber gloves, rubber sleeves, and additional rubber protective equipment are used as required when applying or removing temporary safety grounds to or from the lines or apparatus to be grounded. An approved nonconductive working stick of sufficient length to allow workers to maintain the following required minimum clearances is used to test that the line has been de-energized and to apply temporary safety grounds:

<u>Voltage-kV</u>	<u>Minimum Clearance</u>
138	3'-7"
230	5'-3"
500	11'-3"

Before applying grounds, a test is done to confirm that the line is de-energized. The voltage test device is checked before and after use to assure reliability. When ground pins are used to establish proper ground points, they are driven to a depth of not less than four feet as near vertical as possible.

- Poles or structures are inspected and examined for structural integrity before climbing. If there is any reason to believe that a pole is unsafe, it is stabilized before work is performed. Appropriate safety gear in the form of body belts, safety straps, hard hats, gloves, etc., is worn by linemen during line work activity.

Attachment

5



**MAGNETIC
FIELD
MANAGEMENT**
PPL Electric Utilities
Corporation

ATTACHMENT 5

DECEMBER 2004

TABLE OF CONTENTS

INTRODUCTION	1
DEVELOPMENT OF PPL EU's MAGNETIC FIELD MANAGEMENT PROGRAM.....	6
VARIABLES THAT AFFECT MAGNETIC FIELDS	6
Effect of Phase Current on Magnetic Fields	6
Effect of Conductor Configuration on Magnetic Fields	7
Effect of Distance from the Magnetic Field Source	7
SUMMARY OF PPL EU's MAGNETIC FIELD MANAGEMENT PROGRAM.....	8
MAGNETIC FIELD MANAGEMENT PROGRAM GUIDELINES	9
Overhead Lines	9
New or Rebuilt Transmission Lines	9
Reconductoring or Adding Additional Circuits to Existing Transmission Lines	14
Distribution Lines	14
Underground Transmission Lines.....	15
CHARTS.....	16

INTRODUCTION

At PPL Electric Utilities Corp. (PPL EU), magnetic field management means investigating and implementing methods at low or no cost to reduce magnetic fields in new or rebuilt transmission and distribution lines. This document explains PPL EU's Magnetic Field Management Program, which is part of PPL EU's larger Electric and Magnetic Fields (EMF) policy.

PPL EU's View

Some people are worried that electric and magnetic fields are harming their health. Others think the scientific research does not show a problem at all, and still others believe there's just too much scientific uncertainty to draw any conclusions.

Here's what we do know now. Various panels of scientists that have reviewed the EMF research generally have drawn two main conclusions. First, the large body of evidence does not demonstrate that EMF are harmful. Second, additional research is recommended to explore questions raised in some studies.

Given these conclusions, PPL EU is taking a reasoned approach in responding to the EMF issue. PPL EU's approach to the EMF issue consists of five elements:

- Providing EMF information to customers and employees
- Providing magnetic field measurements
- Establishing and implementing a magnetic field management program to reduce magnetic fields in new or rebuilt facilities when it can be done at no, or low, cost
- Integrating EMF in the public involvement process that PPL EU undertakes in the siting of transmission lines
- Have supported additional research

EMF Are All Around Us

Electric and magnetic fields occur in nature and in all living things. The earth, for instance, has a magnetic field, which makes the needle on a compass point north.

Electric fields and magnetic fields of a different type also surround every wire that carries electricity. In everyday life, these EMF arise from several basic sources, including power lines, electrical appliances, home and building wiring, other utility lines and cables, and currents flowing on water pipes. Though they often occur together, EMF are made up of two separate components:

Electric Fields

Electric fields are produced by the voltage—or electrical pressure—on a wire. The higher the voltage, the higher the electric field. As long as a wire is energized—has voltage present—an electric field is present (see Figure 1). In other words, an appliance, or an electric power line, doesn't actually have to be turned on to create an electric field. It just has to be plugged in. Electric fields diminish with distance and can be blocked or partially shielded by objects such as trees and houses.

Magnetic Fields

Magnetic fields are created by the current or flow of electricity through a wire. Generally speaking, the higher the current, the higher the magnetic field. Because they only occur when current is flowing, magnetic fields are present only when the power is turned on (see Figure 1). Magnetic fields also diminish with distance, but—unlike electric fields—are not blocked by common objects. In recent years, public and scientific interest has turned toward the magnetic field component of EMF because of some scientific studies regarding these fields.

Figure 1




Figure 2


Magnetic field strengths decrease with distance Magnetic fields are measured in milligauss		Source: "EMF in Your Environment", U.S. Environmental Protection Agency 1992		
		At 6 inches	At 1 foot	At 2 feet
Clothes dryer		2 to 10	* to 3	*
Microwave oven		100 to 300	1 to 200	1 to 30
Toaster		5 to 20	* to 7	*
Power drill		100 to 200	20 to 40	3 to 6
Can opener		500 to 1500	40 to 300	3 to 30
Mixer		30 to 600	5 to 100	* to 10
Hair dryer		1 to 700	* to 70	* to 10
Color television		Data not available	* to 20	* to 8

FIGURE 2 * The magnetic field measurement at this distance from the operating appliance could not be distinguished from background measurements taken before the appliance had been turned on.

Measuring Magnetic Fields

Magnetic fields usually are measured in a unit called a milligauss. Magnetic field levels found in the living areas of homes typically range from less than 1 milligauss to about 4 milligauss according to the U.S. Environmental Protection Agency. They can be higher in some cases. The levels next to appliances can exceed 1,000 milligauss (1 gauss). Figures 2 and 3 show how the strength of the field falls off as you move away from the source, just as the heat of a campfire grows weaker as you walk away from it. For overhead power lines, the strength of the magnetic fields is dependent upon a number of factors that will be explained later. Those factors produce a magnetic field that drops off rapidly as you move away from the power line.

Figure 3

Sample Magnetic Field Levels in Milligauss				
Type of Overhead Power Line	Distance from the line			
	Under the line	50 ft.	100 ft.	200 ft.
220 kV and 500 kV	5-400	5-250	1-75	0.5-20
69 kV and 138 kV	3-80	0.5-2.5	0.1-10	0.1-3
12 kV and below	0.4-20	0.1-1	-	-

The magnetic field values provided in this table represent a general range of values associated with the types of overhead power lines listed and are provided for illustration. There will be circumstances in which there will be magnetic field levels above or below the range of values provided due to variations in such factors as height of the wires, current flow and so on.

DEVELOPMENT OF PPL EU'S MAGNETIC FIELD MANAGEMENT PROGRAM

One element of our response to EMF concerns expressed by some of our customers is PPL EU's Magnetic Field Management Program. The program was initiated in March 1991 because PPL EU believes it makes good sense, as a matter of policy, to respond to the concerns expressed by some of our customers and to reduce magnetic fields in new and rebuilt facilities where it can be done with either no-cost or low-cost design changes.

This document updates the original program which has been revised several times since 1991. These guidelines were developed by PPL EU's EMF Working Group.

VARIABLES THAT AFFECT MAGNETIC FIELDS

Magnetic fields from transmission and distribution lines are a function of a number of design variables. The following parameters affect the magnetic field levels produced by transmission and distribution lines:

- Current
- Height of conductors above ground
- Configuration of conductors
- Distance from the line

EFFECT OF PHASE CURRENT ON MAGNETIC FIELDS

At power frequencies (i.e., 60 hertz), the magnetic field level is a function of the current or flow of electricity through a wire. Keeping all other parameters the same, the magnetic field is proportional to the current. Hence, if the current increases by 25 percent, the resulting magnetic field level will increase by 25 percent.

The overall load current on any line varies with the demand for power. It's usually highest during daytime hours and lowest at night. There also are weekly, monthly, seasonal and yearly variations.

The difference in the currents between each phase in a multiphase line also can affect the magnetic field. This difference is called phase unbalance. For a constant load, a statistical analysis of this phase unbalance can be made to determine its effect on the magnetic field. Close to the line, there is very little effect. However, the phase unbalance slows the rate at which the magnetic field decreases with distance from the line.

EFFECT OF CONDUCTOR CONFIGURATION ON MAGNETIC FIELDS

In the transmission and distribution of power, utilities like PPL EU presently use both three-phase and single-phase lines. Each phase on a three-phase power line has either a single conductor or a bundle of two or more conductors. In a three-phase system, the ground-level magnetic field is a result of the fields produced by the currents in each of the phases. Placing the three phases as close together as possible (compaction) creates some field cancellation, and the ground-level magnetic field is reduced. However, appropriate phase separation is required for the reliable operation of the line. In addition, the arrangement of the phases can create some; field cancellation and reduction of the ground-level magnetic field.

EFFECT OF DISTANCE FROM THE MAGNETIC FIELD SOURCE

Magnetic field strength diminishes with the vertical and lateral distances from the magnetic field source. Increasing the height of the conductors above ground is useful for magnetic field reduction at ground level, but may result in increased structure costs and increased aesthetic impact of the structures. Another possible method of increasing the distance to the magnetic field source is to increase the right-of-way requirements. By keeping buildings off increased rights of way, thereby requiring the public to live and work further away from lines, exposure to magnetic fields produced by the lines can be reduced. Increases in right of way are not always practical and may increase costs significantly, however.

SUMMARY OF PPL EU's MAGNETIC FIELD MANAGEMENT PROGRAM

Under its Magnetic Field Management Program, PPL EU has changed the way it builds and rebuilds some of its transmission and distribution lines. These design changes reduce magnetic field levels (assuming balanced circuit loadings and phase currents) by up to 69 percent in most of the company's new transmission lines. These guidelines now are being applied to new and reconstructed transmission facilities, based on this program.

The distribution component of the program focuses on 12 kV lines, the company's standard distribution voltage. It concentrates on the three-phase, primary 12 kV lines, since these are the most heavily loaded facilities and often are located in densely populated areas. The guidelines in this program are being applied to these three-phase, primary 12 kV lines.

A maximum 3-5 percent change in estimated cost was used as the limit for the guidelines since this value is consistent with low cost, is within estimating accuracy and is likely to have little impact on overall line costs.

The magnetic field calculations used in this document for the design of PPL EU's overall magnetic field management plan assume balanced load conditions among the phases and a fixed level of current, not necessarily representative of specific transmission or distribution lines. These levels were calculated using the Electric Power Research Institute's ENVIRO computer program. Under actual operating conditions, the magnetic field levels that result may vary due to such things as actual load per circuit, overall current on each phase conductor and the electrical configuration and operation of each line.

MAGNETIC FIELD MANAGEMENT PROGRAM GUIDELINES

The guidelines for magnetic field management are noted below, with discussion points for each.

OVERHEAD LINES

NEW OR REBUILT TRANSMISSION LINES

1. **Balance transmission circuit loads and phase currents as much as possible.**
 - PPL EU should continue to make every effort to balance loadings between the two circuits of a double circuit line when planning new or rebuilt facilities to maximize the effects of reverse phasing.
 - PPL EU should continue the practice of balancing single-phase loads across the three phases of the distribution system. (Unbalanced phase currents on the distribution system are reflected through to the transmission system.)
 - Unbalanced phase currents result in higher magnetic fields that do not drop off as quickly with distance as do the fields resulting from balanced phase currents.
 - For a 5 percent phase current unbalance, the magnetic field 50 feet from the centerline of a single circuit 138 kV line could be more than twice the value than if the same line had balanced phase circuits.
 - Balanced phase currents on each three-phase distribution circuit also reduce magnetic fields from the distribution circuits themselves. In addition, they reduce magnetic fields on the transmission system from which the distribution system circuits are supplied and connected through substations.
 - Apart from magnetic field considerations, balanced phase currents on each three-phase distribution circuit also reduce line losses and improve the system voltage.

2. **Continue with the present practice of using long-span construction as the PPL EU 138/69 kV standard**
 - Structure designs for short-span and long-span construction are illustrated on Charts I and II, respectively.
 - Short-span design does not significantly reduce magnetic fields when compared to long-span design even though it is more compact than long-span design. Comparison of the magnetic field values from Chart III indicates essentially the same values. Therefore, short-span design should not be used solely to reduce magnetic fields.
 - PPL EU will continue to use long-span construction for 138/69 kV double-circuit lines and for single-circuit/future-double-circuit lines.
 - For single-circuit/future-double-circuit lines, PPL EU will continue to install two conductors on the top positions and one in the middle position as shown in Chart IV.
 - This arrangement minimizes magnetic fields as shown in Chart V by placing the three initial conductors higher on the structure, which increases the ground clearances, and by placing the conductors in a triangular configuration.
3. **Compact design structures are not a low-cost alternative and should be used for magnetic field reduction only in special applications.**

Chart VI illustrates the compact design structure.

 - The compact design increases the initial installation costs by 79 percent when compared to the long-span design but reduces the magnetic field from 9 mG to 3 mG (about 67 percent) at the edge of the 100-foot-wide right of way as shown on Chart III.
4. **Reverse phase new or rebuilt double-circuit transmission lines for all voltage levels.**
 - Reverse phasing was adopted by PPL EU in March 1991 for double-circuit 138/69 kV transmission lines and in April 1992 for all other double circuit transmission lines. Reverse phasing is shown in Chart VII. Reverse phasing will reduce the magnetic fields when the current flow on both circuits is in the same

direction. Calculated values contained here are based on balanced and equal phase currents on both circuits.

- Reverse phasing reduces the magnetic field of a double circuit 138 kV single pole transmission line from 29 mG to 9 mG (about 69 percent) at the edge of the 100-foot-wide right of way as shown on Chart III.
- Reverse phasing reduces the magnetic field of a double circuit 230 kV single pole transmission line from 49 mG to 16 mG (about 67 percent) at the edge of the 150-foot-wide right of way as shown on Chart VIII.
- Reverse phasing reduces the magnetic field of a double-circuit 500 kV single pole transmission line from 37 mG to 21 mG (about 43 percent) at the edge of the 200-foot-wide right of way as shown on Chart IX.
- When new or rebuilt double-circuit lines require tapping existing double-circuit lines, PPL EU will review the existing lines to determine if reverse phasing can be provided at low cost.
- Computer modeling is required to develop the optimum phasing and overall conductor arrangements for lines added to, or rebuilt in, multiple-line corridors.
 - Merely adding a reverse-phase double-circuit line to an existing transmission line corridor or reverse phasing a rebuilt line in the multiple-line corridor will not necessarily produce lower magnetic field levels at the edge of the corridor right of way.
 - The corridor must be computer modeled with all the lines, existing phase conductor locations and currents. Then, magnetic field calculations must be made varying the phase arrangements of the new or reconstructed line to determine the appropriate phasing arrangement.
 - Current flow direction on a line also must be considered. For example, a reverse-phased line should have the current flowing in the same direction on both circuits. If the current flow is in the opposite direction for one circuit, reverse phasing will not produce the lowest magnetic field and another phase arrangement that produces lower fields may need to be utilized.

5. **Increase the minimum ground clearance for all new transmission lines.**

138/69 kV Transmission Lines

- Increasing the minimum line design ground clearance from 25 feet to 30 feet may add up to about 5 percent to the installed cost of a new double-circuit single pole 138/69 kV line. For a given project, such cost may be substantially less, however. In fact, PPL EU frequently uses higher-than-minimum ground clearances due to such features as road crossings, line crossings and site-specific terrain. With long-span reverse-phase design, the magnetic field is reduced from 9 mG to 7 mG (about 22 percent) at the edge of a 100-foot-wide right of way as shown in Chart X.
 - In the actual design of transmission lines to include higher minimum ground clearances, there may be limited segments (such as highway crossings, severe slopes and transmission line crossing locations) where National Electrical Safety Code (NESC) minimum ground clearances may need to be used. The NESC minimum ground clearances are less than the increased ground clearance discussed previously.

230 kV Transmission Lines

- Increasing the minimum line design ground clearances from 27 feet to 32 feet may add up to about 5 percent to the cost of a single-circuit single-pole line (current standard). For a given project, such cost may be substantially less, however. In fact, PPL EU frequently uses higher-than-minimum ground clearances due to such features as road crossings, line crossings and site-specific terrain. By increasing the clearances, the magnetic field is reduced from 30 mG to 28 mG (about 7 percent) at the edge of a 150-foot-wide right of way.
- Increasing clearances from 27 feet to 32 feet could theoretically add up to about 2.8 percent to the cost of a double-circuit single-pole line (current standard) and reduce the magnetic field of a reverse-phase line from 16 mG to 15 mG (about 6 percent) at the edge of a 150-foot-wide right of way. Chart XI is a summary of this data.
- Studies are required for each new 230 kV line to determine optimum structure types, ground clearances, configurations and designs to reduce field levels. Such

studies could include analysis of reduction measures such as additional minimum ground clearances, increasing conductor tensions, using reduced phase spacing (a "Delta" configuration on a single-circuit line), installing the second circuit initially, and/or adding a second set of conductors that are reverse phased and operated in parallel with the first set (bundled/split phase).

500 kV Transmission Lines

- Increasing ground clearances from 33 feet to 53 feet may add up to about 4.5 percent to the cost of a single-circuit "H-frame" line (current standard). For a given project, such cost may be substantially less, however. In fact, PPL EU frequently uses higher-than-minimum ground clearances due to such features as road crossings, line crossings and site-specific terrain. By increasing the clearances, the magnetic field is reduced from 42 mG to 35 mG (about 17 percent) at the edge of a 200-foot-wide right of way.
- Increasing ground clearances from 33 feet to 53 feet could theoretically add up to 2.8 percent to the cost of a double-circuit "H-frame" line (current standard) and reduces the magnetic field of a reverse-phase line from 21 mG to 16 mG (about 24 percent) at the edge of a 200-foot-wide right of way. Chart XII is a summary of this data.
- Studies are required for each new 500 kV line to determine optimum structure types, ground clearances, configurations and designs to reduce field levels. Such studies could include analysis of reduction measures such as additional minimum ground clearances, increasing conductor tensions, using reduced-phase spacing (a "Delta" configuration on a single circuit line), installing the second circuit initially, and/or adding a second set of conductors that are reverse phased and operated in parallel with the first set (bundled/split phase).

RECONDUCTORING OR ADDING ADDITIONAL CIRCUITS TO EXISTING TRANSMISSION LINES

When reconductoring or adding additional circuits to existing transmission lines, PPL EU will evaluate low-cost or no-cost options for magnetic field management on a case-by-case basis.

When reconductoring existing transmission lines or adding additional circuits, low-cost alternatives may not exist; however, the following steps will be taken:

- For a single-circuit line, the use of a Delta arrangement or other modifications on the existing structure, with reduced-phase spacing, will be evaluated.
- For double-circuit lines, application of reverse phasing may reduce the magnetic field under the line and within the right of way and will be evaluated.
- For single- and double-circuit lines, evaluate using higher conductor tensions that can increase the minimum line design ground clearance.

DISTRIBUTION LINES

At the 12 kV distribution level, new main three-phase lines will continue to be constructed with five feet of additional ground clearance.


- Main lines are the most heavily loaded sections of a distribution line and therefore have the highest magnetic fields associated with them.
- Increasing the ground clearance by five feet reduces the magnetic field under the line from 14 mG to 11 mG using the standard eight-foot crossarm design. These values are based on increasing pole heights from 45 feet to 50 feet and a typical operating current of 300 amps per phase.
- Chart XIII is a summary of this data. Increasing ground clearance by five feet could theoretically add about 5 percent to the cost of a typical distribution line.

UNDERGROUND TRANSMISSION LINES

Underground transmission lines are required due to environmental or land use factors or restrictions on available clearances, PPL EU will evaluate options for magnetic field management techniques on a case-by-case basis.


- The phase arrangement that produces the lowest field will be determined.
- The depth of burial of the line will be determined considering the cost of excavation and the location of other buried utilities in the area.
- The use of steel pipe ferromagnetic shielding that reduces magnetic fields will be evaluated.

Short-Span Construction



- More compact design
- Should not be used solely to reduce magnetic fields
- Typical conductor data:
 - 1 3/8" HS steel overhead ground wire - 7.3 feet sag
 - 6-556.5 KCMIL 24/7 ACSR power conductors - (PARAKEET) 10.0 feet sag
 - Average span - 400 feet

Long-Span Construction Remains PPL EU 138 kV Standard




- Lower cost alternative
- Reduces magnetic fields due to higher structures
- Typical conductor data:
 - 1 3/8" HS steel overhead ground wire - 17.3 feet sag
 - 6-556.5 KCMIL 24/7 ACSR power conductors - (PARAKEET) 23.0 feet sag
 - Average span - 600 feet

**138/69 kV REVERSE-PHASE TRANSMISSION LINES
CALCULATED MAGNETIC FIELDS AT 400 AMPERES**


TYPE CONSTRUCTION	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
SHORT SPAN (CHART I)	30
SHORT SPAN (REVERSE PHASE)	8
LONG SPAN (CHART II)	29
LONG SPAN (REVERSE PHASE)	9
COMPACT (CHART VI)	14
COMPACT (REVERSE PHASE)	3

The edge of right of way is 50 feet from the line centerline.
The 400 ampere phase current is balanced between phases.
Calculations are based on a minimum ground clearance of 25 feet.
LONG SPAN, SHORT SPAN and COMPACT are double-circuit lines.


Typical Single-Circuit Structure Designs



Top/Middle



Vertical



Top/Middle/Bottom


——— initial single circuit
- - - - - future second circuit

**138/69 KV SINGLE CIRCUIT TRANSMISSION LINES
CALCULATED MAGNETIC FIELDS AT 400 AMPERES**

TYPE CONSTRUCTION	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
TOP/MIDDLE/BOTTOM	20
VERTICAL	17
TOP/MIDDLE	12


The edge of right of way is 50 feet from the line centerline.
The 400 ampere phase current is balanced between phases.
Calculations are based on a minimum ground clearance of 25 feet.

Compact Design Structure



- Minimize magnetic fields due to compact design
- Not a low-cost alternative
- Typical conductor data:
 - 1 3/8" HS steel overhead ground wire - 9.0 feet sag
 - 6-556.5 KCMIL 24/7 ACSR power conductors - (PARAKEET) 9.0 feet sag
 - Average span - 300 feet

Reverse Phasing of Double-Circuit Transmission Lines



From: → → → → To:

Reverse phasing also can be one of the following phase arrangements:

A	B		B	A		B	C		C	A		C	B
C	C	or	C	C	or	A	A	or	B	B	or	A	A
B	A		A	B		C	B		A	C		B	C

**230 kV REVERSE-PHASE TRANSMISSION LINES
CALCULATED MAGNETIC FIELDS AT 800 AMPERES**

TYPE CONSTRUCTION	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
DOUBLE CIRCUIT POLE	49
DOUBLE CIRCUIT POLE (REVERSE-PHASE)	16

The edge of right of way is 75 feet from the line centerline.
The 800 ampere phase current is balanced between phases.
Calculations are based on a minimum ground clearance of 27 feet.

**500 kV REVERSE-PHASE TRANSMISSION LINES
CALCULATED MAGNETIC FIELDS AT 1100 AMPERES**

TYPE CONSTRUCTION	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
DOUBLE CIRCUIT POLE	37
DOUBLE CIRCUIT POLE (REVERSE PHASE)	21

The edge of right of way is 100 feet from the line centerline.
The 1,100 ampere phase current is balanced between phases.
Calculations are based on a minimum ground clearance of 33 feet.

**INCREASED 138/69 kV MINIMUM GROUND CLEARANCE
CALCULATED MAGNETIC FIELDS AT 400 AMPERES**

TYPE CONSTRUCTION	MINIMUM GROUND CLEARANCE FEET	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
SINGLE CIRCUIT TOP/MIDDLE	25	12
SINGLE CIRCUIT TOP/MIDDLE	30	10
LONG SPAN	25	29
LONG SPAN	30	26
LONG SPAN (REVERSE PHASE)	25	9
LONG SPAN (REVERSE PHASE)	30	7

The edge of right of way is 50 feet from the line centerline.
The 400 ampere phase current is balanced between phases.

**INCREASED 230 kV MINIMUM GROUND CLEARANCE
CALCULATED MAGNETIC FIELDS AT 800 AMPERES**

TYPE CONSTRUCTION	MINIMUM GROUND CLEARANCE FEET	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
SINGLE CIRCUIT TOP/MIDDLE	27	30
SINGLE CIRCUIT TOP/MIDDLE	32	28
DOUBLE CIRCUIT POLE	27	49
DOUBLE CIRCUIT POLE	32	46
DOUBLE CIRCUIT POLE (REVERSE PHASE)	27	16
DOUBLE CIRCUIT POLE (REVERSE PHASE)	32	15

The edge of right of way is 75 feet from the line centerline.
The 800 ampere phase current is balanced between phases.

**INCREASED 500 kV MINIMUM GROUND CLEARANCE
CALCULATED MAGNETIC FIELDS AT 1,100 AMPERES**

TYPE CONSTRUCTION	MINIMUM GROUND CLEARANCE FEET	MAGNETIC FIELD IN MILLIGAUSS AT THE EDGE OF THE RIGHT OF WAY
SINGLE CIRCUIT "H" STRUCTURE	33	42
SINGLE CIRCUIT "H" STRUCTURE	53	35
DOUBLE CIRCUIT POLE	33	37
DOUBLE CIRCUIT POLE	53	31
DOUBLE CIRCUIT POLE (REVERSE PHASE)	33	21
DOUBLE CIRCUIT POLE (REVERSE PHASE)	53	16

The edge of right of way is 100 feet from the line centerline.
The 1,100 ampere phase current is balanced between phases.

**12 kV DISTRIBUTION LINES
CALCULATED MAGNETIC FIELDS AT 300 AMPERES**

TYPE CONSTRUCTION	POLE HEIGHT FEET	MAGNETIC FIELD IN MILLIGAUSS*	
		AT CENTERLINE	AT 30 FEET FROM CENTERLINE
STANDARD CROSSARM	45	14	7
STANDARD CROSSARM	50	11	6

* Field level under the line at mid-span based on 300 amps, balanced loading, one meter above ground level.

Attachment

6

ATTACHMENT 6

**LIST OF INVOLVED GOVERNMENTAL AGENCIES, MUNICIPALITIES AND
OTHER PUBLIC ENTITIES**

1. Pennsylvania Historical and Museum Commission
Bureau for Historic Preservation
Division for Archaeology and Protection
P.O. Box 1026
Harrisburg, Pennsylvania 17108-1026
Attn: Mr. Douglas C. McLearn, Chief

2. Pennsylvania Department of Transportation
Commonwealth Keystone Building
400 North Street, 8th Floor
Harrisburg, Pennsylvania 17120
Attn: The Honorable Allen D. Biehler, Secretary

3. Department of Environmental Protection
P.O. Box 2063
Market Street State Office Building
Harrisburg, Pennsylvania 17105-2063
Attn: Office of Field Operations

4. Wayne County Commissioners
925 Court St.
Honesdale, Pennsylvania 18431
Attn: Brian Smith, Chair

5. Wayne County Planning Commission
925 Court St
Honesdale, Pennsylvania 18431
Attn: Edward J. Coar, Director

6. Paupack Township Board of Supervisors
219 Oak Street
Hawley, Pennsylvania 18428
Attn: Lois Powderly, Secretary

7. Paupack Township Planning Commission
219 Oak Street
Hawley, Pennsylvania 18428
Attn: Lois Powderly, Secretary