



## CHAPTER 94 MUNICIPAL WASTELOAD MANAGEMENT ANNUAL REPORT

**For Calendar Year: 2023**

- Permittee is owner and/or operator of a POTW or other sewage treatment facility  
 Permittee is owner and/or operator of a collection system tributary to a POTW not owned/operated by permittee

### GENERAL INFORMATION

Permittee Name: <b>Lower Allen Township Authority</b>	Permit No.: <b>PA0027189</b>
Mailing Address: <b>120 Limekiln Road</b>	Effective Date: <b>06/01/2022</b>
City, State, Zip: <b>New Cumberland, PA 17070</b>	Expiration Date: <b>05/31/2027</b>
Contact Person: <b>Brian P. Kauffman, PE</b>	Renewal Due Date: <b>12/02/2026</b>
Title: <b>Manager/Engineer</b>	Municipality: <b>Fairview Township</b>
Phone: <b>717-774-0610</b>	County: <b>York</b>
Email: <b>bkauffman@latwp.org</b>	Consultant Name: <b>N/A</b>

### CHAPTER 94 REPORT COMPONENTS

1. Attach to this report a line graph depicting the monthly average flows (expressed in MGD) for each month for the past 5 years and projecting the flows for the next 5 years. The graph must also include a line depicting the hydraulic design capacity per the WQM permit. (25 Pa. Code § 94.12(a)(1))

**Check the appropriate boxes:**

- Line graph for flows attached (**Attachment 1**)  
 DEP Chapter 94 Spreadsheet used (**Attachment 1**)  
 Section 1 is not applicable (report is for a collection system).

2. Attach to this report a line graph depicting the monthly average organic loads (express as lbs BOD5/day) for each month for the past 5 years and projecting the organic loads for the next 5 years. The graph must also include a line depicting the organic design capacity of the treatment plant per the WQM permit. (25 Pa. Code § 94.12(a)(2))

**Check the appropriate boxes:**

- Line graph for organic loads attached (**Attachment 2**)  
 DEP Chapter 94 Spreadsheet used (**Attachment 1**)  
 Section 2 is not applicable (report is for a collection system).

3. If the DEP Chapter 94 Spreadsheet was not used to determine projections, discuss the basis for the hydraulic and organic projections. In all cases, include a description of the time needed to expand the plant to meet the load projections, if necessary, and data used to support the projections should be included in an appendix to this report. (25 Pa. Code § 94.12(a)(3))

**N/A**

4. Attach a map showing all sewer extensions constructed within the past calendar year, sewer extensions approved or exempted in the past year in accordance with Act 537 and Chapter 71, but not yet constructed, and all known proposed projects which require public sewers but are in the preliminary planning stages. The map must be accompanied by a list summarizing each extension or project and the population to be served by the extension or project. If a sewer extension approval or proposed project includes schedules describing how the project will be completed over time, the listing should include that information and the effect this build-out-rate will have on populations served. (25 Pa. Code § 94.12(a)(4))

**Check the appropriate boxes:**

- Map showing sewer extensions constructed, approved/exempted but not yet constructed, and proposed projects attached (**Attachment 3**)
- List summarizing each extension or project attached (**Attachment 3**)
- Schedules describing how each project will be completed over time and effects attached (**Attachment 3**)

**Comments:**

5. Discuss the permittee's program for sewer system monitoring, maintenance, repair and rehabilitation, including routine and special activities, personnel and equipment used, sampling frequency, quality assurance, data analyses, infiltration/inflow monitoring, and, where applicable, maintenance and control of combined sewer regulators during the past year. Attach a separate sheet if necessary. (25 Pa. Code § 94.12(a)(5))

**See attachment 4**

6. Discuss the condition of the sewer system including portions of the system where conveyance capacity is being exceeded or will be exceeded in the next 5 years and portions where rehabilitation or cleaning is needed or is underway to maintain the integrity of the system and prevent or eliminate bypassing, CSOs, SSOs, excessive infiltration and other system problems. Attach a separate sheet if necessary. (25 Pa. Code § 94.12(a)(6))

**Check the appropriate boxes:**

- System experienced capacity-related bypassing, SSOs or surcharging during the report year. On a separate sheet, list the date, location, and reason for each bypass, SSO or surcharge event.
- System did not experience capacity-related bypassing, SSOs or surcharging during the report year.

**Comments:**

7. Attach a discussion on the condition of sewage pumping (pump) stations. Include a comparison of the maximum pumping rate with present maximum flows and the projected 2-year maximum flows for each station. (25 Pa. Code § 94.12(a)(7))

**Check the appropriate boxes:**

- The collection system does not contain pump stations  
 The collection system does contain pump stations (Number – **12**)  
 Discussion of condition of each pump station attached (**Attachment 5**)

8. If the sewage collection system receives industrial wastes (i.e., non-sanitary wastes), attach a report with the information listed below. (25 Pa. Code § 94.12(a)(8))

- a. A copy of any ordinance or regulation governing industrial waste discharges to the sewer system or a copy of amendments adopted since the initial submission of the ordinance or regulation under Chapter 94, if it has not previously been submitted.
- b. A discussion of the permittee's or municipality's program for surveillance and monitoring of industrial waste discharges into the sewer system during the past year.
- c. A discussion of specific problems in the sewer system or at the plant, known or suspected to be caused by industrial waste discharges and a summary of the steps being taken to alleviate or eliminate the problems. The discussion shall include a list of industries known to be discharging wastes which create problems in the plant or in the sewer system and action taken to eliminate the problem or prevent its recurrence. The report may describe pollution prevention techniques in the summary of steps taken to alleviate current problems caused by industrial waste dischargers and in actions taken to eliminate or prevent potential or recurring problems caused by industrial waste dischargers.

**Check the appropriate boxes:**

- Industrial waste report as described in 8 a., b. and c. attached (**Attachment** )  
 Industrial pretreatment report as required in an NPDES permit attached (**Attachment 6**)

9. Existing or Projected Overload.

**Check the appropriate boxes:**

- This report demonstrates an existing hydraulic overload condition.  
 This report demonstrates a projected hydraulic overload condition.  
 This report demonstrates an existing organic overload condition.  
 This report demonstrates a projected organic overload condition.

If one or more boxes above have been checked, attach a Corrective Action Plan (CAP) to reduce or eliminate present or projected overloaded conditions under §§ 94.21 and/or 94.22 (relating to existing overload and projected overload). (25 Pa. Code § 94.12(a)(9))

- Corrective Action Plan attached (**Attachment** )

10. Where required by the NPDES permit, attach a Sewage Sludge Management inventory that demonstrates a mass balance of solids coming in and leaving the facility over the previous calendar year.

- Sewage Sludge Management Inventory attached (**Attachment 7**)

11. For facilities with CSOs and where required by the NPDES permit, attach an Annual CSO Report (including satellite combined sewer systems).

Annual CSO Report attached (**Attachment** )

12. For POTWs, attach a calibration report documenting that flow measuring, indicating and recording equipment has been calibrated annually. (25 Pa. Code § 94.13(b))

Flow calibration report attached (**Attachment 8**)

### RESPONSIBLE OFFICIAL CERTIFICATION

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowledge of violations. See 18 Pa. C.S. § 4904 (relating to unsworn falsification).

**Brian P. Kauffman, PE**



Name of Responsible Official

Signature

**717-774-0610**

**3-25-24**

Telephone No.

Date

### PREPARER CERTIFICATION

I certify under penalty of law that this document and all attachments were prepared by me or otherwise under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. The information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowledge of violations. See 18 Pa. C.S. § 4904 (relating to unsworn falsification).

**Brian P. Kauffman, PE**



Name of Preparer

Signature

**717-774-0610**

**3-25-24**

Telephone No.

Date



## CHAPTER 94 MUNICIPAL WASTELOAD MANAGEMENT ANNUAL REPORT INSTRUCTIONS

This form has been developed to promote consistency in the development of annual municipal wasteload management reports ("Chapter 94 reports") required by 25 Pa. Code § 94.12. At least two copies of the complete report must be submitted to the appropriate regional office of the Department of Environmental Protection (DEP) by March 31.

Enter the calendar year that the report covers at the top of the form. Check the appropriate box to indicate whether the permittee is the owner/operator of a publicly owned treatment works (POTW) or other sewage treatment facility, or is the owner/operator of a sewage collection system that is tributary to a POTW owned/operated by a different entity.

### General Information

Record the name of the permittee, the permittee's full mailing address, the permittee's contact person and this person's title, phone number and email address. Also record the permit number (NPDES or WQM), the effective date of permit coverage, the expiration date of permit coverage (if applicable), the date by which an application or NOI is due for reissuance (renewal) (if applicable), the municipality and county where the sewage treatment facility or collection system is located, and the name of the consultant (company name), if any, who assisted in the preparation of the form.

### Chapter 94 Report Components

This section requests responses to 12 questions that, if applicable, must be addressed for a complete Chapter 94 report. Questions 1 – 9 and 12 come directly from the Chapter 94 regulations, i.e., 25 Pa. Code §§ 94.12(a)(1) – 94.12(a)(9) and 94.13(b). Some questions request that you check an appropriate box, attach the information requested, and specify the attachment number, while responses to other questions may be entered directly on the form.

For Questions 1 and 2, permittees may use DEP's Chapter 94 Spreadsheet to satisfy 25 Pa. Code §§ 94.12(a)(1) and 94.12(a)(2), respectively. DEP encourages use of the Chapter 94 Spreadsheet to provide consistency in the format and calculations associated with hydraulic and organic load evaluations (see [www.depweb.state.pa.us/chapter94](http://www.depweb.state.pa.us/chapter94)). If the Chapter 94 Spreadsheet was used, check the appropriate box(es) and attach printouts of the data and graphs to the Chapter 94 report. If this report is being used for a collection system only, these graphs are not needed.

For Question 6, if the permittee checks the box that there were capacity-related bypasses or SSOs during the report year, in general the box for existing hydraulic overload in Question 9 should be checked. If the permittee checks the box in Question 6 because surcharging occurred during the report year, in general the box for projected hydraulic overload in Question 9 should be checked.

For Question 8, if the permittee has an EPA-approved pretreatment program, attachment of an annual pretreatment report as required in an NPDES permit will satisfy the requirement for an industrial waste report.

For Question 10, if a permit requires a "Sewage Sludge Management" inventory, check the appropriate box if the inventory is attached to the Chapter 94 report.

For Question 11, if an NPDES permit (individual permit or, for satellite collection systems, PAG-06 General NPDES permit coverage) requires an Annual CSO (Status) report, attach the CSO report to the Chapter 94 report and check the appropriate box.

### Certification

In accordance with 25 Pa. Code § 94.12(a), both the individual who prepared the report and (a responsible official of) the permittee must sign the report. The term "responsible official" for a municipality is a principal executive officer or ranking elected official.

Questions on the completion of Chapter 94 reports may be directed to DEP's Bureau of Point and Non-Point Source Management at (717) 787-8184 or to the appropriate DEP regional office (contact information available by visiting DEP's website, [www.depweb.state.pa.us](http://www.depweb.state.pa.us), and selecting Regional Resources).

# TUS A-12\_Attachment

**Attachment 1 Hydraulic Load  
Lower Allen Township Authority  
NPDES PA0027189**

The PADEP Chapter 94 Spreadsheet and Line Graphs for hydraulic data with precipitation are contained in the report.

Additionally, the following information is included in the attachment.

Anticipated Connection Summary for the treatment plant service area as projected for the next five years based on available information.

The operating records for the treatment plant indicate compliance with the NPDES permit conditions during the reporting period, see Department Discharge Monitoring Report NPDES PA0027189 electronic file.

The plant was not hydraulically overloaded in 2023 and is not projected to be overloaded in the next five years.

Reporting Year:

Persons/EDU:

lbs BOD5/day:

Year:

lbs BOD5/day:

Permit No.:

Existing Organic Design Capacity:  
Upgrade Planned in Next 5 Years?

Future Organic Design Capacity:  
Upgrade Planned in Next 5 Years?

Facility Name:

Existing Hydraulic Design Capacity:  
Upgrade Planned in Next 5 Years?

Future Hydraulic Design Capacity:  
Upgrade Planned in Next 5 Years?

MGD

Year:

MGD

Monthly Average BOD5 Loads for Past Five Years (lbs/day)

Month	2019	2020	2021	2022	2023
January	7,329	6,715	6,327	6,354	6,224
February	7,549	7,088	6,284	6,962	5,652
March	7,414	6,586	7,805	6,454	5,371
April	7,604	6,086	6,672	6,918	5,290
May	7,242	5,775	6,437	6,563	5,296
June	6,778	5,969	6,147	6,146	5,018
July	6,545	5,516	6,386	6,224	5,001
August	6,108	5,279	6,031	5,618	4,945
September	5,696	5,317	7,589	5,625	4,238
October	6,047	4,923	6,802	5,198	4,957
November	6,590	6,126	5,870	5,700	4,746
December	6,326	5,391	5,871	6,445	5,771

Monthly Average Flows for Past Five Years (MGD)

Month	2019	2020	2021	2022	2023
January	10.894	6.915	6.429	5.503	5.515
February	9.856	7.352	6.144	7.062	4.538
March	10.67	7.099	7.489	6.449	4.992
April	9.505	7.409	6.868	8.159	4.674
May	9.855	7.824	6.211	9.376	5.604
June	8.39	6.988	6.063	6.669	4.399
July	7.431	5.566	7.067	5.993	5.75
August	5.98	5.085	5.861	4.938	4.243
September	5.335	4.233	8.915	5.143	4.368
October	5.538	3.595	6.612	4.572	4.522
November	6.893	4.342	6.4	3.9	4.148
December	6.758	5.652	4.926	5.22	6.044

Annual Avg: 6,769    5,896    6,518    6,184    5,209

Max Mo Avg: 7,604    7,088    7,805    6,962    6,224

Max : Avg Ratio: 1.12    1.20    1.20    1.13    1.19

Existing EDUs: 22,940    23,040    23,232    23,514    23,842

Load/EDU: 0.295    0.286    0.281    0.263    0.218

Load/Capita: 0.155    0.135    0.148    0.138    0.115

Exist. Overload?: NO    NO    NO    NO    NO

Annual Avg: 8.092    6.003    6.582    6.082    4.9

Max 3-Mo Avg: 10.473    7.444    7.309    8.068    5.251

Max : Avg Ratio: 1.29    1.24    1.11    1.33    1.07

Existing EDUs: 22,940.0    23,040.0    23,232.0    23,514.0    23,842.0

Flow/EDU (GPD): 352.7    260.5    283.3    288.7    205.5

Flow/Capita (GPD): 185.7    137.1    149.1    136.1    108.2

Exist. Overload?: NO    NO    NO    NO    NO

Projected BOD5 Loads for Next Five Years (lbs/day)

	2024	2025	2026	2027	2028
New EDU	285	245	190	183	172
New EDU Load	74,842	64,338	49,895	48,057	45,168
Proj. Annual Avg	6,190	6,284	6,304	6,352	6,398
Proj. Max Avg	7,230	7,305	7,364	7,420	7,473
Proj. Overload?	NO	NO	NO	NO	NO

Projected Flows for Next Five Years (MGD)


	2024	2025	2026	2027	2028
New EDUs	285.0	245.0	190.0	183.0	172.0
New EDU Flow	0.06181	0.04455	0.03967	0.03504	0.0468
Proj. Annual Avg	6.394	6.43855	6.47822	6.51326	6.56006
Proj. Max 3-Mo Avg	7.728	7.782	7.829	7.872	7.928
Proj. Overload?	NO	NO	NO	NO	NO

Show Precipitation Data on Hydraulic Graph?

Total Monthly Precipitation for Past Five Years (Inches)

Month	2019	2020	2021	2022	2023
January	3.31	3.3	3.1	8.9	3.95
February	3.78	2.6	5.3	3.6	1.3
March	4.75	3.33	3.4	3.5	3.21
April	4.6	5.65	2.6	4.55	7.1
May	7.25	2.7	4.65	7.05	0.35
June	4.8	3.7	3.8	3.7	4.85
July	3.9	0.8	7.4	2.5	6.85
August	2.55	5.3	5.9	2.5	2.45
September	1.75	1.4	11.5	4.9	6.3
October	9.8	4.2	4.1	3.9	2.25
November	2.3	2.7	2.1	3.3	2.65
December	4.99	4.1	1.8	6.15	5.9

5-Year Measured and Projected Hydraulic Loads  
Lower Allen WWTP, PA0027189



# TUS A-12\_Attachment

**Lower Allen Township Authority  
Anticipated Connection Summary  
2023 DEP Chapter 94 Report**

Collection System		2024	2025	Year		
				2026	2027	2028
PA American Water Fairview Area LATA	EDUs	120	120	120	120	120
	GPD	27,000	27,000	27,000	27,000	27,000
PA Depart. Corrections SCIC	EDUs	0	0	0	0	0
	GPD	0	0	0	0	0
Upper Allen Twp to LATA	EDUs	91	80	52	47	41
	GPD	20,750	9,000	9,250	5,000	10,250
Lower Allen Township Authority Service Area	EDUs	74	45	18	16	11
	GPD	14,060	8,550	3,420	3,040	2,090
<b>TOTAL</b>	<b>EDUs</b>	<b>285</b>	<b>245</b>	<b>190</b>	<b>183</b>	<b>172</b>
	<b>GPD</b>	<b>61,810</b>	<b>44,550</b>	<b>39,670</b>	<b>35,040</b>	<b>39,340</b>

Note: Based on available estimated connection information.

**Lower Allen Township Authority**

Service Area Connections		2024	2025	Year		
				2026	2027	2028
High Meadow	EDUs	1	1			
	GPD	190	190			
Birch Grove	EDUs	12				
	GPD	2280				
Arcona Phase 3	EDUs			5	5	5
	GPD			950	950	950
Arcona Phase 8.3/9	EDUs		25	25		
	GPD		4750	4750		
Arcona Phase 8.2	EDUs	40	34			
	GPD	7600	6460	0		
Lower Allen Commons	EDUs	1				
	GPD	190				
Lark Meadow	EDUs	6	6			
	GPD	1140	1140			
Sheepford Road	EDUs		3	3	3	3
	GPD		570	570	570	570
Miscellaneous	EDUs	3	3	3	3	3
	GPD	570	570	570	570	570
<b>TOTAL</b>	<b>EDUs</b>	<b>63</b>	<b>72</b>	<b>36</b>	<b>11</b>	<b>11</b>
	<b>GPD</b>	<b>11970</b>	<b>13680</b>	<b>6840</b>	<b>2090</b>	<b>2090</b>

Note: Based on available land development information for Lower Allen Township and Shiremanstown Borough.




# TUS A-12\_Attachment

**Attachment 2 Organic Load  
Lower Allen Township Authority  
NPDES PA0027189**

The PADEP Chapter 94 Spreadsheet and Line Graph for organic data is contained in the report.

Based on the above information, the treatment plant is not by PADEP definition organically overloaded nor projected to be overloaded in the next five years.

**5-Year Measured and Projected Organic Loads  
Lower Allen WWTP, PA0027189**




**Attachment 3 Sewer Extensions  
Lower Allen Township Authority  
NPDES PA0027189**

The sewer system base map sections included identify the Authority sewer system extension activity. Arcona Phase 8,3, 9 and 3 are pending. Lark Meadow, a new 15 home development is complete (2023).

Tributary collection system extension activity can be found in Attachment 10.

# TUS A-12\_Attachment



## **Attachment 4 Sewer System Lower Allen Township Authority NPDES PA0027189**

The Lower Allen Township Authority sewer system remains in good condition due to the continuing maintenance program and rehabilitation work performed by the Authority staff. Sewer system I/I sources when identified are repaired and removed from the system in an ongoing program.

The Authority sewer system includes over 761,700 feet of collection sewers, 2,539 manholes, eight pumping stations and three metering chambers. The Authority owns and operates a sewer flusher truck, sewer line rapid acoustical assessment equipment, sewer televising system, flow metering equipment, and construction equipment for monitoring and maintaining the sewers. The Authority has a staff of 26 people with 11 licensed Class A operators plus 2 have the lab subclass certifications. Monthly summaries of major sewer system maintenance activities are included with this section.

The Authority personnel and contractors completed the following collection system maintenance and rehabilitation activities as listed below.

1. Internal camera inspection of 2681 feet of sewer main.
2. Responded to 15 blockage calls and cleaned 3,789 feet of sewer main related to calls. Seventy eight percent of blockages were identified as being in the home owner's lateral.
3. Sewer line rapid acoustical assessment was completed on 34,583 feet of sewer main resulting in 21,876 feet of pipe requiring flushing and retesting. This represents 15 percent of the sewer main system being tested and cleaned for the year.
4. Responded to over 1,959 PA One Call system requests for sewer system field location markings for utility protection.
5. Inspection of 55 new service connections, 63 service lateral repairs and 1 disconnect.

Infiltration flow monitoring was completed between 2 AM and 5 AM at 8 locations in April and October where tributary municipal systems connect to the Authority system. An average total of 88,456 GPD of unmetered infiltration was observed in April and 83,220 GPD in October at these locations. The tributary municipalities were notified of the metering results.

The Authority future sewer system activities are outlined in Attachment 7.

## Staff Activity Summary Report – January 2023

### Collection System

Responded to 105 PA-One Call utility location requests.

Inspected 9 lateral repairs, 0 lateral disconnects and 5 new service lateral connections.

Air and mandrel testing new mains of Arcona Phase 8.2.

Completed rapid sewer inspection on 0 feet of sewer main.

Flushed 744 feet of sewer main and 3 blockage calls.

Completed internal camera inspection of 343 feet of sewer main.

### Treatment Plant

Replaced high water float at Beacon Hill pump station.

Replaced cord on roll up door in truck bay.

Replaced timer for fan at Windsor Park pump station.

Replaced bad electric contact at Shiremanstown pump station.

Replaced heater in primary pump room.

Replaced block heater at Linda Lane pump station.

Repaired lights in U.V. building.

Repaired lights at aeration tanks.

Preventative maintenance on golf cart.

Preventative maintenance on L.A.-29 Ford truck.

Preventative maintenance on L.A.-26 Ford truck.

Tightened up check valve packing nuts on #3 main pump.

State inspection on L.A.-27 Chevy truck.

Put rebuilt rotating assembly on #4 main pump and rebuilt old assembly.

## Staff Activity Summary Report – February 2023

### Collection System

Responded to 97 PA-One Call utility location requests.

Inspected 8 lateral repairs, 0 lateral disconnects and 2 new service lateral connections.

Air and mandrel testing new mains of Arcona Phase 8.2.

Completed rapid sewer inspection on 847 feet of sewer main.

Flushed 874 feet of sewer main and 0 blockage calls.

Completed internal camera inspection of 347 feet of sewer main.

### Treatment Plant

Replaced glass on sand blaster.

Replaced main sewer pump #2 stand.

Repaired heater in truck loading bay.

Repaired wet well pan/hoist doors.

Rebuilt spare air release valve for Sheepford pump station.

Rebuilt spare rotating assembly for main sewer pumps #1 and #4.

Rebuilt spare drive shaft for main sewer pumps #1 and #4.

Installed new motor on reaeration blower #1.

Had main sewer pump #1 drive motor rebuilt.

Had main sewer pump #2 check valve rebuilt.

State inspection on LA-25 Mack dump truck.

State inspection on LA-22 International dump truck.

## Staff Activity Summary Report – March 2023

### Collection System

Responded to 164 PA-One Call utility location requests.

Inspected 3 lateral repairs, 0 lateral disconnects and 4 new service lateral connections.

Air and mandrel testing new mains of Arcona Phase 8.2.

Completed rapid sewer inspection on 7,291 feet of sewer main.

Flushed 4,145 feet of sewer main and 1 blockage call.

Completed internal camera inspection of 395 feet of sewer main.

### Treatment Plant

Replaced 3-way switch in sludge disposal building.

Replaced pump and nozzle on bulk oil tank.

Replaced air release valve for Sheepford pump station.

Repaired lights in sludge disposal building office.

Repaired portable welder.

Repaired light at anoxic zone mixer 2B.

Repaired and state inspection on LA 29 Ford F250.

Repaired and state inspection on LA 26 Ford F150.

Preventative maintenance on LA 17 Chevrolet Colorado.

Preventative maintenance on air compressor in sludge disposal building.

Preventative maintenance and state inspection on LA 16 Ford Escape.

Preventative maintenance, repaired, and state inspection on LA 18 Ford F450.

Rebuilt back flow preventer in sludge disposal building.

Prepared snow blowers for storage and removed lawn mowers from storage.

## Staff Activity Summary Report – April 2023

### Collection System

Responded to 186 PA-One Call utility location requests.

Inspected 1 lateral repair, 0 lateral disconnects and 2 new service lateral connections.

Air and mandrel testing new mains of Arcona Phase 8.2.

Completed rapid sewer inspection on 14,156 feet of sewer main.

Flushed 10,566 feet of sewer main and 5 blockage calls.

Completed internal camera inspection of 1,063 feet of sewer main.

Preventative maintenance on #1 and #2 pumps at Raven Hill pump station.

### Treatment Plant

Replaced the inner loop on main gate.

Repaired lights in plant.

Repaired flow meter on dilution line for alum pumps.

Repaired electrical system on 6-inch Ford pump.

Rebuilt 5x8 lawn mower trailer.

State inspection and new wiper blades on LA-28 Mack tractor.

Checked ATAD harmonics cooling fans.

Tightened mounting bolts on mixer 1A second anoxic zone.

## Staff Activity Summary Report – May 2023

### Collection System

Responded to 201 PA-One Call utility location requests.

Inspected 8 lateral repairs, 0 lateral disconnects and 5 new service lateral connections.

Air and mandrel testing new mains of Arcona Phase 8.2.

Completed rapid sewer inspection on 4,498 feet of sewer main.

Flushed 3,770 feet of sewer main and 1 blockage call.

Completed internal camera inspection of 300 feet of sewer main.

### Treatment Plant

Replaced Exmark mower deck belts.

Replaced blades on Scag mower.

Replaced MCC cooling fan and filters.

Replaced broken weir plate brackets on all clarifiers.

Installed new weir plates and brackets on 3 final clarifier.

Tightened weir plate bolts on #1 and #2 final clarifiers.

Tightened weir plate bolts on #1 and #2 primary clarifiers.

Repaired biofilter drain pit pump, float and alarm.

Repaired lights on BNR tanks and substation #3.

State inspection on backhoe trailer.

State inspection on #1 and #2 Polar tankers.

Preventative maintenance on 6-inch Ford pump.

Preventative maintenance on LA-27 Chevy pickup.

## Staff Activity Summary Report – June 2023

### Collection System

Responded to 170 PA-One Call utility location requests.

Inspected 3 lateral repairs, 1 lateral disconnects and 3 new service lateral connections.

Air and mandrel testing new mains of Arcona Phase 8.2.

Completed rapid sewer inspection on 342 feet of sewer main.

Flushed 847 feet of sewer main and 2 blockage calls.

Completed internal camera inspection of 0 feet of sewer main.

### Treatment Plant

Replaced #1 air release valve at Raven Hill pump station.

Rebuilt gear box on thickner #2 drive and replaced motor.

Replaced flap valve #1 pump at Sheepford pump station.

Replaced #1 secondary return pump solenoid valve, PSI gauge, and cleaned out lines.

Replaced #2 main pump volute, suction cover, stand, and did preventative maintenance.

Preventative maintenance on #1 and #2 primary's clarifiers.

Replaced light LED tubes in office.

Replaced #1 main pump PSI gauge.

Repaired lights at wet well stairs.

Preventative maintenance on U.V. system.

Replaced Train #1 internal mixer pump.

## Staff Activity Summary Report – July 2023

### Collection System

Responded to 208 PA-One Call utility location requests.

Inspected 6 lateral repairs, 0 lateral disconnects and 9 new service lateral connections.

Air and mandrel testing new mains of Arcona Phase 8.2.

Completed rapid sewer inspection on 0 feet of sewer main.

Flushed 0 feet of sewer main and 0 blockage calls.

Completed internal camera inspection of 0 feet of sewer main.

Preventative maintenance on Sheepford pump station Gen-set.

Preventative maintenance on #1 pump and Gen-set at Beacon Hill pump station.

Preventative maintenance on #1 and #2 pumps at Shiremanstown pump station.

Preventative maintenance on #1 and #2 pumps at Methodist Home pump station.

### Treatment Plant

Repaired light in centrifuge room.

Rebuilt gear box on thickner #2 and replaced drive motor.

Reset VFD on U.V. room exhaust fan.

State inspection on LA-20 tv truck.

State inspection on LA-19 flusher truck.

Preventative maintenance on BNR Aerzen blowers #1 and #2.

Preventative maintenance on Exmark mower.

Preventative maintenance on push mower.

Preventative maintenance on Scag mower.

Preventative maintenance on all BNR aerators.

Preventative maintenance on all BNR mixers.

## Staff Activity Summary Report – August 2023

### Collection System

Responded to 190 PA-One Call utility location requests.

Inspected 0 lateral repairs, 0 lateral disconnects and 10 new service lateral connections.

Air and mandrel testing new mains of Arcona Phase 8.2.

Completed rapid sewer inspection on 0 feet of sewer main.

Flushed 0 feet of sewer main and 0 blockage calls.

Completed internal camera inspection of 0 feet of sewer main.

Preventative maintenance on Linda Lane pump station generator.

Preventative maintenance on Shiremanstown pump station generator.

Preventative maintenance on #1 and #2 pumps at Lisburn pump station.

### Treatment Plant

Repaired light in shop lunch room.

Repaired lights in U.V. building.

Repaired lights in sludge disposal building.

Repaired U.V. building exhaust fan.

Repaired valve in sludge disposal building.

Repaired #2 main pump drive unit wiring.

Preventative maintenance on John Deere gator.

Preventative maintenance on pressure washer.

Preventative maintenance, tune up and new front brake pads and rotors on L.A.-29 Ford F-350.

Preventative maintenance on L.A.-26 Ford F-150.

## Staff Activity Summary Report – September 2023

### Collection System

Responded to 206 PA-One Call utility location requests.

Inspected 5 lateral repairs, 0 lateral disconnects and 4 new service lateral connections.

Air and mandrel testing new mains of Arcona Phase 8.2.

Completed rapid sewer inspection on 0 feet of sewer main.

Flushed 1,161 feet of sewer main and 1 blockage calls.

Completed internal camera inspection of 0 feet of sewer main.

Replaced starter on #1 pump at Lisburn pump station.

### Treatment Plant

Repaired light on #2 final clarifier.

Replaced light on secondary pump room stairs.

Replaced buzzer on main gate to plant.

Replaced main pump #3 VFD.

Replaced oil seals and pressure gauge on BNR reaeration blower #2.

Replaced #2 bar screen outfall transducer.

State inspection on dig job trailer.

Installed new gear box on secondary anoxic mixer #1A on train #1.

## Staff Activity Summary Report – October 2023

### Collection System

Responded to 176 PA-One Call utility location requests.

Inspected 9 lateral repairs, 0 lateral disconnects and 2 new service lateral connections.

Air and mandrel testing new mains of Arcona Phase 8.2.

Completed rapid sewer inspection on 7,449 feet of sewer main.

Flushed 2,816 feet of sewer main and 0 blockage calls.

Completed internal camera inspection of 0 feet of sewer main.

Replaced air release valve at Raven Hill pump station.

### Treatment Plant

Repaired lights and speaker for phone system in centrifuge room.

Repaired lights in sludge disposal room first floor.

Repaired #2 main sewer pump.

Repaired leaks on washdown pump.

Repaired window drive and rear wiper arm on Ford Escape.

Repaired #3 RAS pump seal water line.

Reglazed lunch room windows.

Checked #1 primary scum pump and reset.

Checked all in-plant generators fluid levels and refueled them.

## Staff Activity Summary Report – November 2023

### Collection System

Responded to 140 PA-One Call utility location requests.

Inspected 5 lateral repairs, 0 lateral disconnects and 1 new service lateral connection.

Air and mandrel testing new mains of Arcona Phase 8.2.

Completed rapid sewer inspection on 0 feet of sewer main.

Flushed 556 feet of sewer main and 2 blockage calls.

Completed internal camera inspection of 0 feet of sewer main.

Repaired pump #1 at Methodist Home pump station.

### Treatment Plant

Repaired RAS pump #1 VFD in secondary pump room.

Repaired bar screen #2.

Repaired bar screen #1.

Repaired SNDR roof vent.

Repaired 4-20ma signal to main sewer pump #2 VFD.

Replaced ATAD foam pump VFD.

Replaced forklift bay heater thermostat.

Put main pump #3 VFD back in.

## Staff Activity Summary Report – December 2023

### Collection System

Responded to 116 PA-One Call utility location requests.

Inspected 5 lateral repairs, 0 lateral disconnects and 8 new service lateral connections.

Air and mandrel testing new mains of Arcona Phase 8.2.

Completed rapid sewer inspection on 0 feet of sewer main.

Flushed 233 feet of sewer main and 0 blockage call.

Completed internal camera inspection of 233 feet of sewer main.

### Treatment Plant

Repaired lights in wet well.

Repaired outside lights in plant.

Repaired radiant heater and replaced heater fans in old garage.

Repaired RAS pump #1 at #3 secondary RAS pump room.

Repaired wet well hoist.

Repaired LA-26 Ford F-150.

Preventative maintenance on primary waste pumps #1 and #2.

Preventative maintenance on centrifuge and ATAD grinders.

Preventative maintenance on SNDR jet pump.

Preventative maintenance on Aerzen blowers for ATAD and SNDR.

Preventative maintenance on ATAD jet pump and foam pump.

Preventative maintenance on #3 secondary RAS pumps #1 and #2.

Replaced cord reel on garage door in new garage.

Replaced air compressors in main sewer pump panel.

Replaced belts on biofilter fan.

Cleaned U.V. channel #1.

Cleaned #2 secondary waste pump out.

**Attachment 5 Pump Stations  
Lower Allen Township Authority  
NPDES PA0027189**

The Lower Allen Township Authority collection system includes eight pumping stations. Table 1 included in this section provides a summary of station capacity, design capacity, current maximum flow and two-year maximum flow. Based on current information, all pumping stations have sufficient capacity for the projected two-year flows and beyond.

The Upper Allen Township collection system tributary to the Lower Allen Township Authority sewer system includes two pumping stations, see Attachment 10 of this report.

The Pennsylvania American Water - Fairview Township collection system tributary to the Lower Allen Township Authority sewer system includes two pumping stations, see Attachment 9 of this report.

# TUS A-12\_Attachment

## Lower Allen Township Authority 2023 Pumping Station Flow Summary

<b>Township / Pump Station</b>	<b>Design Capacity GPD</b>	<b>Average Daily Flow GPD</b>	<b>Current Max.Flow GPD</b>	<b>Two-Year Max.Flow GPD</b>
<b>Lower Allen Township</b>				
Shiremanstown	684,000	40,712	46,455	46,455
Linda Lane	144,000	22,131	31,380	31,380
Sheepford Crossing	288,000	24,704	28,920	28,920
Raven Hill	360,000	88,229	109,750	109,750
Lisburn	288,000	30,519	38,640	36,000
Methodist Home	115,200	8,608	11,808	11,808
Beacon Hill	309,600	9,839	12,599	12,599
Windsor Park	230,400	15,907	18,112	18,112

### **Upper Allen Township**

See Attachment 10      Two Pump Stations

### **PAW-Fairview Township**

See Attachment 10      Two Pump Stations

# TUS A-12\_Attachment

**Attachment 6 Industrial Pretreatment Report  
Lower Allen Township Authority  
NPDES PA0027189**

There are three significant industrial dischargers located in Lower Allen Township, Dairy Farmers of America, The Warrell Corporation, and Supply Chain Facility at Yetter Court Vantage Foods PA LLC /Cargill Meat Solutions contributing flow to the Authority's wastewater treatment plant. The tributary municipalities identified no new significant industrial users (SIUs) connected to the collection system during the year.

No hauled or well drilling waste was received during the report period. There were no temporary discharge permits issued in 2023.

The 2023 Industrial Pretreatment Annual Report was submitted electronically to US EPA Region 3 as directed by the Agency and in accordance with the Authority's NPDES permit. A copy is provided to PADEP as required by the permit with this report as an attachment.

**Facility Name:** Lower Allen WWTP  
**Permit Number:** PA0027189  
**Reporting Period:** 2023  
**POTW Name:** Lower Allen Township Authority

[Return to Home](#)

## Reporting Period

January 1 to December 31 of year	2023
----------------------------------	------

## POTW Contacts

Control Authority Name	Lower Allen Township Authority
NPDES Permit No	PA0027189
Permit Issuance Date	6/1/2022
Permit Expiration Date	5/31/2027
Facility Name	Lower Allen WWTP
Facility Address1	120 Limekiln Road
Facility Address2	
Facility City	New Cumberland
Facility County	Cumberland
Facility State	PA
Facility Zip	17070-2428

## Pretreatment Contact(s) - List all Pretreatment Personnel

	Name	Title	Email
01	Brian Kauffman, PE	Manager/Engineer	bkauffman@latwp.org
02	Matthew Reitzel	Industrial Pretreatment Coordinator	mreitzel@latwp.org
03			
04			
05			
06			

Permit Signatory	Brian Kauffman, PE
Permit Signatory Title	Authority Assistant Secretary
Contact Phone	717-774-0610
Contact Email	bkauffman@latwp.org
POTW Site Address	120 Limekiln Road, New Cumberland, PA 17070-2428

## Additional Information

--

# TUS A-12\_Attachment

Facility Name: Lower Allen WWTP  
 Permit Number: PA0027189  
 Reporting Period: 2023  
 POTW Name: Lower Allen Township Authority

[Return to Home](#)

## POTW Information

Status of local limits

NPDES Effluent Violations?

Date of Violations

Cause of NPDES permit violations?

Sludge Disposal Method 1

Sludge Disposal Method 2

Sludge Disposal Method 3

Highest Treatment Level

Parameter(s)

## Treatment Types

Primary Clarification?	Yes	Lagoon?	No
Secondary Clarification?	Yes	Anaerobic Digestion?	No
Activated Sludge?	Yes	Aerobic Digestion?	Yes
Trickling Filter?	No	Chlorination?	No
Oxidation Ditch?	No	Dechlorination?	No
Biotowers?	No	UV Disinfection?	Yes
Rotating Biological Contacts?	No	BNR?	Yes
Other?			

POTW Design Flow (mgd)

POTW Actual Flow (mgd)

Total SIU Flow (mgd)

% Industrial Flow

POTW Organic (BOD) Design Capacity (lbs/day)

POTW TSS Design Capacity (lbs/day)

POTW Ammonia (NH3) Design Capacity (lbs/day)

Actual or Estimated total Flow for Commercial (Non-SIU) Dischargers (mgd)

## Additional Information

Facility Name: #NAME?  
 Permit Number: PA0027189  
 Reporting Period: 2023  
 POTW Name: Lower Allen Township Authority

[Return to Home](#)

## Program Implementation

### Number of Permitted Industrial Users as of December 31

CIUs	0	
Total SIUs	3	<i>Includes CIUs, but excludes NSCIUs</i>
Other Permitted IUs	0	
Zero-Discharge CIUs	0	
Permitted Zero-Discharge CIUs	0	
Middle-Tier CIUs	0	
Non-Significant CIUs	0	

SIUs with No/Expired Permit as of December 31	0
SIUs with Administratively Extended Permits >180 Days	0
Number of SIUs with current control mechanisms	3
Number of NSCIUs that have violated any pretreatment standard	0

### Number of SIUs in significant non-compliance (SNC) as of December 31

	CIUs	Non Categorical SIUs	Total SIUs
SNC Self-monitoring	0	0	0
SNC Reporting	0	0	0
SNC PT Standards	0	0	0
SNC Prohibitions	0	0	0
SNC Compliance Schedule	0	0	0
SNC Pass Through/Interference	0	0	0
SNC Other SNC Violations	0	0	0

Number of SIUs in significant non-compliance (SNC) at any time	0
Number of non-SIUs in significant non-compliance (SNC) at any time	0
Number of SIUs in SNC during the previous calendar year	0
SNC during the July to December period	0

# Permitted Non-SIUs With Unknown Compliance Status	0
# SIUs With Unknown Compliance Status	0
Does the ERP include escalating enforcement actions for SNC	Yes

	CIUs	Non Categorical SIUs	Total SIUs
Number of SIUs with compliance schedule as of December 31	0	0	0

### Additional Information

--

# TUS A-12\_Attachment

Facility Name: #NAME?  
Permit Number: PA0027189  
Reporting Period: 2023  
POTW Name: Lower Allen Township Authority

[Return to Home](#)

## Enforcement Actions

	Non-SIUs	SIUs
Number of NOVs	0	12
Number of Formal Enforcement Actions	0	0
Number of different IUs with Formal Enforcement Actions	0	0
Number of SIUs on formal compliance schedule	0	0

*Formal actions at any time during the reporting year including administrative orders, show cause hearings, out-of-court settlements that are formal settlements, termination of service, formal compliance schedules, penalty actions EXCEPT civil or criminal suits.*

	Civil	Criminal	Total
Number of suits filed against SIUs	0	0	0

	Non-SIUs	SIUs
Number of Different IUs From Whom Penalties Were Collected	0	0
Total Penalties Collected	\$ -	\$ -

Number of IUs Published As Being In SNC	0
---	---

### Additional Information

--

# TUS A-12\_Attachment

Facility Name: #NAME?  
Permit Number: PA0027189  
Reporting Period: 2023  
POTW Name: Lower Allen Township Authority

[Return to Home](#)

## Compliance Monitoring

	Non-SIU	SIU
Number of individual permits issued	0	0
Number of general permits issued	0	0
Number of inspections in the reporting year	0	3

Overview description of Non-SIU inspections

Number of SIUs not inspected during the reporting year

Number of SIUs that submitted required Self-Monitoring Reports

Number of SIUs not sampled during the reporting year

Number of SIUs in SNC With Self-Monitoring Requirements That Were Not Inspected or Sampled

Number of annual certification statements received by NSCIUs

Additional Information

# TUS A-12\_Attachment

Facility Name: #NAME?  
 Permit Number: PA0027189  
 Reporting Period: 2023  
 POTW Name: Lower Allen Township Aut

[Return to Home](#)

## Program Implementation - Resources

Number of Pretreatment FTEs	1
Significant Changes (+/- 20%) to The POTW's Pretreatment Program Budget or Staffing?	No
Source of Budget	user fees
Total Pretreatment Program Budget	\$ 135,000

Number of Jurisdictions Covered By Pretreatment Program	
Adequate delegation in each jurisdiction?	Yes
Miscellaneous Developments and Special Initiatives?	Yes

Additional three priority polutant scans of influent, effluent and slude above one minimum required. SIU sampling beyond minimum. Grease trap installation requirementon nonresidential food preparation establishments. Biosolids processing to meet Exeptional Quality Class A criteria.

*e.g., Fats, Oils, and Grease (FOG) program, PFAS monitoring*

### Additional Information

--

# TUS A-12\_Attachment

Facility Name: #NAME?  
 Permit Number: PA0027189  
 Reporting Period: 2023  
 POTW Name: Lower Allen Township Authority

[Return to Home](#)

## Program Implementation - Hauled Waste

### Does the POTW receive any discharges of

Receive Groundwater From Hydrocarbon Cleanup Site?	No
Receive Hauled Septage (Domestic Only)?	No
Receive Hauled Waste From Industrial Sources?	No
Receive Hauled Waste From Commercial Sources?	No
Receive Hauled Categorical Waste?	No
Receive Hauled Grease Interceptor/Trap Waste?	No
Receive Landfill Leachate?	No
Receive CERCLA Cleanup Wastes?	No
Receive Hazardous (RCRA) Waste?	No
RV Dump Stations in Service Area?	No
Receive Other Unique Waste?	No
Receive Oil & Gas Waste from Stripper wells?	No

*As defined at 40 CFR Part 261 and delivered by truck, rail or dedicated pipeline*

### If you accept any trucked or hauled waste, indicate all of the following that apply to your POTW

Legal Authority To Control Hauled Waste?	
POTW Issues Permits For Hauled Wastes?	
POTW Has A Designated Disposal Site For Hauled Wastes?	
POTW Controls Access At The Designated Disposal Station?	
POTW Uses A Manifest System To Track/Control Hauled Wastes?	
POTW Believes That Illegal Dumping May Be Occurring In Its Jurisdiction?	

### What parameter if any do you surcharge

Surcharge for BOD?	
Surcharge for TSS?	
Surcharge for Oil and Grease?	
Surcharge for Flow?	
Surcharge for Ammonia?	
Surcharge for COD?	
Surcharge for TKN?	
Surcharge for Other Parameters?	

### Additional Information

--

# TUS A-12\_Attachment

Facility Name: #NAME?  
Permit Number: PA0027189  
Reporting Period: 2023  
POTW Name: Lower Allen Township Auth

[Return to Home](#)

## Program Implementation - Pass/INTF

Instances Of Interference At The POTW?	No
Instances Of Pass Through At The POTW?	No

Receive Notification Of The Discharge Of Any Hazardous Waste?	No
---	----

If so, names of IUs

01	
02	
03	
04	
05	
06	
07	
08	
09	
10	
11	

### Additional Information

--

# TUS A-12\_Attachment

Facility Name: #NAME?  
 Permit Number: PA0027189  
 Reporting Period: 2023  
 POTW Name: Lower Allen Township Authority


[Return to Home](#)

## Attachment A: List of CIUs/SIUs

SIU	PERMIT INFO				Address (Number, Street, City, State, ZIP Code)	NPDES Permit No of POTW discharged to	SIU INFO			Limits Type	MWG	Jurisdiction	
	Issued	Effective	Expires	Permit Type			Sampled	Inspected	MRS				# of self-monitorings conducted/required
01	Dairy Farmers of America	8/30/2022	9/1/2022	8/31/2026	IP	4825 Gettysburg Rd	PA0027189	1	1	12	2/2	Concentration-based	Lower Allen Town
02	DFA 2022-26					Mechanicsburg, PA 17055							
03													
04													
05													
06													
07	Supply Chain Facility at Yetter Court (Cargill)	8/30/2022	9/1/2022	8/31/2026	IP	2700 Yetter Court	PA0027189	1	1	12	2/2	Concentration-based	Lower Allen Town
08	SCF 2022-28					Camp Hill, PA 17011							
09													
10													
11													
12	The Warrell Corporation	8/30/2022	9/1/2022	8/31/2026	IP	1250 Slate Hill Road	PA0027189	1	1	12	2/2	Concentration-based	Lower Allen Town
13	WC 2022-26					Camp Hill, PA 17011							
14													
15													
16													
17													
18													
19													
20													

Additional Information (e.g. Permit coverage changes compared to the previous reporting year)

# TUS A-12\_Attachment



Code1	SIC Code2	NAICS Code	Categorical Standard	Total Average Process Flow (gpd)	Total Average Facility Flow (gpd)	MTCIU or NSCIU?	Justification	Discharge Status	Description	SNC?
2086	2026	312111	N/A	157799	157799			Active, continuous	hot bottled milk coffee drink	No
201301	201302	311612	N/A	53866	65625			Active, continuous	beef and pork, cutting and packaging for direct sale	No
2064	2068	311392	N/A	10106	10106			Active, continuous	candy making and nut roasting	No



Facility Name: #NAME?  
Permit Number: PA0027189  
Reporting Period: 2023  
POTW Name: Lower Allen Township Authority

[Return to Home](#)

**Attachment B: Copy of Newspaper Notice of SNC**

*Provide a copy of the newspaper notice identifying all IUs which were in SNC during the reporting period. The notice must show the name of the paper and the date of publication.*

Copy of Newspaper Notice of SNC submitted?

**Additional Information**

# TUS A-12\_Attachment

Facility Name: #NAME?  
Permit Number: PA0027189  
Reporting Period: 2023  
POTW Name: Lower Allen Township Auth

[Return to Home](#)

## **Attachment C: Description of Each Incidence of Pass Through or Interference**

*Provide a description of each incidence of Pass Through or Interference at the wastewater treatment plant or collection system during the year, the cause if determined, and any actions taken by the POTW in response to the Pass Through or Interference.*

### **Description of Pass Through/Interference**

01	N/A
02	
03	
04	
05	
06	
07	
08	
09	
10	
11	

### **Additional Information**

--

# TUS A-12\_Attachment

Facility Name: #NAME?  
Permit Number: PA0027189  
Reporting Period: 2023  
POTW Name: Lower Allen Tow

[Return to Home](#)

## **Attachment D: Description of Significant Change in Program Funding/Staffing**

*An explanation of any significant decrease (20% or greater) in pretreatment funding or staffing of the POTW's Pretreatment Program.*

### **Description of Significant Change in Program Funding/Staffing**

N/A

**/End of Sheet**

Facility Name: Lower Allen WWTP  
 Permit Number: PA0027189  
 Reporting Period: 2023  
 POTW Name: Lower Allen Township Authority

Return to Home

**Attachment E1: Permitted Industrial Users (part 1 of 2)**

*Provide a printout or listing of all permitted non-SIUs*

Permitted Non-SIUs	Address	County	Jurisdiction	SIC Code	NAICS Code	Rationale for permitting these non-SIUs
01   N/A						
02						
03						
04						
05						
06						
07						
08						
09						
10						
11						
12						
13						
14						
15						
16						
17						
18						
19						
20						

Add more rows

Additional Information

Facility Name: Lower Allen WWTP  
Permit Number: PA0027189  
Reporting Period: 2023  
POTW Name: Lower Allen Township Authority

[Return to Home](#)

**Attachment E2: Permitted Industrial Users (part 2 of 2)**

*Provide a printout or listing of all SIUs covered by a General Permit*

	SIUs covered by a General Permit	Justification Criteria
01	N/A	
02		
03		
04		
05		
06		
07		
08		
09		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		

Add more rows

Additional Information

Facility Name: #NAME?  
 Permit Number: PA0027189  
 Reporting Period: 2023  
 POTW Name: Lower Allen Township Authority

[Return to Home](#)

### Attachment F: IUs in SNC During the Reporting Period

For those IUs in SNC during the Reporting Period

IU Name	Reason for SNC	Date of Enforcement Action		Type of Enforcement Action	Parameter(s) Violated	Date in Compliance	Penalties Assessed	Penalties Collected	Quarters In SNC	In SNC during PRP?
01	N/A									
02										
03										
04										
05										
06										
07										
08										
09										
10										
11										
12										
13										
14										
15										
16										
17										
18										
19										
20										

Add more rows

Additional Information

/End of Sheet

Facility Name: #NAME?  
Permit Number: PA0027189  
Reporting Period: 2023  
POTW Name: Lower Allen Township Authority

[Return to Home](#)

## Attachment G: Modification History

	Type of Modification	Description of Modification	Date of PN	Approval
01	N/A			
02				
03				
04				
05				
06				
07				
08				
09				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				

### Expected Modifications

--

# TUS A-12\_Attachment

Facility Name: #NAME?  
Permit Number: PA0027189  
Reporting Period: 2023  
POTW Name: Lower Allen Township Authority

[Return to Home](#)

## **Attachment H: Influent/Effluent and Biosolids Monitoring**

Influent Monitoring Results Submitted or Attached?	Yes	<i>Includes priority pollutant scan where applicable</i>
Effluent Monitoring Results Submitted or Attached?	Yes	
Biosolids Monitoring Results Submitted or Attached?	Yes	

**Additional Information**

--



The signature certification page must be printed, signed, and sent in hard copy to U.S. EPA Region 3 at the address below. The QR code must be visible.

Attn: U.S. EPA Region 3 Pretreatment [3WD41]  
Four Penn Center  
1600 John F Kennedy Blvd  
Philadelphia, PA 19103-2852

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

#NAME?



  
\_\_\_\_\_  
Authorized Signatory Official

03/21/2024

Date

BRIAN KAUFFMAN, ASST. SECRETARY  
Print or type name and title

Note: The Signatory Official is the person authorized by the POTW to sign the Annual Report (see 40 CFR Section 403.12(m)).

The following documents may be attached to the email or hard copies can be mailed to US EPA Region 3

1. A copy of the newspaper notice identifying all IUs which were in SNC during the reporting period. The notice must show the name of the paper and the date of publication.
2. The results of all influent monitoring results that were performed as required in the Pretreatment section of your state issued NPDES permit. The results must include the name of the pollutant, measured concentration, analytical method used, detection
3. The results of all effluent monitoring results from the monitoring required by the Pretreatment section of your state issued NPDES permit. Provide monitoring results for those pollutants that were reported above the detection limit. The results must include the
4. The results of all monitoring results for biosolids (sludge) monitoring for any pollutants listed in 40 CFR Part 122, Appendix D, Table II, III, and V. This is for final sludge to disposal only. This monitoring may have been required by your state issued NPDES permit, or

Time Stamp:

User Stamp:

Facility Name: LOWER ALLEN TOWNSHIP AUTHORITY		UNITS: MG/L		Date	Date	Date	Date	Date
Facility ID: PAP027189		Goals	Frequency	3/14/2023	6/8/2023	8/30/2023	12/5/2023	
Location: INFLUENT		Pollutant		Date	Date	Date	Date	Date
01002	ARSENIC- TOTAL	0.0136	4	<0.005	<0.005	<0.005	<0.005	
01027	CADMIUM- TOTAL	0.0087	4	<0.001	<0.001	<0.001	<0.001	
01034	CHROMIUM- TOTAL	0.404	4	<0.0025	<0.0025	<0.0025	<0.0025	
01042	COPPER- TOTAL	0.3374	4	0.034	0.036	0.049	0.042	
00720	CYANIDE- TOTAL	0.137	4	<.004	<.004	<.004	<.004	
01051	LEAD- TOTAL	0.0926	4	<0.003	<0.003	<0.003	<0.003	
71900	MERCURY- TOTAL	0.0042	4	<0.0002	<0.0002	<0.0002	<0.0002	
01062	MOLYBDENUM- TOTAL	0.0565	4	<0.01	<0.01	<0.01	<0.01	
01067	NICKEL- TOTAL	0.1492	4	<0.01	<0.01	<0.01	<0.01	
04166	PCB- TOTAL	0.0012	4	<0.000024	<0.000097	<0.000097	<0.0005	
01147	SELENIUM- TOTAL	0.0298	4	<0.01	<0.01	<0.01	<0.01	
01077	SILVER- TOTAL	0.3125	4	<0.002	<0.002	<0.002	<0.002	
01092	ZINC- TOTAL	0.411	4	0.14	0.15	0.06	0.12	







Facility Name:	LOWER ALLEN TOWNSHIP AUTHORITY		
Facility ID:	PAP027189		
Location:	<b>SLUDGE</b>		
	Pollutant	Date	Date
01002	ARSENIC- TOTAL	11/6/2023	11/16/2023
01027	CADMIUM- TOTAL	6.4	10.7
01034	CHROMIUM- TOTAL	<4.6	<7.8
01042	COPPER- TOTAL	45.65	56.8
00720	CYANIDE- TOTAL	648.05	779
01051	LEAD- TOTAL	<2.8	2.8
71900	MERCURY- TOTAL	13.45	18.1
01062	MOLYBDENUM- TOTAL	0.51	0.58
01067	NICKEL- TOTAL	14.25	15.8
04166	PCB- TOTAL	27.05	29.3
01147	SELENIUM- TOTAL	<0.085	<0.13
01077	SILVER- TOTAL	<12.4	<19.6
01092	ZINC- TOTAL	3.1	3.1
		1878.05	1980

**Attachment 7 Sewage Sludge  
Lower Allen Township Authority  
NPDES PA0027189**

The Phase 1 Solids Facility Upgrade Project was completed and placed into operation in 2011. The PADEP issued the Authority a Beneficial Use Exceptional Quality Class A Biosolids permit in February 2012, PAG-07-3519. The Notice of Intent for continued use was granted by the Department and General Permit extensions as published by the Department.

The biosolids data indicates the quality remains high with the concentrations of regulated parameters lower than regulatory limits for high quality land application material, volatile solids reduction exceeds the minimum requirement, and quarterly fecal coliform bacteria analysis are significantly below the limit for classification as a beneficial use Exceptional Quality Class A biosolids material.

The 2023 calculated expected sewage sludge production using the Department mandated methodology contained in the 1984 EPA Handbook Improving POTW Performance is 821.8 dry tons, see the following page 1. The plant solids process data indicates the sewage sludge production was 814.2 dry tons prior to digestion, and after digestion biosolids production was 385.5 dry tons before dewatering, see page 2. During 2023, biosolids distribution totaled 404.6 with 373.2 dry tons going to beneficial use and 31.4 dry tons sent to Harrisburg AWWTF.

Annual Biosolids Reports for 2023 were submitted in February 2023 to the PADEP and EPA Region 7 as required by permit conditions and should be referenced for additional program details.

The 2023 annual average effluent flow was 4.9 MGD, average influent BOD concentration was 130 mg/L and the average effluent CBOD concentration was 3.0 mg/L. The combined total volume of primary and waste activated sludge flow was 42,626,100 gallons and the average solids concentration of return activated sludge was 10,594 mg/L as reported in the DMRs submitted to PADEP and EPA Region 3, see page 2 of this attachment.

The DEP sludge Calculator 1 indicates the actual wasted amount is 136% greater than the calculated amount and the DEP Calculator 2 indicates actual production is more than 15% less than the calculated value. It is noted that Calculator 1 does not include 1.7 lbs/TSS for primary sludge and Calculator 2 uses 0.4 digester reduction factor and our reduction for the year is 0.52 in line with the 0.5 value used in calculator 1.

Lower Allen Township Authority  
 Expected Sewage Sludge Production 2022

DEP Mandated Methodology - EPA Handbook Improving POTW Performance 1984

Month	Days	Influent		BNR Infl.		Effluent		Primary Sludge lbs/D (1)	Secondary Sludge lbs/D (1)	Total	
		Flow MGD	BOD mg/L	BOD mg/L		Flow MGD	CBOD mg/L			Sludge lbs/D	DT/Mon.
January	31	5.515	138	119		5.446	4.3	1485.6	3646.7	5132.4	79.6
February	28	4.538	150	113		4.441	3.8	2380.6	2831.2	5211.8	73.0
March	31	4.992	128	101		4.740	3.3	1911.0	2703.6	4614.5	71.5
April	30	4.674	135	108		5.35	2.3	1789.2	3301.4	5090.6	76.4
May	31	5.604	120	109		5.641	2.9	874.0	3494.1	4368.1	67.7
June	30	4.399	139	117		4.369	3.1	1372.1	2905.2	4277.3	64.2
July	31	5.75	105	84		6.042	1.6	1712.0	2906.5	4618.5	71.6
August	31	4.243	140	110		4.114	2.1	1804.7	2591.5	4396.2	68.1
September	30	4.368	122	102		3.851	1.6	1238.6	2257.2	3495.8	52.4
October	31	4.522	130	95		3.416	1.8	2244.0	1858.7	4102.6	63.6
November	30	4.148	138	109		3.497	4.6	1705.5	2131.4	3836.9	57.6
December	31	6.044	119	90		4.863	4.2	2485.1	2435.9	4920.9	76.3
<b>TOTAL</b>		<b>4.900</b>	<b>130</b>			<b>4.648</b>	<b>3.0</b>			<b>4505.464</b>	<b>821.8</b>
<b>AVERAGE</b>											

Notes:

1. EPA Unit Sludge Production Values: Primary Clarification 1.7 lbs TSS sludge/ lb BOD Removed; Activated Sludge w/Primary Clarifier 0.7 lbs TSS sludge/ lb BOD Removed
2. EPA sludge production values are assumed and do not reflect BNR process conditions.
3. Method does not properly account for changes in recycle loads at higher flows.

Lower Allen Township Authority  
 Expected Sewage Sludge Production 2023  
 Based On Monthly Solids Process Data

Month	Days	Primary Sludge MG	WAS Pumped MG	RAS Concent. mg/L	ATAD Feed MG	Solids %	Total (1) Sludge DT/Mon.	ATAD Feed VSS %	ATAD VSS Reduc %	Total (2) Biosolids DT/Mon.
January	31	1.544700	1.849400	13580	0.468100	3.86	75.3	83.35	66.15	33.8
February	28	2.015700	1.775100	12685	0.375800	3.75	58.8	83.33	59.92	29.4
March	31	1.572500	1.921500	12023	0.450500	4.12	77.4	84.83	62.48	36.4
April	30	1.418900	1.911100	10343	0.304700	4.22	53.6	84.46	66.84	23.3
May	31	1.706200	2.280600	9325	0.414100	3.75	64.8	82.29	63.26	31.0
June	30	1.738500	1.775300	10913	0.427200	3.36	59.9	81.33	57.18	32.0
July	31	1.814600	1.950500	9264	0.516900	3.56	76.7	82.65	60.55	38.3
August	31	1.630800	1.567300	9197	0.440900	3.73	68.6	82.58	63.25	32.8
September	30	1.605300	1.290900	10877	0.487100	3.75	76.2	82.72	64.96	35.2
October	31	1.742000	2.151600	9635	0.453900	3.91	74.0	82.18	60.87	37.0
November	30	1.678600	1.928800	9957	0.384200	4.13	66.2	83.53	66.26	29.5
December	31	1.823400	1.932800	9325	0.339900	4.43	62.8	84.25	68.39	26.6

TOTAL	20.291200	22.334900	5.063300	814.2	385.5
AVERAGE			10594	83	63
Notes:			3.88		

1. Based on actual combined thickened primary and WAS sludge measured values in ATAD Feed.
2. Based on actual measured ATAD VSS reduction values prior to dewatering.

# TUS A-12\_Attachment

## Solids Management (Sludge) Calculator

This worksheet calculates the expected sludge volume that should be produced by various treatment processes over a one-year period. Enter data into green cells - hit the Tab key to move between cells. Red cells are calculated.

Facility Name: **Lower Allen WWTP** Permit No.: **PA0027189**

Evaluation Period: **1/1/2023** to **12/31/2023**

Design Flow: **7.5** MGD Actual Annual Average Flow: **4.9** MGD

Type of Biological Treatment Process: **Activated Sludge with Primary Clarification** Treatment Factor: **0.7**

Type of Digestion Process: **Aerobic Thermophilic** Digestion Factor: **0.5**

Total Population Served by Treatment Plant: **45,296**

Average Annual Influent BOD5 Load (per Ch. 94 Report): **5,209.0** lbs/day

Average Annual Influent BOD5 Load (Expected based on Population): **7,700.3** lbs/day (Population x 0.17)

% of Influent BOD5 Load per Ch. 94 Report / Influent Load Expected: **67.6%** (Influent Load per Ch. 94 Report / Influent Load based on Population)

Average Annual Effluent Concentration of **CBOD5**: **3** mg/L **Assume 3.6 mg/L BOD5**

Average Annual Pounds (lbs) of BOD5 Discharged: **147.12** lbs/day (Actual Flow x Effluent BOD5 Concentration x 8.34)

Influent BOD5 Load per Person per Day (based on Ch. 94): **0.115** (Influent BOD5 Load per Ch. 94 Report / Population - 0.17 to 0.22 is typical)

Pounds of BOD5 Removed (based on Ch. 94): **5,061.9** lbs/day (Influent BOD5 Load per Ch. 94 Report - BOD5 Discharged)

Pounds of BOD5 Removed (based on Population): **7,553.2** lbs/day (Influent BOD5 Load Expected based on Population - BOD5)

Sludge Removed from Treatment Plant (Previous Year): **440.9** Dry Tons = **881,800** Dry lbs

### Sludge Production and Wasting Calculations

#### Based on Chapter 94 Report

X	<b>5,061.9</b>	BOD5 Removed / Day (lbs)
	<b>0.7</b>	Treatment Factor
	<b>3,543.32</b>	Daily Solids Production (lbs)
X	<b>0.5</b>	Digestion Factor
	<b>1,771.66</b>	Daily Digested Solids (lbs)
X	<b>365</b>	Days per Year
	<b>646,655</b>	Solids Generated / Year (lbs)
-	<b>881,800</b>	Solids Actually Wasted / Year (lbs)
	<b>-235,145</b>	Difference (lbs)
	<b>136%</b>	% of Expected Volume Wasted (85 - 115% is generally acceptable)
	<b>3.9%</b>	Percent Solids of Wasted Solids
	<b>1,998,367</b>	Volume of Solids to Remove Annually (gallons)
-	<b>2,725,036</b>	Volume of Solids Actually Removed Annually (gallons)
	<b>-726,670</b>	Difference (gallons)

#### Based on Population

X	<b>7,553.2</b>	BOD5 Removed / Day (lbs)
	<b>0.7</b>	Treatment Factor
	<b>5,287.24</b>	Daily Solids Production (lbs)
X	<b>0.5</b>	Digestion Factor
	<b>2,643.62</b>	Daily Digested Solids (lbs)
X	<b>365</b>	Days per Year
	<b>964,922</b>	Solids Generated / Year (lbs)
	<b>881,800</b>	Solids Actually Wasted / Year (lbs)
	<b>83,122</b>	Difference (lbs)
	<b>91%</b>	% of Expected Volume Wasted (85 - 115% is generally acceptable)
	<b>3.9%</b>	Percent Solids of Removed Solids
	<b>2,981,908</b>	Volume of Solids to Remove Annually (gallons)
-	<b>2,725,036</b>	Volume of Solids Actually Removed Annually (gallons)
	<b>256,872</b>	Difference (gallons)

## SLUDGE GENERATION CALCULATION

Facility Name:

Permit Number:

Date of Calculation:

### Required Information For Calculation

Average Daily Flow (mgd):  Digester Capacity (gal):

Influent BOD (mg/l):  %Solids of Outgoing Sludge:

Effluent BOD (mg/l):  Monitoring Period (days):

### Wastewater Treatment Processes

Place an "X" in the box beside the corresponding treatment process. Select a maximum of Primary Clarification and one other treatment process.

Primary Clarification       Contact Stabilization       RBC   
 Conventional Activated Sludge       SBR       ABF   
 Extended Aeration       Trickling Filter       Small Plant with low SOR   
 (<500 gpd/sq ft)

### Operational Information

BOD Removed (lbs/day):  TSS Removed (lbs/day):

### Digester Information

#### Type of Digester

Place an "X" in the box beside the corresponding treatment process.

Aerobic Digestion       Anaerobic Digestion       None

Sludge Feed Rate to Digesters (gpd):

Digester Hydraulic Detention Time (days):

Estimated Total Solids Reduction (%):

### Sludge Generation

dry lbs/day  wet lbs/day

dry tons/monitoring period  wet tons/monitoring period

gal/day  gal/monitoring period

### Amount of Sludge Reported as Being Generated by the Facility

wet tons/monitoring period

OR

dry tons/monitoring period

Enter only one of the above values. The remaining value should be "0".

Is the amount reported by the generator within 15% of the calculated value?

NO explanation:

What type of information was used to calculate the above information:

Dates used:  TO

Name of person performing the calculation:

# TUS A-12\_Attachment

**Attachment 8 Flow Meter Calibration**  
**Lower Allen Township Authority**  
**NPDES PA0027189**

The treatment plant influent and effluent flow metering equipment were checked for calibration and operational parameters per the manufacturer's specifications monthly. Copies of the meter certifications are included in this section.



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 76674

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** CEDAR RUN

**Description** Flow Meter  
**Manufacturer** Sigma  
**Model Number** 950  
**Serial Number** N/A  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 40  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 01/10/2023  
**Next Due Date** 02/28/2023

### Calibration Specifications

**Group Name** MGD

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	0.40 MGD	+/-0.02	0.40 MGD	P	0.40 MGD	P	0.00

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Tim Starr

Finalized By: Tim Starr 10 January 2023 9:01:54AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 76675

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID ROSSMOYNE

Description Flow Meter  
Manufacturer Hach  
Model Number SC200  
Serial Number 8712A808118  
Location N/A  
Building N/A  
Department N/A

Status Active  
Temp °F 40  
Cal Proc 4.8  
Adjusted To Improve Yes  
Calibration Frequency Monthly  
Calibrated 01/10/2023  
Next Due Date 02/28/2023

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	1.08 MGD	+0.05/-0.05	1.39 MGD	*F*	1.06 MGD	P	-0.02

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Tim Starr

Finalized By: Tim Starr 10 January 2023 9:07:15AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 76676

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID SCIC PRISON METER

Description Flow Meter  
Manufacturer Hach  
Model Number SC200  
Serial Number 1412C0141778  
Location N/A  
Building N/A  
Department N/A

Status Active  
Temp °F 40  
Cal Proc 4.8  
Adjusted To Improve No  
Calibration Frequency Monthly  
Calibrated 01/10/2023  
Next Due Date 02/28/2023

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	256.400 GPM	+12.820/-12.820	256.700 GPM	P	256.700 GPM	P	0.300

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Tim Starr

Finalized By: Tim Starr 10 January 2023 9:19:02AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 76677

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID PLANT INFLUENT

Description Flow Meter  
Manufacturer Hach  
Model Number SC200  
Serial Number 1506C0147261  
Location Influent  
Building  
Department N/A

Status Active  
Temp °F 70  
Cal Proc 4.8  
Adjusted To Improve No  
Calibration Frequency Monthly  
Calibrated 01/10/2023  
Next Due Date 02/28/2023

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	5.909 MGD	+/-0.295	5.860 MGD	P	5.860 MGD	P	-0.049

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Tim Starr

Finalized By: Tim Starr 10 January 2023 9:38:18AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 76678

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID EFFLUENT FLOW

Description	Flow Meter	Status	Active
Manufacturer	Siemens	Temp °F	60
Model Number	OCM III	Cal Proc	4.8
Serial Number	PBD/U1090008-022405101XV	Adjusted To Improve	No
Location	N/A	Calibration Frequency	Monthly
Building	N/A	Calibrated	01/10/2023
Department	N/A	Next Due Date	02/28/2023

### Calibration Specifications

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
Group Name Inches (Pass 1)							
1	1.000 Inches	+/-0.020	1.130 Inches	*F*	0.980 Inches	P	-0.020
Group Name Echo Strength (D-18) Pass 1							
1	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00
Group Name Inches (Pass 2)							
1	1.000 Inches	+/-0.020	0.980 Inches	P	0.980 Inches	P	-0.020
Group Name Echo Strength (D-18) Pass 2							
1	100.00 %	+/-50.00	81.00 %	P	81.00 %	P	-19.00

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customer's location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Print Date: 01/10/2023

Page 1 of 2

Control Systems 21

713 Range End Rd. • Dillsburg, PA 17019 • Voice: 717 432-5511 • Fax: 717 432-7550  
email@controlsystems21.com



# Control Systems 21

"Your Process Control Specialists"

## *CERTIFICATE of CALIBRATION*

Cal Certificate # 76678

Calibration Result: Calibration Successful

Calibrated By: Tim Starr

Finalized By: Tim Starr 10 January 2023 11:48:46AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 77583

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID CEDAR RUN

Description Flow Meter  
Manufacturer Sigma  
Model Number 950  
Serial Number N/A  
Location N/A  
Building N/A  
Department N/A

Status Active  
Temp °F 40  
Cal Proc 4.8  
Adjusted To Improve No  
Calibration Frequency Monthly  
Calibrated 02/08/2023  
Next Due Date 03/31/2023

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	0.36 MGD	+/-0.02	0.37 MGD	P	0.37 MGD	P	0.01

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 08 February 2023 8:28:14AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 77584

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID ROSSMOYNE

Description Flow Meter  
Manufacturer Hach  
Model Number SC200  
Serial Number 8712A808118  
Location N/A  
Building N/A  
Department N/A

Status Active  
Temp °F 40  
Cal Proc 4.8  
Adjusted To Improve Yes  
Calibration Frequency Monthly  
Calibrated 02/08/2023  
Next Due Date 03/31/2023

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	1.07 MGD	+0.05/-0.05	1.21 MGD	*F*	1.07 MGD	P	0.00

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 08 February 2023 8:45:19AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 77585

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** SCIC PRISON METER

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1412C0141778  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 40  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 02/08/2023  
**Next Due Date** 03/31/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	250.800 GPM	+/-12.540	262.600 GPM	P	262.600 GPM	P	11.800

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 08 February 2023 8:56:09AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 77586

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID PLANT INFLUENT

Description Flow Meter  
Manufacturer Hach  
Model Number SC200  
Serial Number 1506C0147261  
Location Influent  
Building  
Department N/A

Status Active  
Temp °F 70  
Cal Proc 4.98  
Adjusted To Improve No  
Calibration Frequency Monthly  
Calibrated 02/08/2023  
Next Due Date 03/31/2023

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	5.412 MGD	+0.271/-0.27	5.400 MGD	P	5.400 MGD	P	-0.012

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customer's location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 08 February 2023 9:19:36AM

Print Date: 02/08/2023

Page 1 of 1

Control Systems 21

713 Range End Rd. • Dillsburg, PA 17019 • Voice: 717 432-5511 • Fax: 717 432-7550  
email@controlsystems21.com



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 77587

**Company Name** Lower Allen Township  
 120 Limekiln Road  
 New Cumberland, PA 17070

**Instrument ID** EFFLUENT FLOW

<b>Description</b>	Flow Meter	<b>Status</b>	Active
<b>Manufacturer</b>	Siemens	<b>Temp °F</b>	60
<b>Model Number</b>	OCM III	<b>Cal Proc</b>	4.8
<b>Serial Number</b>	PBD/U1090008-022405101XV	<b>Adjusted To Improve</b>	No
<b>Location</b>	N/A	<b>Calibration Frequency</b>	Monthly
<b>Building</b>	N/A	<b>Calibrated</b>	02/08/2023
<b>Department</b>	N/A	<b>Next Due Date</b>	03/31/2023

### Calibration Specifications

<b>Group Name</b> Inches (Pass 1)							
<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	-2.500 Inches	+/-0.050	-2.500 Inches	P	-2.500 Inches	P	0.000
-----							
<b>Group Name</b> Echo Strength (D-18) Pass 1							
<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00
-----							
<b>Group Name</b> Inches (Pass 2)							
<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	0.875 Inches	+0.018/-0.01	0.870 Inches	P	0.870 Inches	P	-0.005
-----							
<b>Group Name</b> Echo Strength (D-18) Pass 2							
<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.



## Control Systems 21

"Your Process Control Specialists"

### *CERTIFICATE of CALIBRATION*

Cal Certificate # 77587

Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 08 February 2023 9:29:27AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 78306

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID CEDAR RUN

Description Flow Meter  
Manufacturer Sigma  
Model Number 950  
Serial Number N/A  
Location N/A  
Building N/A  
Department N/A

Status Active  
Temp °F 40  
Cal Proc 4.8  
Adjusted To Improve No  
Calibration Frequency Monthly  
Calibrated 03/07/2023  
Next Due Date 04/30/2023

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	0.39 MGD	+/-0.02	0.38 MGD	P	0.38 MGD	P	-0.01

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 March 2023 8:27:26AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 78307

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** ROSSMOYNE

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 8712A808118  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 40  
**Cal Proc** 4.8  
**Adjusted To Improve** Yes  
**Calibration Frequency** Monthly  
**Calibrated** 03/07/2023  
**Next Due Date** 04/30/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	1.08 MGD	+0.05/-0.05	0.99 MGD	*F*	1.05 MGD	P	-0.03

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 March 2023 8:43:48AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 78308

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** SCIC PRISON METER

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1412C0141778  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 40  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 03/07/2023  
**Next Due Date** 04/30/2023

### Calibration Specifications

**Group Name** MGD

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	303.100 GPM	+/-15.155	302.200 GPM	P	302.200 GPM	P	-0.900

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

*Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.*

*Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).*

*Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print*

*All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.*

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 March 2023 8:55:06AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 78309

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** PLANT INFLUENT

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1506C0147261  
**Location** Influent  
**Building**  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 03/07/2023  
**Next Due Date** 04/30/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	5.990 MGD	+0.300/-0.29	6.050 MGD	P	6.050 MGD	P	0.060
		9					

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 March 2023 9:12:12AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 78310

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** EFFLUENT FLOW

<b>Description</b>	Flow Meter	<b>Status</b>	Active
<b>Manufacturer</b>	Siemens	<b>Temp °F</b>	70
<b>Model Number</b>	OCM III	<b>Cal Proc</b>	4.8
<b>Serial Number</b>	PBD/U1090008-022405101XV	<b>Adjusted To Improve</b>	No
<b>Location</b>	N/A	<b>Calibration Frequency</b>	Monthly
<b>Building</b>	N/A	<b>Calibrated</b>	03/07/2023
<b>Department</b>	N/A	<b>Next Due Date</b>	04/30/2023

### Calibration Specifications

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
<b>Group Name</b> Inches (Pass 1)							
1	0.700 Inches	+/-0.014	0.710 Inches	P	0.710 Inches	P	0.010

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
<b>Group Name</b> Echo Strength (D-18) Pass 1							
1	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
<b>Group Name</b> Inches (Pass 2)							
1	-0.270 Inches	+0.005/-0.00	-0.270 Inches	P	-0.270 Inches	P	0.000
5							

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
<b>Group Name</b> Echo Strength (D-18) Pass 2							
1	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

Print Date: 03/07/2023

Page 1 of 2

Control Systems 21

713 Range End Rd. • Dillsburg, PA 17019 • Voice: 717 432-5511 • Fax: 717 432-7550  
email@controlsystems21.com



# Control Systems 21

"Your Process Control Specialists"

## *CERTIFICATE of CALIBRATION*

Cal Certificate # 78310

Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 March 2023 9:22:13AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 79188

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** CEDAR RUN

**Description** Flow Meter  
**Manufacturer** Sigma  
**Model Number** 950  
**Serial Number** N/A  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 50  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 04/12/2023  
**Next Due Date** 05/31/2023

### Calibration Specifications

**Group Name** MGD

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	0.45 MGD	+/-0.02	0.46 MGD	P	0.46 MGD	P	0.01

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 12 April 2023 8:50:23AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 79189

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID ROSSMOYNE

Description Flow Meter  
Manufacturer Hach  
Model Number SC200  
Serial Number 8712A808118  
Location N/A  
Building N/A  
Department N/A

Status Active  
Temp °F 50  
Cal Proc 4.8  
Adjusted To Improve No  
Calibration Frequency Monthly  
Calibrated 04/12/2023  
Next Due Date 05/31/2023

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	1.02 MGD	+/-0.05	0.99 MGD	P	0.99 MGD	P	-0.03

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 12 April 2023 9:02:00AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 79190

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** SCIC PRISON METER

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1412C0141778  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 50  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 04/12/2023  
**Next Due Date** 05/31/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	191.700 GPM	+/-9.585	198.800 GPM	P	198.800 GPM	P	7.100

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 12 April 2023 9:16:04AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 79191

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** PLANT INFLUENT

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1506C0147261  
**Location** Influent  
**Building**  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 04/12/2023  
**Next Due Date** 05/31/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	4.697 MGD	+0.235/-0.23	4.710 MGD	P	4.710 MGD	P	0.013
		5					

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 12 April 2023 9:33:08AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 79192

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID EFFLUENT FLOW

Description	Flow Meter	Status	Active
Manufacturer	Siemens	Temp °F	70
Model Number	OCM III	Cal Proc	4.8
Serial Number	PBD/U1090008-022405101XV	Adjusted To Improve	No
Location	N/A	Calibration Frequency	Monthly
Building	N/A	Calibrated	04/12/2023
Department	N/A	Next Due Date	05/31/2023

### Calibration Specifications

Test Point	Group Name	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	Inches (Pass 1)	-1.875 Inches	+0.037/-0.03	-1.910 Inches	P	-1.910 Inches	P	-0.035
8								

Test Point	Group Name	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	Echo Strength (D-18) Pass 1	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00

Test Point	Group Name	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	Inches (Pass 2)	1.150 Inches	+0.023/-0.02	1.150 Inches	P	1.150 Inches	P	0.000
3								

Test Point	Group Name	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	Echo Strength (D-18) Pass 2	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

Print Date: 04/12/2023

Page 1 of 2

Control Systems 21

713 Range End Rd. • Dillsburg, PA 17019 • Voice: 717 432-5511 • Fax: 717 432-7550  
email@controlsystems21.com



## Control Systems 21

"Your Process Control Specialists"

### *CERTIFICATE of CALIBRATION*

Cal Certificate # 79192

Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 12 April 2023 9:44:39AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 79628

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID CEDAR RUN

Description Flow Meter  
Manufacturer Sigma  
Model Number 950  
Serial Number N/A  
Location N/A  
Building N/A  
Department N/A

Status Active  
Temp °F 50  
Cal Proc 4.8  
Adjusted To Improve No  
Calibration Frequency Monthly  
Calibrated 05/02/2023  
Next Due Date 06/30/2023

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	0.55 MGD	+0.03/-0.03	0.54 MGD	P	0.54 MGD	P	-0.01

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 02 May 2023 8:27:12AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 79629

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** ROSSMOYNE

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 8712A808118  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 50  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 05/02/2023  
**Next Due Date** 06/30/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	1.81 MGD	+/-0.09	1.81 MGD	P	1.81 MGD	P	0.00

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 02 May 2023 8:45:34AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 79630

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID SCIC PRISON METER

Description	Flow Meter	Status	Active
Manufacturer	Hach	Temp °F	50
Model Number	SC200	Cal Proc	4.8
Serial Number	1412C0141778	Adjusted To Improve	No
Location	N/A	Calibration Frequency	Monthly
Building	N/A	Calibrated	05/02/2023
Department	N/A	Next Due Date	06/30/2023

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	256.400 GPM	+12.820/-12.820	258.100 GPM	P	258.100 GPM	P	1.700

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 02 May 2023 9:24:56AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 79631

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID RAVEN HILL PUMP STATION

Description Flow Meter  
Manufacturer E & H  
Model Number ProMag 53  
Serial Number N2039116000  
Location N/A  
Building N/A  
Department N/A

Status Active  
Temp °F 55  
Cal Proc 4.9  
Adjusted To Improve No  
Calibration Frequency 6 Months  
Calibrated 05/02/2023  
Next Due Date 11/30/2023

### Calibration Specifications

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
<b>Group Name</b> Transmitter Test % Deviation @ 5%							
1	0.00 %	+/-1.50	0.74 %	P	0.74 %	P	0.74
<b>Group Name</b> Transmitter Test % Deviation @ 10%							
1	0.00 %	+/-1.00	0.99 %	P	0.99 %	P	0.99
<b>Group Name</b> Transmitter Test % Deviation @ 50%							
1	0.00 %	+/-0.60	0.10 %	P	0.10 %	P	0.10
<b>Group Name</b> Transmitter Test % Deviation @ 100%							
1	0.00 %	+/-0.55	-0.07 %	P	-0.07 %	P	-0.07

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
E&H SIMUBOX	Endress & Hauser Flowtec AG	CH-4153	D7186102000	11/30/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

Print Date: 05/02/2023

Page 1 of 2

Control Systems 21

713 Range End Rd. • Dillsburg, PA 17019 • Voice: 717 432-5511 • Fax: 717 432-7550  
email@controlsystems21.com



## Control Systems 21

"Your Process Control Specialists"

### *CERTIFICATE of CALIBRATION*

Cal Certificate # 79631

Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 02 May 2023 9:20:10AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 79632

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** PLANT INFLUENT

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1506C0147261  
**Location** Influent  
**Building**  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 05/02/2023  
**Next Due Date** 06/30/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	9.295 MGD	+/-0.465	9.320 MGD	P	9.320 MGD	P	0.025

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 02 May 2023 9:52:23AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 79633

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** EFFLUENT FLOW

<b>Description</b>	Flow Meter	<b>Status</b>	Active
<b>Manufacturer</b>	Siemens	<b>Temp °F</b>	60
<b>Model Number</b>	OCM III	<b>Cal Proc</b>	4.8
<b>Serial Number</b>	PBD/U1090008-022405101XV	<b>Adjusted To Improve</b>	No
<b>Location</b>	N/A	<b>Calibration Frequency</b>	Monthly
<b>Building</b>	N/A	<b>Calibrated</b>	05/02/2023
<b>Department</b>	N/A	<b>Next Due Date</b>	06/30/2023

### Calibration Specifications

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
<b>Group Name</b> Inches (Pass 1)							
1	0.760 Inches	+/-0.015	0.770 Inches	P	0.770 Inches	P	0.010
<b>Group Name</b> Echo Strength (D-18) Pass 1							
1	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00
<b>Group Name</b> Inches (Pass 2)							
1	0.850 Inches	+/-0.017	0.840 Inches	P	0.840 Inches	P	-0.010
<b>Group Name</b> Echo Strength (D-18) Pass 2							
1	100.00 %	+/-50.00	98.00 %	P	98.00 %	P	-2.00

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
M-003	Komelon	SL2825	N/A	5/31/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Print Date: 05/02/2023

Page 1 of 2

Control Systems 21

713 Range End Rd. • Dillsburg, PA 17019 • Voice: 717 432-5511 • Fax: 717 432-7550  
email@controlsystems21.com



# Control Systems 21

"Your Process Control Specialists"

## *CERTIFICATE of CALIBRATION*

Cal Certificate # 79633

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 02 May 2023 10:26:55AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 80192

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** CEDAR RUN

**Description** Flow Meter  
**Manufacturer** Sigma  
**Model Number** 950  
**Serial Number** N/A  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 06/07/2023  
**Next Due Date** 07/31/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	1.53 MGD	+/-0.08	1.53 MGD	P	1.53 MGD	P	-0.02

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 June 2023 8:28:25AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 80193

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID ROSSMOYNE

Description Flow Meter  
Manufacturer Hach  
Model Number SC200  
Serial Number 8712A808118  
Location N/A  
Building N/A  
Department N/A

Status Active  
Temp °F 70  
Cal Proc 4.8  
Adjusted To Improve No  
Calibration Frequency Monthly  
Calibrated 06/07/2023  
Next Due Date 07/31/2023

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	0.86 MGD	+/-0.04	0.85 MGD	P	0.85 MGD	P	-0.01

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 June 2023 8:41:02AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 80194

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** SCIC PRISON METER

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1412C0141778  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 06/07/2023  
**Next Due Date** 07/31/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	352.600 GPM	+/-17.630	358.500 GPM	P	358.500 GPM	P	5.900

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 June 2023 8:54:48AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 80195

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** PLANT INFLUENT

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1506C0147261  
**Location** Influent  
**Building**  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 06/07/2023  
**Next Due Date** 07/31/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	4.697 MGD	+0.235/-0.23	4.920 MGD	P	4.920 MGD	P	0.223
		5					

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 June 2023 9:11:37AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 80196

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID EFFLUENT FLOW

Description	Flow Meter	Status	Active
Manufacturer	Siemens	Temp °F	70
Model Number	OCM III	Cal Proc	4.8
Serial Number	PBD/U1090008-022405101XV	Adjusted To Improve	No
Location	N/A	Calibration Frequency	Monthly
Building	N/A	Calibrated	06/07/2023
Department	N/A	Next Due Date	07/31/2023

### Calibration Specifications

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	-2.125 Inches	+0.042/-0.04	-2.160 Inches	P	-2.160 Inches	P	-0.035
3							

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	100.00 %	+/-50.00	98.00 %	P	98.00 %	P	-2.00

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	1.000 Inches	+/-0.020	1.000 Inches	P	1.000 Inches	P	0.000

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	100.00 %	+/-50.00	99.00 %	P	99.00 %	P	-1.00

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.



# Control Systems 21

"Your Process Control Specialists"

## *CERTIFICATE of CALIBRATION*

Cal Certificate # 80196

Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 June 2023 9:27:24AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 81073

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** CEDAR RUN

**Description** Flow Meter  
**Manufacturer** Sigma  
**Model Number** 950  
**Serial Number** N/A  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 07/12/2023  
**Next Due Date** 08/31/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	0.44 MGD	+/-0.02	0.46 MGD	P	0.46 MGD	P	0.02

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
TAPE MEASURE	N/A	N/A	N/A	

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Dylan Smith 12 July 2023 9:02:17AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 81074

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID ROSSMOYNE

Description Flow Meter  
Manufacturer Hach  
Model Number SC200  
Serial Number 8712A808118  
Location N/A  
Building N/A  
Department N/A

Status Active  
Temp °F 70  
Cal Proc 4.8  
Adjusted To Improve No  
Calibration Frequency Monthly  
Calibrated 07/12/2023  
Next Due Date 08/31/2023

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	1.33 MGD	+/-0.07	1.29 MGD	P	1.29 MGD	P	-0.04

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
TAPE MEASURE	N/A	N/A	N/A	

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Dylan Smith 12 July 2023 9:21:31AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 81075

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID SCIC PRISON METER

Description Flow Meter  
Manufacturer Hach  
Model Number SC200  
Serial Number 1412C0141778  
Location N/A  
Building N/A  
Department N/A

Status Active  
Temp °F 70  
Cal Proc 4.8  
Adjusted To Improve No  
Calibration Frequency Monthly  
Calibrated 07/12/2023  
Next Due Date 08/31/2023

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	362.100 GPM	+/-18.105	360.400 GPM	P	360.400 GPM	P	-1.700

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
TAPE MEASURE	N/A	N/A	N/A	

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Dylan Smith 12 July 2023 9:58:46AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 81076

**Company Name** Lower Allen Township  
 120 Limekiln Road  
 New Cumberland, PA 17070

**Instrument ID** PLANT INFLUENT

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1506C0147261  
**Location** Influent  
**Building**  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 07/12/2023  
**Next Due Date** 08/31/2023

### Calibration Specifications

**Group Name** MGD

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	7.310 MGD	+0.366/-0.36	7.230 MGD	P	7.230 MGD	P	-0.080
		5					

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
ISCO	Isco Flow Book	N/A	N/A	
TAPE MEASURE	N/A	N/A	N/A	

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Dylan Smith 12 July 2023 10:15:03AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 81077

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** EFFLUENT FLOW

<b>Description</b>	Flow Meter	<b>Status</b>	Active
<b>Manufacturer</b>	Siemens	<b>Temp °F</b>	70
<b>Model Number</b>	OCM III	<b>Cal Proc</b>	4.8
<b>Serial Number</b>	PBD/U1090008-022405101XV	<b>Adjusted To Improve</b>	No
<b>Location</b>	N/A	<b>Calibration Frequency</b>	Monthly
<b>Building</b>	N/A	<b>Calibrated</b>	07/12/2023
<b>Department</b>	N/A	<b>Next Due Date</b>	08/31/2023

### Calibration Specifications

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
<b>Group Name</b> Inches (Pass 1)							
1	0.600 Inches	+/-0.012	0.600 Inches	P	0.600 Inches	P	0.000
<b>Group Name</b> Echo Strength (D-18) Pass 1							
1	100.00 %	+/-50.00	99.00 %	P	99.00 %	P	-1.00
<b>Group Name</b> Inches (Pass 2)							
1	1.420 Inches	+0.028/-0.02	1.440 Inches	P	1.440 Inches	P	0.020
<b>Group Name</b> Echo Strength (D-18) Pass 2							
1	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
ISCO	Isco Flow Book	N/A	N/A	
TAPE MEASURE	N/A	N/A	N/A	

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.



# Control Systems 21

"Your Process Control Specialists"

## *CERTIFICATE of CALIBRATION*

Cal Certificate # 81077

Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Dylan Smith 12 July 2023 10:56:13AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 81506

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** CEDAR RUN

**Description** Flow Meter  
**Manufacturer** Sigma  
**Model Number** 950  
**Serial Number** N/A  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 08/01/2023  
**Next Due Date** 09/30/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	0.38 MGD	+/-0.02	0.39 MGD	P	0.39 MGD	P	0.01

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 01 August 2023 8:23:32AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 81507

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** ROSSMOYNE

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 8712A808118  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 08/01/2023  
**Next Due Date** 09/30/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	0.91 MGD	+/-0.05	0.90 MGD	P	0.90 MGD	P	-0.01

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 01 August 2023 8:37:31AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 81508

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** SCIC PRISON METER

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1412C0141778  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 08/01/2023  
**Next Due Date** 09/30/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	250.800 GPM	+/-12.540	260.100 GPM	P	260.100 GPM	P	9.300

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 01 August 2023 8:54:14AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 81509

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** PLANT INFLUENT

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1506C0147261  
**Location** Influent  
**Building**  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 08/01/2023  
**Next Due Date** 09/30/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	5.090 MGD	+0.255/-0.25	5.220 MGD	P	5.220 MGD	P	0.130
		4					

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 01 August 2023 9:21:14AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 81510

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** EFFLUENT FLOW

**Description** Flow Meter  
**Manufacturer** Siemens  
**Model Number** OCM III  
**Serial Number** PBD/U1090008-022405101XV  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 08/01/2023  
**Next Due Date**

### Calibration Specifications

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
<b>Group Name</b> Inches (Pass 1)							
1	0.750 Inches	+/-0.015	0.670 Inches	*F*	0.630 Inches	*F*	-0.120
<b>Group Name</b> Echo Strength (D-18) Pass 1							
1	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00
<b>Group Name</b> Inches (Pass 2)							
1	-0.580 Inches	+/-0.012	-0.580 Inches	P	-0.580 Inches	P	0.000
<b>Group Name</b> Echo Strength (D-18) Pass 2							
1	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Print Date: 08/01/2023

Page 1 of 2

Control Systems 21

713 Range End Rd. • Dillsburg, PA 17019 • Voice: 717 432-5511 • Fax: 717 432-7550  
email@controlsystems21.com



# Control Systems 21

"Your Process Control Specialists"

## *CERTIFICATE of CALIBRATION*

Cal Certificate # 81510

Pass # 1 jumping around and not holding steady readings. Needs new meter and transducer.

Calibration Result: Calibration Failed

Calibrated By: Dylan Smith

Finalized By: Tim Starr 01 August 2023 10:19:36AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 82227

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** CEDAR RUN

**Description** Flow Meter  
**Manufacturer** Sigma  
**Model Number** 950  
**Serial Number** N/A  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 09/07/2023  
**Next Due Date** 10/31/2023

### Calibration Specifications

**Group Name** MGD

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	0.45 MGD	+/-0.02	0.44 MGD	P	0.44 MGD	P	-0.01

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

*Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.*

*Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).*

*Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print*

*All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customer's location.*

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 September 2023 8:20:59AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 82228

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** ROSSMOYNE

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 8712A808118  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 09/07/2023  
**Next Due Date** 10/31/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	0.95 MGD	+/-0.05	0.92 MGD	P	0.92 MGD	P	-0.03

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 September 2023 8:45:48AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 82229

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** SCIC PRISON METER

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1412C0141778  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 09/07/2023  
**Next Due Date** 10/31/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	262.100 GPM	+/-13.105	267.300 GPM	P	267.300 GPM	P	5.200

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 September 2023 8:56:33AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 82230

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** PLANT INFLUENT

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1506C0147261  
**Location** Influent  
**Building**  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 09/07/2023  
**Next Due Date** 10/31/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	3.448 MGD	+/-0.172	3.450 MGD	P	3.450 MGD	P	0.002

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 September 2023 9:24:40AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 82231

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** EFFLUENT FLOW

<b>Description</b> Flow Meter	<b>Status</b> Active
<b>Manufacturer</b> Siemens	<b>Temp °F</b> 70
<b>Model Number</b> OCM III	<b>Cal Proc</b> 4.8
<b>Serial Number</b> PBD/U1090008-022405101XV	<b>Adjusted To Improve</b> No
<b>Location</b> N/A	<b>Calibration Frequency</b> Monthly
<b>Building</b> N/A	<b>Calibrated</b> 09/07/2023
<b>Department</b> N/A	<b>Next Due Date</b> 10/31/2023

### Calibration Specifications

<b>Group Name</b> Inches (Pass 1)							
<b>Test Point</b>	<b>Ref Standard</b>	<b>Tol</b>	<b>UUT As Found</b>	<b>P/F</b>	<b>UUT As Left</b>	<b>P/F</b>	<b>Dev</b>
1	1.300 Inches	+/-0.026	1.300 Inches	P	1.300 Inches	P	0.000
<b>Group Name</b> Echo Strength (D-18) Pass 1							
<b>Test Point</b>	<b>Ref Standard</b>	<b>Tol</b>	<b>UUT As Found</b>	<b>P/F</b>	<b>UUT As Left</b>	<b>P/F</b>	<b>Dev</b>
1	100.00 %	+/-50.00	96.00 %	P	96.00 %	P	-4.00
<b>Group Name</b> Inches (Pass 2)							
<b>Test Point</b>	<b>Ref Standard</b>	<b>Tol</b>	<b>UUT As Found</b>	<b>P/F</b>	<b>UUT As Left</b>	<b>P/F</b>	<b>Dev</b>
1	1.625 Inches	+0.033/-0.03	1.650 Inches	P	1.650 Inches	P	0.025
<b>Group Name</b> Echo Strength (D-18) Pass 2							
<b>Test Point</b>	<b>Ref Standard</b>	<b>Tol</b>	<b>UUT As Found</b>	<b>P/F</b>	<b>UUT As Left</b>	<b>P/F</b>	<b>Dev</b>
1	100.00 %	+/-50.00	99.00 %	P	99.00 %	P	-1.00

### Calibration Standards Used

<b>Test Instrument ID</b>	<b>Manufacturer</b>	<b>Model Number</b>	<b>Serial Number</b>	<b>Next Cal Date</b>
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.



## Control Systems 21

"Your Process Control Specialists"

### *CERTIFICATE of CALIBRATION*

Cal Certificate # 82231

Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 07 September 2023 9:33:09AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 82989

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** CEDAR RUN

**Description** Flow Meter  
**Manufacturer** Sigma  
**Model Number** 950  
**Serial Number** N/A  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 50  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 10/12/2023  
**Next Due Date** 11/30/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	0.43 MGD	+/-0.02	0.43 MGD	P	0.43 MGD	P	0.00

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 12 October 2023 8:40:20AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 82990

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** ROSSMOYNE

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 8712A808118  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 50  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 10/12/2023  
**Next Due Date** 11/30/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	0.77 MGD	+/-0.04	0.79 MGD	P	0.79 MGD	P	0.02

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 12 October 2023 8:54:42AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 82991

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** SCIC PRISON METER

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1412C0141778  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 50  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 10/12/2023  
**Next Due Date** 11/30/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	431.500 GPM	+/-21.575	438.900 GPM	P	438.900 GPM	P	7.400

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 12 October 2023 9:04:38AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 82992

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** PLANT INFLUENT

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1506C0147261  
**Location** Influent  
**Building**  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 10/12/2023  
**Next Due Date** 11/30/2023

### Calibration Specifications

**Group Name** MGD

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	4.775 MGD	+0.239/-0.23	4.750 MGD	P	4.750 MGD	P	-0.025
		9					

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 12 October 2023 9:22:50AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 82993

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** EFFLUENT FLOW

<b>Description</b>	Flow Meter	<b>Status</b>	Active
<b>Manufacturer</b>	Siemens	<b>Temp °F</b>	70
<b>Model Number</b>	OCM III	<b>Cal Proc</b>	4.8
<b>Serial Number</b>	PBD/U1090008-022405101XV	<b>Adjusted To Improve</b>	No
<b>Location</b>	N/A	<b>Calibration Frequency</b>	Monthly
<b>Building</b>	N/A	<b>Calibrated</b>	10/12/2023
<b>Department</b>	N/A	<b>Next Due Date</b>	11/30/2023

### Calibration Specifications

<b>Group Name</b> Inches (Pass 1)							
<b>Test Point</b>	<b>Ref Standard</b>	<b>Tol</b>	<b>UUT As Found</b>	<b>P/F</b>	<b>UUT As Left</b>	<b>P/F</b>	<b>Dev</b>
1	0.750 Inches	+/-0.015	0.740 Inches	P	0.740 Inches	P	-0.010
-----							
<b>Group Name</b> Echo Strength (D-18) Pass 1							
<b>Test Point</b>	<b>Ref Standard</b>	<b>Tol</b>	<b>UUT As Found</b>	<b>P/F</b>	<b>UUT As Left</b>	<b>P/F</b>	<b>Dev</b>
1	100.00 %	+/-50.00	98.00 %	P	98.00 %	P	-2.00
-----							
<b>Group Name</b> Inches (Pass 2)							
<b>Test Point</b>	<b>Ref Standard</b>	<b>Tol</b>	<b>UUT As Found</b>	<b>P/F</b>	<b>UUT As Left</b>	<b>P/F</b>	<b>Dev</b>
1	-1.300 Inches	+/-0.026	-1.310 Inches	P	-1.310 Inches	P	-0.010
-----							
<b>Group Name</b> Echo Strength (D-18) Pass 2							
<b>Test Point</b>	<b>Ref Standard</b>	<b>Tol</b>	<b>UUT As Found</b>	<b>P/F</b>	<b>UUT As Left</b>	<b>P/F</b>	<b>Dev</b>
1	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Print Date: 10/12/2023

Page 1 of 2



## Control Systems 21

"Your Process Control Specialists"

---

### *CERTIFICATE of CALIBRATION*

Cal Certificate # 82993

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 12 October 2023 9:45:41AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 83462

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** CEDAR RUN

**Description** Flow Meter  
**Manufacturer** Sigma  
**Model Number** 950  
**Serial Number** N/A  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 35  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 11/01/2023  
**Next Due Date** 12/31/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	0.36 MGD	+/-0.02	0.35 MGD	P	0.35 MGD	P	-0.01

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 01 November 2023 8:29:27AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 83463

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** ROSSMOYNE

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 8712A808118  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 35  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 11/01/2023  
**Next Due Date** 12/31/2023

### Calibration Specifications

**Group Name** MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	1.00 MGD	+/-0.05	0.99 MGD	P	0.99 MGD	P	-0.01

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 01 November 2023 8:45:17AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 83464

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** SCIC PRISON METER

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1412C0141778  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 35  
**Cal Proc** 4.9  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 11/01/2023  
**Next Due Date** 12/31/2023

### Calibration Specifications

**Group Name** MGD

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	245.200 GPM	+/-12.260	245.400 GPM	P	245.400 GPM	P	0.200

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 01 November 2023 9:25:25AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 83465

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** PLANT INFLUENT

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1506C0147261  
**Location** Influent  
**Building**  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 11/01/2023  
**Next Due Date** 12/31/2023

### Calibration Specifications

**Group Name** MGD

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	4.775 MGD	+0.239/-0.23	4.810 MGD	P	4.810 MGD	P	0.035
		9					

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 01 November 2023 9:49:31AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 83466

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** RAVEN HILL PUMP STATION

**Description** Flow Meter  
**Manufacturer** E & H  
**Model Number** ProMag 53  
**Serial Number** N2039116000  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 60  
**Cal Proc** 4.9  
**Adjusted To Improve** No  
**Calibration Frequency** 6 Months  
**Calibrated** 11/01/2023  
**Next Due Date** 05/31/2024

### Calibration Specifications

<b>Group Name</b> Transmitter Test % Deviation @ 5%							
<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	0.00 %	+/-1.50	0.97 %	P	0.97 %	P	0.97

<b>Group Name</b> Transmitter Test % Deviation @ 10%							
<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	0.00 %	+/-1.00	-0.24 %	P	-0.24 %	P	-0.24

<b>Group Name</b> Transmitter Test % Deviation @ 50%							
<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	0.00 %	+/-0.60	-0.21 %	P	-0.21 %	P	-0.21

<b>Group Name</b> Transmitter Test % Deviation @ 100%							
<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	0.00 %	+/-0.55	-0.15 %	P	-0.15 %	P	-0.15

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
E&H SIMUBOX	Endress & Hauser Flowtec AG	CH-4153	D7186102000	11/30/2023

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.



# Control Systems 21

"Your Process Control Specialists"

## *CERTIFICATE of CALIBRATION*

Cal Certificate # 83466

Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 01 November 2023 9:50:39AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 83467

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** EFFLUENT FLOW

<b>Description</b> Flow Meter	<b>Status</b> Active
<b>Manufacturer</b> Siemens	<b>Temp °F</b> 70
<b>Model Number</b> OCM III	<b>Cal Proc</b> 4.8
<b>Serial Number</b> PBD/U1090008-022405101XV	<b>Adjusted To Improve</b> No
<b>Location</b> N/A	<b>Calibration Frequency</b> Monthly
<b>Building</b> N/A	<b>Calibrated</b> 11/01/2023
<b>Department</b> N/A	<b>Next Due Date</b> 12/31/2023

### Calibration Specifications

<b>Group Name</b> Inches (Pass 1)							
<b>Test Point</b>	<b>Ref Standard</b>	<b>Tol</b>	<b>UUT As Found</b>	<b>P/F</b>	<b>UUT As Left</b>	<b>P/F</b>	<b>Dev</b>
1	1.000 Inches	+/-0.020	1.000 Inches	P	1.000 Inches	P	0.000
-----							
<b>Group Name</b> Echo Strength (D-18) Pass 1							
<b>Test Point</b>	<b>Ref Standard</b>	<b>Tol</b>	<b>UUT As Found</b>	<b>P/F</b>	<b>UUT As Left</b>	<b>P/F</b>	<b>Dev</b>
1	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00
-----							
<b>Group Name</b> Inches (Pass 2)							
<b>Test Point</b>	<b>Ref Standard</b>	<b>Tol</b>	<b>UUT As Found</b>	<b>P/F</b>	<b>UUT As Left</b>	<b>P/F</b>	<b>Dev</b>
1	1.310 Inches	+/-0.026	1.300 Inches	P	1.300 Inches	P	-0.010
-----							
<b>Group Name</b> Echo Strength (D-18) Pass 2							
<b>Test Point</b>	<b>Ref Standard</b>	<b>Tol</b>	<b>UUT As Found</b>	<b>P/F</b>	<b>UUT As Left</b>	<b>P/F</b>	<b>Dev</b>
1	100.00 %	+/-50.00	100.00 %	P	100.00 %	P	0.00

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customer's location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Print Date: 11/01/2023

Page 1 of 2

**Control Systems 21**

713 Range End Rd. • Dillsburg, PA 17019 • Voice: 717 432-5511 • Fax: 717 432-7550  
email@controlsystems21.com



# Control Systems 21

"Your Process Control Specialists"

## *CERTIFICATE of CALIBRATION*

Cal Certificate # 83467

Calibration Result: Calibration Successful

Calibrated By: Dylan Smith

Finalized By: Tim Starr 01 November 2023 11:01:49AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 84044

Company Name Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

Instrument ID CEDAR RUN

Description Flow Meter  
Manufacturer Sigma  
Model Number 950  
Serial Number N/A  
Location N/A  
Building N/A  
Department N/A

Status Active  
Temp °F 40  
Cal Proc 4.8  
Adjusted To Improve No  
Calibration Frequency Monthly  
Calibrated 12/06/2023  
Next Due Date 01/31/2024

### Calibration Specifications

Group Name MGD

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
1	0.40 MGD	+/-0.02	0.42 MGD	P	0.42 MGD	P	0.02

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

Please note: any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Jon Wirth

Finalized By: Tim Starr 06 December 2023 8:48:43AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 84045

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** ROSSMOYNE

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 8712A808118  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 40  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 12/06/2023  
**Next Due Date** 01/31/2024

### Calibration Specifications

**Group Name** MGD

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	0.84 MGD	+/-0.04	0.80 MGD	P	0.80 MGD	P	-0.04

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Jon Wirth

Finalized By: Tim Starr 06 December 2023 8:59:31AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 84046

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** SCIC PRISON METER

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1412C0141778  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 40  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 12/06/2023  
**Next Due Date** 01/31/2024

### Calibration Specifications

**Group Name** MGD

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	346.200 GPM	+/-17.310	331.200 GPM	P	331.200 GPM	P	-15.000

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Jon Wirth

Finalized By: Tim Starr 06 December 2023 9:10:35AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 84047

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** PLANT INFLUENT

**Description** Flow Meter  
**Manufacturer** Hach  
**Model Number** SC200  
**Serial Number** 1506C0147261  
**Location** Influent  
**Building**  
**Department** N/A

**Status** Active  
**Temp °F** 70  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 12/06/2023  
**Next Due Date** 01/31/2024

### Calibration Specifications

**Group Name** MGD

<u>Test Point</u>	<u>Ref Standard</u>	<u>Tol</u>	<u>UUT As Found</u>	<u>P/F</u>	<u>UUT As Left</u>	<u>P/F</u>	<u>Dev</u>
1	5.576 MGD	+0.279/-0.27	5.670 MGD	P	5.670 MGD	P	0.094
9							

### Calibration Standards Used

<u>Test Instrument ID</u>	<u>Manufacturer</u>	<u>Model Number</u>	<u>Serial Number</u>	<u>Next Cal Date</u>
ISCO	Isco Flow Book	N/A	N/A	
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customers location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired

### Remarks or Special Requirements:

Calibration Result: Calibration Successful

Calibrated By: Jon Wirth

Finalized By: Tim Starr 06 December 2023 9:28:26AM



# Control Systems 21

"Your Process Control Specialists"

## CERTIFICATE of CALIBRATION

Cal Certificate # 84048

**Company Name** Lower Allen Township  
120 Limekiln Road  
New Cumberland, PA 17070

**Instrument ID** EFFLUENT FLOW

**Description** Flow Meter  
**Manufacturer** Siemens  
**Model Number** OCM III  
**Serial Number** PBD/U1090008-022405101XV  
**Location** N/A  
**Building** N/A  
**Department** N/A

**Status** Active  
**Temp °F** 60  
**Cal Proc** 4.8  
**Adjusted To Improve** No  
**Calibration Frequency** Monthly  
**Calibrated** 12/06/2023  
**Next Due Date** 01/31/2024

### Calibration Specifications

Test Point	Ref Standard	Tol	UUT As Found	P/F	UUT As Left	P/F	Dev
<b>Group Name</b> Inches (Pass 1)							
1	1.000 Inches	+/-0.020	0.980 Inches	P	0.980 Inches	P	-0.020
<b>Group Name</b> Echo Strength (D-18) Pass 1							
1	100.00 %	+/-50.00	99.00 %	P	99.00 %	P	-1.00
<b>Group Name</b> Inches (Pass 2)							
1	0.750 Inches	+/-0.015	0.750 Inches	P	0.750 Inches	P	0.000
<b>Group Name</b> Echo Strength (D-18) Pass 2							
1	100.00 %	+/-50.00	98.00 %	P	98.00 %	P	-2.00

### Calibration Standards Used

Test Instrument ID	Manufacturer	Model Number	Serial Number	Next Cal Date
M-003	Komelon	SL2825	N/A	5/31/2024

Equipment listed on this cert is certified in reference to our current work instructions as part of our quality system.

Where applicable and noted calibrations were performed using standards whose calibration is traceable through NIST or another National Metrology Institute to the International System of Units (SI units).

Control Systems 21 utilizes the comparison method of calibration. Results are reviewed, when applicable, and any results exceeding the agreed upon specifications are indicated by red and/or bold print

All results with this certification relate only to the item(s) calibrated. This certificate shall not be reproduced except in full and with written consent of Control Systems 21. Unless otherwise noted all calibrations were performed in the field at the customer's location.

**Please note:** any number of factors may cause the calibration item to drift out of tolerance before the calibration interval has expired.

### Remarks or Special Requirements:

Print Date: 12/06/2023

Page 1 of 2

Control Systems 21

713 Range End Rd. • Dillsburg, PA 17019 • Voice: 717 432-5511 • Fax: 717 432-7550  
email@controlsystems21.com



# Control Systems 21

"Your Process Control Specialists"

## *CERTIFICATE of CALIBRATION*

Cal Certificate # 84048

Calibration Result: Calibration Successful

Calibrated By: Jon Wirth

Finalized By: Tim Starr 06 December 2023 9:48:14AM

**Attachment 9 Tributary Sewer Systems  
Lower Allen Township Authority  
NPDES PA0027189**

The Lower Allen Township Authority wastewater treatment plant receives wastewater from Lower Allen Township, Borough of Shiremanstown, portions of Upper Allen Township and Pennsylvania American Water - Fairview Township, and the State Correctional Institution at Camp Hill. The Authority owns and operates the collection system in Lower Allen Township and Shiremanstown Borough, and the Lower Allen treatment plant. The tributary users are responsible for the condition of their sewer systems and were requested to submit information for this report. Documentation received from the tributary users is included in this section.



## CHAPTER 94 MUNICIPAL WASTELOAD MANAGEMENT ANNUAL REPORT

For Calendar Year: **2023**

- Permittee is owner and/or operator of a POTW or other sewage treatment facility  
 Permittee is owner and/or operator of a collection system tributary to a POTW not owned/operated by permittee

<b>GENERAL INFORMATION</b>			
Permittee Name:	Pennsylvania American Water	Permit No.:	PA0081868
Mailing Address:	852 Wesley Drive	Effective Date:	February 1, 2022
City, State, Zip:	Mechanicsburg, PA 17055	Expiration Date:	January 31, 2027
Contact Person:	Stephen DeFriece	Renewal Due Date:	August 4, 2026
Title:	Engineering Project Manager	Municipality:	Fairview Township North
Phone:	(717) 550-1608	County:	York
Email:	Stephen.DeFriece@amwater.com	Consultant Name:	N/A
<b>CHAPTER 94 REPORT COMPONENTS</b>			
<p>1. Attach to this report a line graph depicting the monthly average flows (expressed in MGD) for each month for the past 5 years and projecting the flows for the next 5 years. The graph must also include a line depicting the hydraulic design capacity per the WQM permit. (<u>25 Pa. Code § 94.12(a)(1)</u>)</p> <p><b>Check the appropriate boxes:</b></p> <p><input type="checkbox"/> Line graph for flows attached (<b>Attachment</b> )</p> <p><input type="checkbox"/> DEP Chapter 94 Spreadsheet used (<b>Attachment</b> )</p> <p><input checked="" type="checkbox"/> Section 1 is not applicable (report is for a collection system).</p>			
<p>2. Attach to this report a line graph depicting the monthly average organic loads (express as lbs BOD5/day) for each month for the past 5 years and projecting the organic loads for the next 5 years. The graph must also include a line depicting the organic design capacity of the treatment plant per the WQM permit. (<u>25 Pa. Code § 94.12(a)(2)</u>)</p> <p><b>Check the appropriate boxes:</b></p> <p><input type="checkbox"/> Line graph for organic loads attached (<b>Attachment</b> )</p> <p><input type="checkbox"/> DEP Chapter 94 Spreadsheet used (<b>Attachment</b> )</p> <p><input checked="" type="checkbox"/> Section 2 is not applicable (report is for a collection system).</p>			
<p>3. If the DEP Chapter 94 Spreadsheet was not used to determine projections, discuss the basis for the hydraulic and organic projections. In all cases, include a description of the time needed to expand the plant to meet the load projections, if necessary, and data used to support the projections should be included in an appendix to this report. (<u>25 Pa. Code § 94.12(a)(3)</u>)</p>			

4. Attach a map showing all sewer extensions constructed within the past calendar year, sewer extensions approved or exempted in the past year in accordance with Act 537 and Chapter 71, but not yet constructed, and all known proposed projects which require public sewers but are in the preliminary planning stages. The map must be accompanied by a list summarizing each extension or project and the population to be served by the extension or project. If a sewer extension approval or proposed project includes schedules describing how the project will be completed over time, the listing should include that information and the effect this build-out-rate will have on populations served. (25 Pa. Code § 94.12(a)(4))

**Check the appropriate boxes:**

- Map showing sewer extensions constructed, approved/exempted but not yet constructed, and proposed projects attached (**Attachment 2**)
- List summarizing each extension or project attached (**Attachment** )
- Schedules describing how each project will be completed over time and effects attached (**Attachment** )

**Comments:**

Sienna is a Residential Development that has a build out of 655 EDUs, the anticipated schedule of construction is 40 EDUs starting in 2024.

Green Lane Meadows is a Residential Development that has a build out of 208 EDUs, the anticipated schedule of construction is 40 EDUs starting in 2024.

100 Spanglers Mill Road is a Residential Development that has a build out of 227 EDUs, the anticipated schedule of construction is 40 EDUs starting in 2026.

5. Discuss the permittee's program for sewer system monitoring, maintenance, repair and rehabilitation, including routine and special activities, personnel and equipment used, sampling frequency, quality assurance, data analyses, infiltration/inflow monitoring, and, where applicable, maintenance and control of combined sewer regulators during the past year. Attach a separate sheet if necessary. (25 Pa. Code § 94.12(a)(5))

**Typically, the collection system maintenance program consists of systematic checks on manholes throughout the collection system. Televising inspections are periodically performed to identify potential problem areas.**

6. Discuss the condition of the sewer system including portions of the system where conveyance capacity is being exceeded or will be exceeded in the next 5 years and portions where rehabilitation or cleaning is needed or is underway to maintain the integrity of the system and prevent or eliminate bypassing, CSOs, SSOs, excessive infiltration and other system problems. Attach a separate sheet if necessary. (25 Pa. Code § 94.12(a)(6))

**Check the appropriate boxes:**

- System experienced capacity-related bypassing, SSOs or surcharging during the report year. On a separate sheet, list the date, location, and reason for each bypass, SSO or surcharge event.
- System did not experience capacity-related bypassing, SSOs or surcharging during the report year.

**Comments:**

**During 2023 PAWC personnel monitored and maintained the collection system, no maintenance or capacity concerns were discovered.**

7. Attach a discussion on the condition of sewage pumping (pump) stations. Include a comparison of the maximum pumping rate with present maximum flows and the projected 2-year maximum flows for each station. (25 Pa. Code § 94.12(a)(7))

**Check the appropriate boxes:**

- The collection system does not contain pump stations
- The collection system does contain pump stations (Number – )
- Discussion of condition of each pump station attached (**Attachment 1**)

8. If the sewage collection system receives industrial wastes (i.e., non-sanitary wastes), attach a report with the information listed below. (25 Pa. Code § 94.12(a)(8))

- a. A copy of any ordinance or regulation governing industrial waste discharges to the sewer system or a copy of amendments adopted since the initial submission of the ordinance or regulation under Chapter 94, if it has not previously been submitted.
- b. A discussion of the permittee's or municipality's program for surveillance and monitoring of industrial waste discharges into the sewer system during the past year.
- c. A discussion of specific problems in the sewer system or at the plant, known or suspected to be caused by industrial waste discharges and a summary of the steps being taken to alleviate or eliminate the problems. The discussion shall include a list of industries known to be discharging wastes which create problems in the plant or in the sewer system and action taken to eliminate the problem or prevent its recurrence. The report may describe pollution prevention techniques in the summary of steps taken to alleviate current problems caused by industrial waste dischargers and in actions taken to eliminate or prevent potential or recurring problems caused by industrial waste dischargers.

**Check the appropriate boxes:**

- Industrial waste report as described in 8 a., b. and c. attached (**Attachment** )
- Industrial pretreatment report as required in an NPDES permit attached (**Attachment** )

9. Existing or Projected Overload.

**Check the appropriate boxes:**

- This report demonstrates an existing hydraulic overload condition.
- This report demonstrates a projected hydraulic overload condition.
- This report demonstrates an existing organic overload condition.
- This report demonstrates a projected organic overload condition.

If one or more boxes above have been checked, attach a Corrective Action Plan (CAP) to reduce or eliminate present or projected overloaded conditions under §§ 94.21 and/or 94.22 (relating to existing overload and projected overload). (25 Pa. Code § 94.12(a)(9))

- Corrective Action Plan attached (**Attachment** )

10. Where required by the NPDES permit, attach a Sewage Sludge Management inventory that demonstrates a mass balance of solids coming in and leaving the facility over the previous calendar year.

- Sewage Sludge Management Inventory attached (**Attachment** )

3800-FM-BPNPSM0507 4/2014  
Chapter 94 Report

11. For facilities with CSOs and where required by the NPDES permit, attach an Annual CSO Report (including satellite combined sewer systems).

Annual CSO Report attached (**Attachment** )

12. For POTWs, attach a calibration report documenting that flow measuring, indicating and recording equipment has been calibrated annually. (25 Pa. Code § 94.13(b))


Flow calibration report attached (**Attachment** )

### RESPONSIBLE OFFICIAL CERTIFICATION

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowledge of violations. See 18 Pa. C.S. § 4904 (relating to unsworn falsification).

**Bruce Aiton, VP Engineering**

Name of Responsible Official

  
Signature

**(717) 550-1610**

Telephone No.


**3-14-24**  
Date

### PREPARER CERTIFICATION

I certify under penalty of law that this document and all attachments were prepared by me or otherwise under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. The information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowledge of violations. See 18 Pa. C.S. § 4904 (relating to unsworn falsification).

**Stephen DeFriece**

Name of Preparer

  
Signature

**(717) 550-1608**

Telephone No.

**3/14/2024**

Date

# TUS A-12\_Attachment

*Attachment No.1*

PAWC owns and operates eleven (11) pump stations in the Fairview North Sewer Service Area. Each pump station is equipped with two (2) pumps and a device that records pump operating (run) time. The rated capacities are determined by assuming one pump is in standby mode, in conformance with DEP guidelines. The maximum capacity of each pump station is expected to be less than the combined individual capacity of the two (2) pumps. Data for each of the pump stations is provided in Table 1.

Lower Allen Township receives flows from two (2) of the eleven (11) stations Pin Oak, and Corporate Circle. The daily average and maximum monthly flow from the Pin Oak Pump Station are estimated based on pump run times and rated capacities. And Corporate Circle is equipped with a flow meter and is based on actual monthly gallons pumped.

Projected Max Monthly Flow= (Peaking factor \* Max Monthly Flow, GPD) + 5%

The Peaking factor ("Max : Avg Ratio")= 3mo. Avg GPD / Daily avg Flow GPD

Maximum month flows through 2026 are projected to increase by 5% since only minimal growth is anticipated in the collection system tributary to these pump stations. As the data indicates in Table 1, the pump stations are not currently hydraulically overloaded or anticipated to be overloaded within the next 2 years.

Normal preventative maintenance and repairs of the Pump Stations are performed on a needed basis during the year and are in good condition.

**Table 1. Pump Station Data**

Pump Station	Rated Capacity	3MO,MAX AVG GPD	2023 Average Daily Flow, GPD	Peaking Factor Max : Avg Ratio	2023 Max. Month Flow, GPD	2026 Projected Max. Month Flow, GPD <sup>(1)</sup>
10. Corporate Circle	55 GPM 79,200 GPD	2,568	1,503	1.71	3,228	5,791
11. Pin Oak	210 GPM 302,400 GPD	8,133	7,741	1.05	9,308	10,268


<sup>(1)</sup> Based on 5% increase.





**SITE UTILITY NOTES:**

- EXISTING LOCATIONS OF SEWER, WATER, GAS, DATA, CABLE, PHONE AND POWER ARE APPROXIMATED FROM RECORD DRAWINGS AND LIMITED FIELD LOCATES. THE CONTRACTOR SHALL VERIFY THE DEPTH AND LOCATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING ANY WORK.
- THE CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES PRIOR TO CONSTRUCTION TO COORDINATE WORK FOR NEW SERVICES, CONNECTIONS AND EXTENSIONS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY PERMITS RELATIVE TO THE DEMOLITION AND / OR CONSTRUCTION SHOWN ON THESE PLANS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TRAFFIC CONTROL, TRENCH BARRICADING AND SHEETING AND SHORING.
- ALL SANITARY SEWER CONSTRUCTION METHODS AND MATERIALS SHALL CONFORM TO THE LATEST STANDARDS OF PA AMERICAN SEWER AUTHORITY AND SHALL BE SUBJECT TO APPROVAL BY THE TOWNSHIP ENGINEER.
- THE CONTRACTOR SHALL PERFORM ALL WORK IN ACCORDANCE WITH APPLICABLE TOWNSHIP CODES, UTILITY REGULATIONS AND CONSTRUCTION SPECIFICATIONS, INCLUDING BUT NOT LIMITED TO TRENCHING, MATERIALS AND LINE SEPARATION REQUIREMENTS.
- CONSTRUCTION OF ALL WORK WITHIN THE PUBLIC STREET RIGHT-OF-WAY AND WORK RELATED TO STORM DRAINAGE FACILITIES REQUIRES INSPECTION BY THE TOWNSHIP. PROVIDE A MINIMUM 48 HOURS NOTICE TO THE TOWNSHIP BEFORE STARTING WORK.
- THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PROTECT THE EXISTING UTILITIES AND MAINTAIN UNINTERRUPTED SERVICE. ANY DAMAGE DONE DUE TO CONTRACTOR NEGLIGENCE SHALL BE IMMEDIATELY AND COMPLETELY REPAIRED AT EXPENSE OF THE CONTRACTOR.
- SHOULD ANY UNCHARTED OR INCORRECTLY CHARTED, EXISTING PIPING OR OTHER UTILITIES BE UNCOVERED DURING EXCAVATION, CONSULT THE UTILITY OWNER OR ENGINEER IMMEDIATELY FOR DIRECTION BEFORE PROCEEDING FURTHER WITH WORK IN THIS AREA.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE LOCATION OF ANY AND ALL EXISTING UNDERGROUND UTILITIES IN THE VICINITY OF THE CONTRACTOR'S WORK. THE CONTRACTOR SHALL PROVIDE ADEQUATE MEANS OF SUPPORT AND PROTECTION DURING EXCAVATION OPERATIONS WHEN IT IS INDICATED THAT THESE UTILITIES ARE TO REMAIN IN PLACE.
- ALL SITE WATER PIPING SHALL BE CEMENT LINED CLASS 52 DUCTILE IRON PIPE.
- CONTRACTOR SHALL INSTALL BRIGHTLY COLORED WARNING TAPE WITH TRACE WIRE IN ALL UTILITY TRENCHES AT 12 INCHES BELOW FINISHED GRADE.
- ALL WORK WITHIN THE EXISTING OR PROPOSED RIGHT OF WAY SHALL BE RESTORED TO TOWNSHIP STANDARDS.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO CONTACT/SCHEDULE ALL SITE INSPECTIONS WITH THE TOWNSHIP AND APPROPRIATE UTILITY SERVICE PROVIDERS. ALL UTILITY CONSTRUCTION IS SUBJECT TO INSPECTION FOR APPROVAL PRIOR TO BACKFILLING IN ACCORDANCE WITH THE APPROPRIATE TOWNSHIP/UTILITY COMPANY REGULATIONS.
- ALL PIPES SHALL BE LAID ON STRAIGHT ALIGNMENTS AND EVEN GRADES USING A PIPE LASER OR OTHER ACCURATE METHOD FOR INSTALLATION.
- ALL UTILITIES SHALL BE INSTALLED UNDERGROUND BEFORE CONSTRUCTING PAVEMENT OR SIDEWALKS.
- ALL STORM SEWER STRUCTURES GREATER THAN FIVE (5) FEET OF DEPTH SHALL BE FITTED WITH MANHOLE TYPE STEPS.
- ALL PROPOSED STORM SEWER PIPING SHALL BE SMOOTH INTERIOR WITH GASKETED JOINTS FOR WATER-TIGHT CONNECTIONS.
- THE SITE CONTRACTOR SHALL BE RESPONSIBLE FOR FLUSHING ALL DRAINAGE PIPES TO INSURE THEY ARE CLEAR OF ALL SEDIMENT AND DEBRIS AFTER PAVEMENT HAS BEEN INSTALLED AND THE SITE IS COMPLETELY STABILIZED.
- ALL INLETS SHALL BE TYPE "C" UNLESS OTHERWISE NOTED ON THE PROFILES.
- ALL INLETS AT LOW POINTS ALONG THE ROADWAY SHALL HAVE A TEN-INCH CURB REVEAL AND SHALL BE EQUIPPED WITH PAVEMENT BASE DRAIN EXTENDING 50 FEET IN EITHER DIRECTION, PARALLEL TO THE CENTER LINE OF THE ROADWAY.



4250 Crums Mill Road  
Suite 301 PA 17112  
P: 884.432.6655  
F: 717.732.8596



**EXISTING LEGEND**

- Boundary Line
- Legal Right-Of-Way Line
- Easement Line
- Building
- Edge Of Road
- Curbing
- Fence Line
- Existing Edge of Creek
- Wetlands
- Road Sign
- Bollard
- Tree Line
- Vegetation
- Light Post/Pole
- Existing 2' Contour
- Existing 10' Contour
- Storm Sewer Line
- Storm Sewer Inlet
- Storm Sewer Manhole
- Sanitary Sewer Line
- Sewer Manhole
- Water Line
- Fire Hydrant
- Water Meter
- Water Valve
- Gas Line
- Gas Valve
- Overhead Electric Line
- Electric & Telephone Line
- Electric, Telephone & Cable TV Line
- Underground Cable TV Line
- Utility Pole
- Guy Wire

**PROPOSED LEGEND**

- PROPOSED PROPERTY LINE
- PROPOSED RIGHT-OF-WAY LINE
- PROPOSED EASEMENT
- PROPOSED CENTERLINE
- PROPOSED BUILDING
- PROPOSED CURB
- PROPOSED EDGE OF PAVEMENT
- PROPOSED STREET SIGN / TYPE LIGHT POLE
- PROPOSED SIDEWALK
- PROPOSED 1' CONTOUR
- PROPOSED 5' CONTOUR
- PROPOSED STORM SEWER LINE
- PROPOSED STORM SEWER INLET
- PROPOSED RIP-RAP
- PROPOSED MANHOLE
- PROPOSED SANITARY SEWER LINE
- PROPOSED SANITARY LATERAL
- PROPOSED WATER LINE
- PROPOSED FIRE HYDRANT
- PROPOSED WATER VALVE

REVISIONS		CHECKED	DRAWN
NO.	DATE	DESCRIPTION	

FINAL SUBDIVISION /  
LAND DEVELOPMENT PLAN  
FOR  
**GREEN LANE MEADOWS**  
FAIRVIEW TOWNSHIP  
YORK COUNTY  
PENNSYLVANIA


DRAWING TITLE  
**UTILITY PLAN**

DATE NOVEMBER 5, 2021  
JOB NO. 2000297.00  
FILE NAME LDE-FL-UT01  
DRAWN BY CZ/HAB  
CHECKED BY TLG  
SHEET NO.





# TUS A-12 Attachment



DN:2020, JDS, 2008297-001, JN, FINAL, FINAL PHASE, 1:2008297-001-FL-0101, November 7/15/2021, 2:34 PM

TIE INTO EXISTING 8" WATER LINE AT DERBY AVE

MATCHLINE - SEE SHEET-15



# **Wasteload Management Report Chapter 94 - 2023**

**Wastewater Collection and Conveyance System  
Tributary to Lower Allen Township Authority  
Wastewater Conveyance and Treatment System**

Upper Allen Township

14 March 2024

## GHD 380

225 Grandview Avenue, Suite 403  
Camp Hill, PA 17011, United States  
T 717.541.0622 | [ghd.com](http://ghd.com)

<b>Author</b>	Emily Ellithorpe
<b>Project manager</b>	Nancy Adams
<b>Client name</b>	Upper Allen Township
<b>Project name</b>	Chapter 94 Report
<b>Document title</b>	Wasteload Management Report Chapter 94 - 2023   Wastewater Collection and Conveyance System Tributary to Lower Allen Township Authority Wastewater Conveyance and Treatment System
<b>Project number</b>	12631652

© GHD 2024

This document is and shall remain the property of GHD. The document may only be used for the purpose for which it was commissioned and in accordance with the Terms of Engagement for the commission. Unauthorised use of this document in any form whatsoever is prohibited.

*This report: has been prepared by GHD for Upper Allen Township and may only be used and relied on by Upper Allen Township for the purpose agreed between GHD and Upper Allen Township.*

*GHD otherwise disclaims responsibility to any person other than Upper Allen Township arising in connection with this report. GHD also excludes implied warranties and conditions, to the extent legally permissible.*

*The services undertaken by GHD in connection with preparing this report were limited to those specifically detailed in the report and are subject to the scope limitations set out in the report.*

*The opinions, conclusions and any recommendations in this report are based on conditions encountered and information reviewed at the date of preparation of the report. GHD has no responsibility or obligation to update this report to account for events or changes occurring subsequent to the date that the report was prepared.*

*The opinions, conclusions and any recommendations in this report are based on assumptions made by GHD described in this report. GHD disclaims liability arising from any of the assumptions being incorrect.*

## Contents

1.	<b>Scope</b>	1
2.	<b>Hydraulic Loading</b>	1
3.	<b>Projected Hydraulic Loading</b>	1
4.	<b>Industrial Users</b>	2
5.	<b>Sewer Extensions</b>	2
6.	<b>Sewer System Maintenance</b>	2
7.	<b>Summary of I/I Related Work for 2023</b>	3
7.1	Flow Monitoring	3
7.2	Televising of Sanitary Sewer Mainlines	3
7.3	Televising of Sanitary Sewer Laterals	3
7.4	External Repairs to Sanitary Sewers and Manholes	4
7.5	Full Mainline Replacement	4
7.6	Messiah Village Collection System – Tributary to Lower Allen Basin	4

## Table index

Table 1	Projected Flow to the LATA Wastewater Conveyance and Treatment System	1
Table 2	UAT Pumping Station Existing and Projected Flows (All Flows are in MGD)	2
Table 3	Lineal Feet Televised Per Mini-Basin	3
Table 4	Laterals Televised Per Mini-Basin	3

## Exhibits

- Exhibit A 2023 DEP Chapter 94 Form
- Exhibit B Current and Projected Connections and Sewer Extensions 2023
- Exhibit C Pumping Station No. 3 Flow Data
- Exhibit D Hydraulic Loading Data

# 1. Scope

The following Wasteload Management Report provides an analysis of the hydraulic loading to the Township's wastewater collection and conveyance system that is tributary to the Lower Allen Township Authority wastewater conveyance and treatment facilities. The information provided herein contains hydraulic and organic loading data for the past five years and projected loadings for the next five years. This report is prepared to meet the requirements of Chapter 94, Title 25, of the regulation of the Pennsylvania Department of Environmental Protection.

# 2. Hydraulic Loading

The Lower Allen Township Authority (LATA) received its final Water Quality Management (WQM) and National Pollutant Discharge Elimination System (NPDES) Permits from the Pennsylvania Department of Environmental Protection (DEP), with an effective date of June 1, 2017, increasing Upper Allen Township's (UAT) total allocated capacity to 2.383 MGD annual average daily flow, 3.336 MGD maximum monthly daily flow, and 6.339 MGD peak instantaneous flow at the Lower Allen Township Authority Wastewater Treatment Plant (WWTP). UAT has 3.205 MGD allocated capacity in the Lower Allen Township portion of the Cedar Run interceptor sewer, and 50,000 GPD allocated capacity in portions of the Rossmoyne Industrial Park sewer system discharging to Lower Allen Township.

The total number of new EDU connections to the UAT sewer system tributary to Lower Allen Township during 2023 was 84. One (1) onlot system was retired and two (2) onlot systems were added within the drainage basin that is tributary to Lower Allen in 2023. The 2023 average daily flow for UAT into the Lower Allen Township wastewater system was 1.226 MGD.

Flows to Lower Allen Township are monitored at three locations; Rossmoyne Industrial Park (RIP), and the Cedar Run and Rossmoyne Road metering chambers. The average daily wastewater flow from the UAT portion of the RIP was 21,352GPD based on water consumption information provided by the Pennsylvania American Water Company. The average daily flow measured at the Cedar Run and Rossmoyne Road metering chambers were 448,301GPD and 731,436GPD (after subtracting out 59,895 GPD from the LATA Raven Hill pumping station), respectively. In addition, average infiltration/inflow (I/I), measured twice annually, in RIP totaled 11,775 GPD, and estimated flow in the amount of 300 GPD for each residential EDU in the Fair Oaks Manor at Fair Oaks and Lisburn developments (not flowing through a meter) totaled 11,100 GPD for 37 existing homes. The total average daily flow as determined above was 1.226 MGD.

# 3. Projected Hydraulic Loading

The projected hydraulic loading to the LATA wastewater conveyance and treatment system for the next five years is based on anticipated growth from approved and planned developments and is shown in Table 1 below. Anticipated flow is based on 250 GPD per EDU.

*Table 1 Projected Flow to the LATA Wastewater Conveyance and Treatment System*

Year	Projected EDU Connections	Projected Flow Increase (250 gpd/EDU)	Projected Avg. Daily Flow (MGD)	Projected Max. Month Avg. Daily Flow (MGD)
2024	91	22,750	1.233	1.74
2025	80	20,000	1.253	1.77
2026	52	13,000	1.266	1.78
2027	47	11,750	1.278	1.80
2028	41	10,250	1.288	1.81

The average daily flow for the preceding five years (1.210 MGD) is used as the base starting flow for the projections. The projected average daily flow for 2024 through 2028 is the projected average annual daily flow for the preceding year plus the projected flow increase for the year. The projected maximum month average daily flow is the projected average daily flow times the 5-year historic average ratio of the maximum month average daily flow to the annual average daily flow (1.41). The 5-year historic flow and associated ratio of average to maximum flows are summarized in Exhibit D.

## 4. Industrial Users

There are no major industrial users connected to the Upper Allen Township Sewer System draining to Lower Allen Township. There are no proposed connections that will significantly change the existing wastewater characteristics.

## 5. Sewer Extensions

A table with planned and approved developments and a map showing sewer extensions constructed in 2023 are provided in Exhibit B.

## 6. Sewer System Maintenance

Monitoring, maintenance, and repair of the sanitary sewer system tributary to Lower Allen Township Authority's sewer system and treatment plant is carried out by five full-time Upper Allen Township wastewater treatment plant staff. The Lower Allen drainage basin has one pumping station that is checked and maintained three times per week as part of a preventive maintenance program.

The sewer collection system is reasonably well maintained and in generally good condition. A Vector truck is used for routine sewer main cleaning as well as for cutting roots, removing grease and clearing blockages as they are identified. These materials are safely disposed of at a concrete grit/grease pad at the Grantham WWTP. In conjunction with an aggressive I/I program, the Township also utilizes its televising truck on a routine basis to continually help identify problems within its sanitary sewer mains and laterals. Once identified these problems are corrected. Repairs and maintenance of the collection system is budgeted for annually in the Lower Allen drainage basin.

Present and projected daily flows to the pumping station in the UAT sewer system tributary to Lower Allen Township are shown in Table 2. The actual average monthly daily flow (gallons) for the pumping station is shown in Exhibit C.

**Table 2** UAT Pumping Station Existing and Projected Flows (All Flows are in MGD)

Pump Station	No. of Pumps	Pump Station Capacity <sup>1</sup>	Existing Avg. Daily Flow	2023 Max. Daily Flow	2-Year Projected Flow Increase <sup>2</sup>	2-Year Projected Max. Daily Flow
3	4	7.11	0.647	1.637	0.056	1.3

Pumping Station No. 3 (Arcona Road) was originally constructed in 1974 and serves the southern portion of the Lower Allen Basin. The 2023 average daily flow was 647,023 GPD. There are 141 projected connections to this pumping station in the next two years.

Pumping Station No. 3 is equipped with a Diesel-powered generator for emergency power.

<sup>1</sup> Based on 2023 drawdown tests with two pumps running.

<sup>2</sup> Based on 2-year projected new connections tributary to the pumping station as shown in Exhibit B times 400 gpd.

## 7. Summary of I/I Related Work for 2023

Upper Allen Township continues to aggressively pursue the goal of identifying and correcting sources of I/I throughout the collection system's various mini-basins. This work is generally focused on previously identified priority mini-basins or wherever excessive I/I is suspected. Township staff routinely conduct sanitary sewer mainline and lateral televising and perform manhole field inspections to identify problems within the system. These efforts are followed by repairs and rehabilitation of the sanitary sewer system. When necessary, home inspections are also performed to identify and remove private sources of I/I.

### 7.1 Flow Monitoring

Flow monitoring for the majority of the Lower Allen basin sewer collection system is provided by continuous flow recording meters located at two separate locations where flow enters the Lower Allen Township Authority collection system. In addition, a previously completed flow metering program, utilizing portable flow meters installed at key manholes located throughout the basin, accomplished its main goal of prioritizing mini-basins based on the magnitude of infiltration and inflow in each mini-basin. This information allows Sewer Department staff to choose where to focus investigative efforts and ultimately repairs. Future metering will be completed in efforts to show the affect completed repairs may have had on the amount of infiltration and inflow entering the collection system.

### 7.2 Televising of Sanitary Sewer Mainlines

A total of 19,794 lineal feet (LF) of sanitary sewer mainline piping was televised within the Lower Allen Basin in 2023 to identify existing conditions and any pipeline leaks or defects. While the overall goal is to televise every sewer main in the Township within an eight to nine-year cycle, emphasis is placed first on televising lines in streets scheduled for paving, followed by televising of lines in high and medium priority mini-basins. Sewers located in low priority or unmetred basins are televised as the need arises or as time permits. A breakdown of footages televised in each mini-basin is shown in Table 3.

Table 3 Lineal Feet Televised Per Mini-Basin

Drainage Basin	L.F.	Drainage Basin	L.F.
LN-03	1,714	LS-05	135
LN-04	3,806	LS-08	4,411
LN-05	1,144	LS-09	4,646
LN-06	320	LS-10	1,172
LS-03	464	LS-11	1,982

### 7.3 Televising of Sanitary Sewer Laterals

Televising of sanitary sewer laterals is completed as time and staffing permits. A total of 107 laterals were televised within the Lower Allen Basin in 2023 to identify existing conditions and any pipeline leaks or defects. A breakdown for each mini-basin is shown in Table 4.

Table 4 Laterals Televised Per Mini-Basin

Drainage Basin	Laterals
LN-04	22
LS-08	3
LS-09	2
LS-10	2
LS-11	78

## 7.4 External Repairs to Sanitary Sewers and Manholes

A total of one (1) I/I related external repair was completed within the Lower Allen drainage basin:

1. LS-08: Install 6-inch cleanout due to blockage/infiltration at 6" x 4" transition in lateral piping.

In addition to the above pipeline repair, the Township replaced nine (9) manhole frames/covers experiencing moderate inflow with new self-sealing, watertight frames/covers within the Lower Allen Basin. Manhole frames/covers were replaced in the following mini-basins:

- a. LN-01: 3 frames/covers
- b. LS-03: 1 frame/cover
- c. LS-04: 1 frame/cover
- d. LS-05: 4 frames/covers

## 7.5 Full Mainline Replacement

There were no full mainline replacements in 2023.

## 7.6 Messiah Village Collection System – Tributary to Lower Allen Basin

Also tributary to the Lower Allen basin is the private sanitary sewer collection system serving the Messiah Village campus in mini-basin LS-07, which is owned and maintained by Messiah Lifeways. An infiltration and inflow program began in 2015 with the staff of Messiah Village along with their consulting engineer taking the lead on the program with Township assistance. Messiah Lifeways subsequently completed televisual and manhole inspections and repairs along with mapping of the entire collection system.

All of which is Respectfully Submitted,

GHD



Emily Ellithorpe

# Exhibits

# **Exhibit A**

**2023 DEP Chapter 94 Form**



## CHAPTER 94 MUNICIPAL WASTELOAD MANAGEMENT ANNUAL REPORT

For Calendar Year: **2023**

- Permittee is owner and/or operator of a POTW or other sewage treatment facility  
 Permittee is owner and/or operator of a collection system tributary to a POTW not owned/operated by permittee

GENERAL INFORMATION	
Permittee Name: <b>Upper Allen Township</b>	Permit No.: <b>PA</b>
Mailing Address: <b>100 Gettysburg Pike</b>	Effective Date:
City, State, Zip: <b>Mechanicsburg, PA 17055-5698</b>	Expiration Date:
Contact Person: <b>Barry Cupp</b>	Renewal Due Date:
Title: <b>Sewer Department Manager</b>	Municipality:
Phone: <b>717-766-0756</b>	County: <b>Cumberland</b>
Email: <b>bcupp@uatwp.org</b>	Consultant Name: <b>GHD</b>
CHAPTER 94 REPORT COMPONENTS	
<p>1. Attach to this report a line graph depicting the monthly average flows (expressed in MGD) for each month for the past 5 years and projecting the flows for the next 5 years. The graph must also include a line depicting the hydraulic design capacity per the WQM permit. <u>(25 Pa. Code § 94.12(a)(1))</u></p> <p><b>Check the appropriate boxes:</b></p> <p><input type="checkbox"/> Line graph for flows attached (<b>Attachment</b> )</p> <p><input type="checkbox"/> DEP Chapter 94 Spreadsheet used (<b>Attachment</b> )</p> <p><input checked="" type="checkbox"/> Section 1 is not applicable (report is for a collection system).</p>	
<p>2. Attach to this report a line graph depicting the monthly average organic loads (express as lbs BOD5/day) for each month for the past 5 years and projecting the organic loads for the next 5 years. The graph must also include a line depicting the organic design capacity of the treatment plant per the WQM permit. <u>(25 Pa. Code § 94.12(a)(2))</u></p> <p><b>Check the appropriate boxes:</b></p> <p><input type="checkbox"/> Line graph for organic loads attached (<b>Attachment</b> )</p> <p><input type="checkbox"/> DEP Chapter 94 Spreadsheet used (<b>Attachment</b> )</p> <p><input checked="" type="checkbox"/> Section 2 is not applicable (report is for a collection system).</p>	
<p>3. If the DEP Chapter 94 Spreadsheet was not used to determine projections, discuss the basis for the hydraulic and organic projections. In all cases, include a description of the time needed to expand the plant to meet the load projections, if necessary, and data used to support the projections should be included in an appendix to this report. <u>(25 Pa. Code § 94.12(a)(3))</u></p> <p>N/A</p>	

4. Attach a map showing all sewer extensions constructed within the past calendar year, sewer extensions approved or exempted in the past year in accordance with Act 537 and Chapter 71, but not yet constructed, and all known proposed projects which require public sewers but are in the preliminary planning stages. The map must be accompanied by a list summarizing each extension or project and the population to be served by the extension or project. If a sewer extension approval or proposed project includes schedules describing how the project will be completed over time, the listing should include that information and the effect this build-out-rate will have on populations served. (25 Pa. Code § 94.12(a)(4))

**Check the appropriate boxes:**

- Map showing sewer extensions constructed, approved/exempted but not yet constructed, and proposed projects attached (**Exhibit B**)
- List summarizing each extension or project attached (**Exhibit B**)
- Schedules describing how each project will be completed over time and effects attached (**Exhibit B**)

**Comments:**

5. Discuss the permittee's program for sewer system monitoring, maintenance, repair and rehabilitation, including routine and special activities, personnel and equipment used, sampling frequency, quality assurance, data analyses, infiltration/inflow monitoring, and, where applicable, maintenance and control of combined sewer regulators during the past year. Attach a separate sheet if necessary. (25 Pa. Code § 94.12(a)(5))

See sections 6 and 7 of the report.

6. Discuss the condition of the sewer system including portions of the system where conveyance capacity is being exceeded or will be exceeded in the next 5 years and portions where rehabilitation or cleaning is needed or is underway to maintain the integrity of the system and prevent or eliminate bypassing, CSOs, SSOs, excessive infiltration and other system problems. Attach a separate sheet if necessary. (25 Pa. Code § 94.12(a)(6))

**Check the appropriate boxes:**

- System experienced capacity-related bypassing, SSOs or surcharging during the report year. On a separate sheet, list the date, location, and reason for each bypass, SSO or surcharge event.
- System did not experience capacity-related bypassing, SSOs or surcharging during the report year.

**Comments:**

# TUS A-12\_Attachment

3800-FM-BPNPSM0507 4/2014  
Chapter 94 Report

7. Attach a discussion on the condition of sewage pumping (pump) stations. Include a comparison of the maximum pumping rate with present maximum flows and the projected 2-year maximum flows for each station. (25 Pa. Code § 94.12(a)(7))

**Check the appropriate boxes:**

- The collection system does not contain pump stations
- The collection system does contain pump stations (Number – 1)
- Discussion of condition of each pump station attached (Section 6 of report)

8. If the sewage collection system receives industrial wastes (i.e., non-sanitary wastes), attach a report with the information listed below. (25 Pa. Code § 94.12(a)(8))

- a. A copy of any ordinance or regulation governing industrial waste discharges to the sewer system or a copy of amendments adopted since the initial submission of the ordinance or regulation under Chapter 94, if it has not previously been submitted.
- b. A discussion of the permittee's or municipality's program for surveillance and monitoring of industrial waste discharges into the sewer system during the past year.
- c. A discussion of specific problems in the sewer system or at the plant, known or suspected to be caused by industrial waste discharges and a summary of the steps being taken to alleviate or eliminate the problems. The discussion shall include a list of industries known to be discharging wastes which create problems in the plant or in the sewer system and action taken to eliminate the problem or prevent its recurrence. The report may describe pollution prevention techniques in the summary of steps taken to alleviate current problems caused by industrial waste dischargers and in actions taken to eliminate or prevent potential or recurring problems caused by industrial waste dischargers.

**Check the appropriate boxes:**

- Industrial waste report as described in 8 a., b. and c. attached (**Attachment** )
- Industrial pretreatment report as required in an NPDES permit attached (**Attachment** )

\* **There are no major industrial users connected to the Upper Allen Township sewer system draining to Lower Allen Township.**

9. Existing or Projected Overload.

**Check the appropriate boxes:**

- This report demonstrates an existing hydraulic overload condition.
- This report demonstrates a projected hydraulic overload condition.
- This report demonstrates an existing organic overload condition.
- This report demonstrates a projected organic overload condition.

If one or more boxes above have been checked, attach a Corrective Action Plan (CAP) to reduce or eliminate present or projected overloaded conditions under §§ 94.21 and/or 94.22 (relating to existing overload and projected overload). (25 Pa. Code § 94.12(a)(9))

- Corrective Action Plan attached (**Attachment** )

\*No projected overloads

10. Where required by the NPDES permit, attach a Sewage Sludge Management inventory that demonstrates a mass balance of solids coming in and leaving the facility over the previous calendar year.

- Sewage Sludge Management Inventory attached (**Attachment** )

\* **N/A**

11. For facilities with CSOs and where required by the NPDES permit, attach an Annual CSO Report (including satellite combined sewer systems).

Annual CSO Report attached (**Attachment** )


---

12. For POTWs, attach a calibration report documenting that flow measuring, indicating and recording equipment has been calibrated annually. (25 Pa. Code § 94.13(b))

Flow calibration report attached (**Appendix D**)


**RESPONSIBLE OFFICIAL CERTIFICATION**

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowledge of violations. See 18 Pa. C.S. § 4904 (relating to unsworn falsification).

<b>Barry A. Cupp, Sewer Dept. Manager</b>	
Name of Responsible Official	Signature
717-766-0756	3/15/2024
Telephone No.	Date

**PREPARER CERTIFICATION**

I certify under penalty of law that this document and all attachments were prepared by me or otherwise under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. The information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowledge of violations. See 18 Pa. C.S. § 4904 (relating to unsworn falsification).

<b>Emily Ellithorpe, EIT (GHD)</b>	
Name of Preparer	Signature
315-082-0298	3/8/24
Telephone No.	Date

# **Exhibit B**

**Current and Projected Connections and  
Sewer Extensions 2023**

UPPER ALLEN TOWNSHIP  
SEWER CONNECTION PROJECTIONS  
YEARS 2024 THROUGH 2028

APPROVED AND PLANNED DEVELOPMENT CONNECTIONS - EDUS LOWER ALLEN BASIN												
SUBDIVISION / LAND DEVELOPMENT	TOTAL EDUS	REMAINING EDUS JANUARY 1, 2023	EDUS CONNECTED DURING 2023	REMAINING EDUS JANUARY 1, 2024	PROJECTED NEW CONNECTIONS				PROJECTED NEW CONNECTIONS TRIBUTARY TO			
					2024	2025	2026	2027	2028	TATTERSALL P.S. <sup>(2)</sup>	ARCONA ROAD P.S. NO. 3 <sup>(1)</sup>	
<b>APPROVED DEVELOPMENT</b>												
ALLEN GLEN	22	7	0	7	0	1	0	1	0	0	0	1
AUTUMN CHASE PRD, PHASE I (2021)	39	8	4	4	4	0	0	0	0	0	0	4
AUTUMN CHASE PRD, PHASE II (2023)	56	56	12	44	7	8	7	5	8			15
AUTUMN CHASE PRD, PHASE III (2022)	39	39	13	26	5	6	5	5	5			11
AUTUMN CHASE PRD, PHASE IV (2023)	28	28	0	28	5	6	5	2	3			11
AUTUMN CHASE PRD, PHASE VI (2025)	36	36	0	36	0	0	3	3	4			
CUMBERLAND BUSINESS PARK	705											
CUMB. BUSI. PARK, PREVIOUSLY DEVELOPED LOTS	590	0	0	0	0	0	0	0	0	0	0	0
CUMBERLAND BUSI. PARK, LOT 1, CLASSIC COMMUN.	48	5	0	5	0	5	0	0	0	0	0	0
CUMBERLAND BUSINESS LOT 2, WILSON	1	0	0	0	0	0	0	0	0	0	0	0
CUMBERLAND BUSINESS PARK, LOT 6B (ARBY'S), 6C (STARBUCKS) & 6D (DOLLAR TREE & SUBWAY)	11	0	0	0	0	0	0	0	0	0	0	0
CUMB. BUSI. PARK, FUTURE DEVELOPMENT	55	55	0	55	0	0	0	0	0	0	0	0
FORD FARM DEVELOPMENT	13	1	0	1	0	0	0	1	0	0	0	0
GENERATIONS PARK	10	10	0	10	0	10	0	0	0	0	0	10
GEORGETOWN	62	2	1	1	0	1	0	0	0	0	0	0
151 GETTSBURG PK. - 7 ELEVEN	5	5	0	5	5	0	0	0	0	0	0	5
HART ENTERPRISES SUBDIVISION	4	1	0	1	0	0	0	0	0	0	0	0
KLINEDINST FARM	4	1	0	1	0	0	1	0	0	0	0	0
LINDENWOOD	63	2	0	2	0	0	1	0	0	0	0	0
LOT #4-GETTSBURG PK. & S. MRKT. ST. - 2 OFFICE BLDGS. (34,888 s.f. @ 55.6 gal./1,000 s.f.)	9	4	0	4	0	0	4	0	0	0	0	0
LOUDOUN CENTRE	21											
LOUDOUN CENTRE, CVS	1	0	0	0	0	0	0	0	0	0	0	0
PAUL B HARDWARE	1	0	0	0	0	0	0	0	0	0	0	0
LOUDOUN CENTRE (ADDITIONS)- BANK (66.67 GPD)- HOTEL (4-361 GPD)- OFFICE BLDG.-(2,600 GPD)	1	18	0	18	0	0	1	0	0	0	0	0
MISCELLANEOUS	10	8	1	7	1	0	1	0	1	0	1	0
MODWASH CARWASH	8	8	0	8	8	0	0	0	0	0	0	8
ORCHARD GLEN (FAILOR FARM)	363											
ORCHARD GLEN, PHASE 1	41	0	0	0	0	0	0	0	0	0	0	0
ORCHARD GLEN, PHASE 2	74	0	0	0	0	0	0	0	0	0	0	0
ORCHARD GLEN, PHASE 3	16	0	0	0	0	0	0	0	0	0	0	0
ORCHARD GLEN, PHASE 4	22	0	0	0	0	0	0	0	0	0	0	0
ORCHARD GLEN, PHASE 5	25	0	0	0	0	0	0	0	0	0	0	0

UPPER ALLEN TOWNSHIP  
SEWER CONNECTION PROJECTIONS  
YEARS 2024 THROUGH 2028

APPROVED AND PLANNED DEVELOPMENT CONNECTIONS - EDUS												
LOWER ALLEN BASIN												
SUBDIVISION / LAND DEVELOPMENT	TOTAL EDUS	REMAINING EDUS JANUARY 1, 2023	EDUS CONNECTED DURING 2023	REMAINING EDUS JANUARY 1, 2024	PROJECTED NEW CONNECTIONS				PROJECTED NEW CONNECTIONS TRIBUTARY TO			
					2024	2025	2026	2027	2028	TATTERSALL P.S. (2)	ARCONA ROAD P.S. NO. 3 (1)	
ORCHARD GLEN, PHASE 6	17	1	0	1	1	0	0	0	0	0		1
ORCHARD GLEN, PHASE 7A	15	0	0	0	0	0	0	0	0	0		
ORCHARD GLEN, PHASE 7B	39	0	0	0	0	0	0	0	0	0		
ORCHARD GLEN, PHASE 8 (2016)	35	0	0	0	0	0	0	0	0	0		
ORCHARD GLEN, PHASE 9 (2017)	26	0	0	0	0	0	0	0	0	0		
ORCHARD GLEN, PHASE 10A (2018)	29	0	0	0	0	0	0	0	0	0		
ORCHARD GLEN, PHASE 10B (2018)	24	0	0	0	0	0	0	0	0	0		
DAVID & HOLLY RITCHEY	2	2	0	0	0	0	0	1	0	0		
ROSSMOYNE BUSINESS PARK	168											
ROSSMOYNE BUSI. PARK, PREVIOUSLY DEVEL. LOTS	19	0	0	0	0	0	0	0	0	0		
ROSSMOYNE BUSI. PK., LOT E1-3-A, CLARK ST	1	0	0	0	0	0	0	0	0	0		
ROSSMOYNE BUSINESS PARK, LOT 10B	23	0	0	0	0	0	0	0	0	0		
ROSSMOYNE BUSINESS PARK, LOT D4-B, HOTEL	41	0	0	0	0	0	0	0	0	0		
ROSSMOYNE BUSINESS PARK, TRACT 11, LOT D-12A, AMERICAN MINT	5	0	0	0	0	0	0	0	0	0		
ROSSMOYNE BUSINESS PARK, FUTURE DEVELOPMENT	9	9	0	0	0	0	0	0	0	0		
MICHAEL A. SURLUCO	3	3	0	0	0	0	3	0	0	0		
TATTERSALL (WEST WINDING) - 159 RESIDENTIAL LOTS	169											
TATTERSALL, PHASE 1 (2020-2022)	71	29	20	9	9	0	0	0	0	0	9	
TATTERSALL, FUTURE PHASES	98	98	0	0	0	0	0	20	20	20		
THE MILLS AT SHEPHERDSTOWN CROSSING	70											
LOT 1 - 27 APTS./9,650 S.F. RETAIL	29	29	0	29	29	0	0	0	0	0		29
LOT 2 - 27 APTS./9,960 S.F. RETAIL	29	29	0	29	29	0	0	29	0	0		29
LOTS 3 & 4 - CHICK-FIL-A	5	5	5	0	0	0	0	0	0	0		
LOT 5 - BURGER KING (PLAN WITHDRAWN)	4	4	0	4	4	0	0	4	0	0		
UNION HOTEL	4	3	0	3	3	0	0	0	0	0		
UPPER ALLEN BUSINESS PARK	96											
UPPER ALLEN BUSINESS PARK, PREVIOUS DEVEL.	53	0	0	0	0	0	0	0	0	0		
U. ALLEN BUSINESS PARK, LOT 7, EQUITERRA	6	6	0	6	6	0	0	0	0	0		
U. ALLEN BUSINESS PARK, LOT 10 C	3	0	0	0	0	0	0	0	0	0		
U. ALLEN BUSINESS PK., LOT 11, VALLEY SUPPLY	3	3	0	3	3	0	0	0	0	0		
UABP, LOT 11, SUBLOT 1 - VALLEY SUPPLY	1	0	0	0	0	0	0	0	0	0		
UABP, LOT 11, SUBLOT 2 - FRANK M. BINGMAN REV. TRUST (FORMERLY DEBLIN)	2	2	0	2	2	0	0	0	0	0		
UABP, LOT 11, SUBLOT 3, MOUNTAINEER PROPERTIES	0	0	0	0	0	0	0	0	0	0		
UABP, LOT 11, SUBLOT 4, WM. R. GRACE	1	1	0	1	1	0	0	0	0	0		
UPPER ALLEN BUSINESS PARK, FUTURE DEVEL.	27	27	0	27	27	0	0	0	0	0		

UPPER ALLEN TOWNSHIP  
SEWER CONNECTION PROJECTIONS  
YEARS 2024 THROUGH 2028

APPROVED AND PLANNED DEVELOPMENT CONNECTIONS - EDUS LOWER ALLEN BASIN												
SUBDIVISION / LAND DEVELOPMENT	TOTAL EDUS	REMAINING EDUS JANUARY 1, 2023	EDUS CONNECTED DURING 2023	REMAINING EDUS JANUARY 1, 2024	PROJECTED NEW CONNECTIONS				PROJECTED NEW CONNECTIONS TRIBUTARY TO			
					2024	2025	2026	2027	2028	TATTERSALL P.S. (2)	ARCONA ROAD P.S. NO. 3 (1)	
RICHARD S. & MARGARET M. WILDER	2	2	0	2	0	0	0	0	0	0		
WINDING HILL CORPORATE CENTER	21	6	0	6	0	0	0	0	0	0		
GLAZE ORCHARD PRD (WINDING HILLS STAGE 1)	175	0	0	0	0	0	0	0	0	0		
WINDING HILLS PRD, STAGE 2	214	0	0	0	0	0	0	0	0	0		
WINDING HILLS PRD, STAGE 3	56	0	0	0	0	0	0	0	0	0		
WINDING HILLS PRD, STAGE 4 (2013-2017)	109	0	0	0	0	0	0	0	0	0		
WINDING HILLS PRD, STAGE 5 (2015-2018)	93											
WINDING HILLS PRD, STAGE 5 - LOTS 198-215 (A)	22	2	0	2	0	0	0	0	0	0		2
WINDING HILLS PRD, STAGE 5 - LOTS 325-360 (B)	36	0	0	0	0	0	0	0	0	0		
WINDING HILLS PRD, STAGE 5 - LOTS 361-395 (C)	35	14	10	4	4	0	0	0	0	0		4
WINDING HILLS PRD, STAGE 6 (2017-2019)	47											
WINDING HILLS PRD, STAGE 6 - LOTS 278-290, LOTS 310, 311, AND 324 (A)	16	0	0	0	0	0	0	0	0	0		
WINDING HILLS PRD, STAGE 6 - LOTS 291-309, 312-323 (B)	31	0	0	0	0	0	0	0	0	0		
WINDING HILLS PRD, STAGE 7 (2018-2020)	78											
STAGE 7, SECTION 1	59	0	0	0	0	0	0	0	0	0		
STAGE 7, SECTION 2	19	0	0	0	0	0	0	0	0	0		
WINDING HILLS PRD, STAGE 8 (2019-2021)	117											
WINDING HILLS PRD, STAGE 8 (A) - LOTS 420-436, 465-471, J and K	50	1	1	0	0	0	0	0	0	0		
WINDING HILLS PRD, STAGE 8 (B) - LOTS 439-464, LOT L	68	28	17	11	11	0	0	0	0	0		11
<b>Total Approved</b>	<b>2,831</b>	<b>598</b>	<b>84</b>	<b>514</b>	<b>91</b>	<b>70</b>	<b>52</b>	<b>37</b>	<b>41</b>	<b>9</b>	<b>141</b>	
<b>PLANNED DEVELOPMENT</b>												
GRAHAM HILL APARTMENTS (ADDITION)	24	24	0	24	0	0	0	0	0	0		
FUTURE ANTICIPATED	100	100	0	100	0	10	0	10	0	0		0
<b>Total Planned</b>	<b>124</b>	<b>124</b>	<b>0</b>	<b>124</b>	<b>0</b>	<b>10</b>	<b>0</b>	<b>10</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>
<b>TOTAL APPROVED AND PLANNED</b>	<b>2,955</b>	<b>722</b>	<b>84</b>	<b>638</b>	<b>91</b>	<b>80</b>	<b>52</b>	<b>47</b>	<b>41</b>	<b>9</b>	<b>141</b>	

(1) Projected connections to pumping stations are only 2-year projections for DEP Chapter 94 Wasteload Management reporting.

(2) Tattersall pumping station is privately owned and operated by Tattersall HOA.

# Upper Allen Township






2023

## Sanitary Sewer Extensions


### Legend

- 1 Pump Stations
- Grantham WWTP
- 2023
- Existing Manholes
- 2023 Sewers
- Parcels
- Mini Drainage Basins**
- Grantham
- Lower Allen North
- Lower Allen South
- Mechanicsburg
- Collector
- Trunk / Interceptor
- Force Main
- Low Pressure
- Basin Divide
- Railroad
- Parcels
- Township Boundary

24 Manholes installed in 2023  
 2 Developments:  
 • Winding Hills PRD Stage 8B  
 • Autumn Chase PRD Phase 2



# MECHANICSBURG BASIN



# **Exhibit C**

**Pumping Station No. 3 Flow Data**

EXHIBIT C

UPPER ALLEN TOWNSHIP  
ARCONA ROAD PUMPING STATION NO. 3  
LOWER ALLEN TOWNSHIP DRAINAGE BASIN

YEAR 2023	PUMP RUN HOURS <sup>1</sup>				GALLONS PUMPED				TOTAL MONTHLY GALLONS PUMPED	AVERAGE MONTHLY DAILY FLOW (GPD)	PUMP CAPACITY (GPM) <sup>2</sup>			
	PUMP NO. 1	PUMP NO. 2	PUMP NO. 3	PUMP NO. 4	PUMP NO. 1	PUMP NO. 2	PUMP NO. 3	PUMP NO. 4			PUMP NO. 1	PUMP NO. 2	PUMP NO. 3	PUMP NO. 4
JANUARY	30.6	27.6	28.8	133.0	5,239,944	4,671,576	4,442,688	8,530,620	22,884,828	738,220	2,854	2,821	2,571	1,069
FEBRUARY	21.8	19.5	20.1	125.0	3,733,032	3,300,570	3,100,626	8,017,500	18,151,728	648,276				
MARCH	21.3	19.3	20.1	183.0	3,647,412	3,266,718	3,100,626	11,737,620	21,752,376	701,690				
APRIL	20.1	18.0	18.7	126.0	3,441,924	3,046,680	2,884,662	8,081,640	17,454,906	581,830				
MAY	54.8	49.2	52.6	12.0	9,383,952	8,327,592	8,114,076	769,680	26,595,300	857,913				
JUNE	28.6	25.4	26.7	87.0	4,897,464	4,299,204	4,118,742	5,580,180	18,895,590	629,853				
JULY	26.2	23.7	25.1	124.0	4,486,488	4,011,462	3,871,926	7,953,360	20,323,236	655,588				
AUGUST	15.8	14.3	15.0	142.0	2,705,592	2,420,418	2,313,900	9,107,880	16,547,790	533,800				
SEPTEMBER	21.5	19.7	20.7	111.0	3,681,660	3,334,422	3,193,182	7,119,540	17,328,804	577,627				
OCTOBER	19.0	19.2	20.9	123.0	3,253,560	3,249,792	3,224,034	7,889,220	17,616,606	568,278				
NOVEMBER	18.2	20.8	19.3	135.0	3,116,568	3,520,608	2,977,218	8,658,900	18,273,294	609,110				
DECEMBER	25.2	27.4	27.2	115.0	4,315,248	4,637,724	4,195,872	7,376,100	20,524,944	662,095				
<b>TOTAL</b>	<b>303.1</b>	<b>284.1</b>	<b>295.2</b>	<b>1416.0</b>	<b>51,902,844</b>	<b>48,086,766</b>	<b>45,537,552</b>	<b>90,822,240</b>	<b>236,349,402</b>					
<b>MONTHLY MINIMUM FLOW (GAL.)</b>					<b>2,705,592</b>	<b>2,420,418</b>	<b>2,313,900</b>	<b>769,680</b>	<b>16,547,790</b>					
<b>MONTHLY AVERAGE FLOW (GAL.)</b>					<b>4,325,237</b>	<b>4,007,231</b>	<b>3,794,796</b>	<b>7,568,520</b>	<b>19,695,784</b>					
<b>MONTHLY MAXIMUM FLOW (GAL.)</b>					<b>9,383,952</b>	<b>8,327,592</b>	<b>8,114,076</b>	<b>11,737,620</b>	<b>26,595,300</b>					
<b>MAXIMUM DAILY FLOW (GAL.)<sup>3</sup></b>					<b>1,637,000</b>									
<b>ANNUAL AVERAGE DAILY FLOW (GAL.)</b>					<b>647,023</b>									

<sup>1</sup> Data from manual pump run times.

<sup>2</sup> Determined through manual pump drawdown tests.

<sup>3</sup> Data from flowmeter located at UAT/LATA Rossmoyne metering vault.

# **Exhibit D**

## **Hydraulic Loading Data**

# TUS A-12\_Attachment

## EXHIBIT D UAT Flows to LATA WWTP Flow Table

### Flows - MGD

Month	Monthly Average Daily Flows, MGD					
	2019	2020	2021	2022	2023	5-Year Average
January	2.021	1.148	1.090	1.079631	1.379254	
February	1.816	1.156	1.135	1.217525	1.089576	
March	2.183	1.199	1.229	1.114946	1.195256	
April	1.816	1.260	1.180	1.388553	1.182396	
May	1.860	1.302	1.063	1.736614	1.225125	
June	1.258	1.155	1.049	1.151783	1.976883	
July	1.104	0.995	1.109	1.041644	1.283653	
August	0.956	0.964	1.006	1.006529	1.002603	
September	0.915	0.918	1.397	0.988253	1.035016	
October	0.992	0.937	1.126	0.968067	1.033753	
November	1.055	0.952	1.108	1.013992	1.04337	
December	1.114	1.107	1.041	1.490045	1.266413	
Annual Average	1.424	1.091	1.128	1.183	1.226	1.210

Max. Month	2.183	1.302	1.397	1.737	1.977	1.719
Max/Average Ratio	1.53	1.19	1.24	1.47	1.61	1.41
2-Month Max.	2.102	1.281	1.313	1.613	1.678	1.597
2-Month Max./Average Ratio	1.48	1.17	1.16	1.36	1.37	1.31
3-Month Max.	1.994	1.247	1.241	1.497	1.447	1.485
3-Month Max./Average Ratio	1.40	1.14	1.10	1.27	1.18	1.22

### Flow Projections

Year	Previous Flow +	(Additional EDUs)	Increased Flow =	Projected Flow x	Projected Factor =	Projected Max. Month
2024	1.210	91	0.02275	1.233	1.41	1.74
2025	1.233	80	0.02000	1.253	1.41	1.77
2026	1.253	52	0.01300	1.266	1.41	1.78
2027	1.266	47	0.01175	1.278	1.41	1.80
2028	1.278	41	0.01025	1.288	1.41	1.81

