



PUC Notification of Proposed Major Expenditure

Submit reports to the PA PUC Secretary's Bureau through eFiling at

efiling.puc.pa.gov

Include case: Docket number **M-2020-3021947** in the notification

Also Email To: Safety Division

Email To The Following Addresses: RA-PC-Pipelinesafety@pa.gov & TCSmith@pa.gov

Regional Engineering Office	One UGI Center, Wilkes Barre, PA 18711
Description of Proposed Work	The Luzerne Avenue, Salem Township medium pressure replacement project will consist of the installation of approximately 1,707 LF of 4" HDPE medium-pressure gas main and 552 LF of 2" HDPE medium-pressure gas main by direct burial to eliminate approximately 1,567 LF of 4" bare steel medium-pressure gas main and 1,142 LF of 4" coated steel medium-pressure gas main. There will be approximately 25 service renewals and 2 service test and connects associated with this project. Work for this project will take place on Luzerne Avenue, E. 5th Street, E. 4.5 Street, E. 3rd Street, and E. 2nd Street
Location of Proposed Work	Salem Township, Luzerne County
Type of Facility	Natural Gas Distribution Main and Services
Estimated Starting Date	Estimated Starting Date: 7/8/2026
Design Pressure (MAOP, psi)	60.00
Estimated Cost	Estimated Cost: \$1,075,800
Reporting Gas Company for Project	UGI North
Project Contact Person(s)	Andress, Seth M
Project Contact Person(s) Address & Phone	Project Contact Person(s) Address & Phone: One UGI Center, Wilkes Barre, PA 18711; 570-550-3461
Estimated Completion Date	Estimated Completion Date: 9/30/2026
Actual Completion Date	Actual Completion Date:

PA PUC Notification Documentation	
Notified By (Proposed)	Andress, Seth M
Notifier's Title (Proposed)	Notifier's Title (Proposition): Engineer III
Notification Date (Proposed)	Notification Date (Proposition): 1/6/2025
Notified By (Actual Completion)	
Notifier's Title (Actual Completion)	Notifier's Title (Actual Completion):
Notification Date (Actual Completion)	Notification Date (Actual Completion):