



PUC Notification of Proposed Major Expenditure

Submit reports to the PA PUC Secretary's Bureau through eFiling at

efiling.puc.pa.gov

Include case: Docket number **M-2025-3052787** in the notification

Also Email To: **Safety Division**

Email To The Following Addresses: **RA-PC-Pipelinesafety@pa.gov & TCSmith@pa.gov**

Regional Engineering Office	1301 AIP Drive, Middletown, PA 17057-5987
Description of Proposed Work	B016400 1st St LTIIP - Ruby & Coral. Direct bury 2,091' 2" PE MP gas main and insert 386' of 2" PE MP gas main on 1st, Ruby, Coral and Lake Streets in Lancaster. The project will retire in place 1,694' of existing 4" cast iron LP gas main, 347' of existing 6" steel LP gas main, 355' of existing 4" steel LP gas main, 2' of existing 2" steel LP gas main, 22' of existing 1.25" steel LP gas main, 104' of existing 6" PE LP gas main, 135' of existing 4" PE LP gas main, and 112' of existing 1.25" PE LP gas main.
Location of Proposed Work	1st, Ruby, Coral and Lake Streets in Lancaster.
Type of Facility	Distribution Main
Estimated Starting Date	Estimated Starting Date: 4/1/2024
Design Pressure (MAOP, psi)	60.00
Estimated Cost	Estimated Cost: \$2,500,000
Reporting Gas Company for Project	UGI South
Project Contact Person(s)	O'Donald, David;
Project Contact Person(s) Address & Phone	Project Contact Person(s) Address & Phone: 1 UGI Drive, Denver, PA. 17517 610-816-4862
Estimated Completion Date	Estimated Completion Date: 9/30/2024
Actual Completion Date	Actual Completion Date: 9/30/2024
PA PUC Notification Documentation	
Notified By (Proposed)	O'Donald, David;
Notifier's Title (Proposed)	Notifier's Title (Proposition): Manager Project Manager
Notification Date (Proposed)	Notification Date (Proposition): 1/30/2024
Notified By (Actual Completion)	Ferguson, Geoffrey J;
Notifier's Title (Actual Completion)	Notifier's Title (Actual Completion): Senior Manager Area Engineering
Notification Date (Actual Completion)	Notification Date (Actual Completion): 9/30/2024

DocuSigned by:

 6AA3C2A337D044F...