



March 3, 2025

Via E-Filing

Rosemary Chiavetta, Secretary
Pennsylvania Public Utility Commission
Commonwealth Keystone Building
400 North Street 2nd Floor North
P.O. Box 3265
Harrisburg, PA 17105-3265

M-2025-3052787 ydd/sec

Re: PA Code §59.38 Filing of Major Construction Reports – Notification of Proposed Construction in the Township of Harford, Susquehanna County Pennsylvania

Dear Secretary Chianetta:

Enclosed find the filing for Leatherstocking Gas Company of a Notification of Proposed Construction project that will expenditure in excess of \$300,000.00, which is made pursuant to 52 PA. Code 59.38.

Thank you,

A handwritten signature in black ink, appearing to read "Jeffery Spear", is written over the "Thank you," text.

Jeffery Spear
Chief Operating Officer
Leatherstocking Gas Company



NOTIFICATION OF PROPOSED CONSTRUCTION

Pursuant to the requirements of 52 Pa. Code § 59.38, Leatherstocking Gas Company hereby files the following Notification of Proposed Construction:

1. **Description and Location of Proposed Work:** The Mountain View Gate Station & Pipeline Project consists of approximately 4,452 feet of 4-inch HDPE gas main, crossing both S.R. 2022 and S.R. 0106 state highways. The project begins at the Williams - Owego South 24-inch pipeline tie-in area, just south of the Gate Station building, then extends northeast, paralleling the Gate Station access road down to S.R. 2022. From there, the pipeline continues eastward, running parallel to S.R. 2022, before crossing both S.R. 2022 and S.R. 0106 in a northeasterly direction. The pipeline terminates on the western side of Mountain View Elementary School.

As part of the project, the Mountain View High School and Elementary School and additionally multiple support buildings.

Additionally, the project includes:

- Approximately 464 feet of 2-inch HDPE gas main along S.R. 2022 'Milford & Owego Turnpike', starting at the Gate Station entranceway and extending northwest to serve additional residences.
 - 144 feet of 2-inch steel gas main, connecting the Owego South Pipeline to the Mountain View Gate Station.
 - A 4-inch HDD bore underneath S.R. 0106, enabling service to the Mountain View Elementary School building.
 - A gate station for metering and regulating gas purchased from Williams, which will be injected into the Mountain View School distribution system.
2. **Type of Facility:** 2" and 4" plastic gas main and 2" and 1" steel gas main.
 3. **Estimated Starting Date:** Construction is expected to begin on or about April 1st, 2025.
 4. **Estimated Completion Date:** Construction is expected to be completed by November 1, 2025.
 5. **Design Pressure:** The distribution side of the pipeline will be designed for a maximum allowable operating pressure of 120 psig. The short section of pipeline upstream of the Gate Station will be designed for a maximum allowable operating pressure of 1440 psig.
 6. **Estimated Cost:** The cost of the pipeline project is \$1,900,000,00.
 7. **Name and Address of Reporting Gas Co:** Leatherstocking Gas Company, 498 S Main Street, Montrose PA 18801
 8. **Leatherstocking Contact:** Harry German, Leatherstocking Gas Company, 330 West William Street, Corning NY 14830. Phone 607-936-3755. Email: HGerman@corninggas.com