



**PUC Notification of Proposed Major Expenditure**

**Submit reports to the PA PUC Secretary's Bureau through eFiling at**

efiling.puc.pa.gov

Include case: Docket number **M-2025-3052787** in the notification

**Also Email To: Safety Division**

**Email To The Following Addresses: RA-PC-Pipelinesafety@pa.gov & TCSmith@pa.gov**

Regional Engineering Office	One UGI Center, Wilkes Barre, PA 18711
Description of Proposed Work	To install approximately 2320 feet of two (2) inch plastic gas main by direct burial, renew thirty-five (35) gas services and tie over one (1) gas service. This replacement project will eliminate 2262 feet of existing bare steel main, 453 feet of existing coated steel main, and 74 feet of existing plastic.
Location of Proposed Work	The work will be performed in Bailey St., between Leach St. and Bobcat Ln; in Leach St., between Bailey St. and S Abington Rd.; and in Grandview St., between Bailey St. and Mountain Rd., S Abington Twp., Lackawanna County
Type of Facility	Natural Gas Distribution Main and Services
Estimated Starting Date	Estimated Starting Date: 10/6/2025
Design Pressure (MAOP, psi)	35.00
Estimated Cost	Estimated Cost: \$1,165,200
Reporting Gas Company for Project	UGI North
Project Contact Person(s)	Coolican, Megan C
Project Contact Person(s) Address & Phone	Project Contact Person(s) Address & Phone: 150 Power Blvd. Archbald, PA 18403; 570-309-9502
Estimated Completion Date	Estimated Completion Date: 11/7/2025
Actual Completion Date	Actual Completion Date:

**PA PUC Notification Documentation**

Notified By (Proposed)	Coolican, Megan C
Notifier's Title (Proposed)	Notifier's Title (Proposition): Engineer III
Notification Date (Proposed)	Notification Date (Proposition): 6/16/2025
Notified By (Actual Completion)	
Notifier's Title (Actual Completion)	Notifier's Title (Actual Completion):
Notification Date (Actual Completion)	Notification Date (Actual Completion):