



Energy to do more®

### PUC Notification of Proposed Major Expenditure

Submit reports to the PA PUC Secretary's Bureau through eFiling at

[efiling.puc.pa.gov](http://efiling.puc.pa.gov)

Include case: Docket number **M-2025-3052787** in the notification

**Also Email To: Safety Division**

**Email To The Following Addresses: RA-PC-Pipelinesafety@pa.gov & TCSmith@pa.gov**

Regional Engineering Office	One UGI Center, Wilkes Barre, PA 18711
Description of Proposed Work	Install approximately 94LF of 2" PE4710 (MP) G.M. via HDDFT, Install approximately 300LF of 8" PE4710 (MP) G.M. via HDD and Install approximately 2,110LF of 8" PE4710 (MP) G.M. via Direct Burial. Project will renew (22) gas services and T/C (2) gas services. The work will be performed in public/private right-of-way on S Stevens St (SR0044) and along Oswayo St (SR4012), Coudersport, Potter County.
Location of Proposed Work	Coudersport, Shinglehouse Borough / Sharon Twp, Potter County, PA.
Type of Facility	Natural Gas Distribution Main and Services.
Estimated Starting Date	Estimated Starting Date: 8/25/2025
Design Pressure (MAOP, psi)	60.00
Estimated Cost	Estimated Cost: \$1,096,783
Reporting Gas Company for Project	UGI Central
Project Contact Person(s)	Hoover, John J.
Project Contact Person(s) Address & Phone	Project Contact Person(s) Address & Phone: One UGI Center, Wilkes-Barre, Pa. 18711; 507-831-9737
Estimated Completion Date	Estimated Completion Date: 9/30/2025
Actual Completion Date	Actual Completion Date:
<b>PA PUC Notification Documentation</b>	
Notified By (Proposed)	Hoover, John J.
Notifier's Title (Proposed)	Notifier's Title (Proposition): Engineer III
Notification Date (Proposed)	Notification Date (Proposition): 6/16/2025
Notified By (Actual Completion)	
Notifier's Title (Actual Completion)	Notifier's Title (Actual Completion):
Notification Date (Actual Completion)	Notification Date (Actual Completion):