



Energy to do more®

PUC Notification of Proposed Major Expenditure

Submit reports to the PA PUC Secretary’s Bureau through eFiling at

efiling.puc.pa.gov

Include case: Docket number **M-2025-3052787** in the notification

Also Email To: Safety Division

Email To The Following Addresses: RA-PC-Pipelinesafety@pa.gov & TCSmith@pa.gov

Regional Engineering Office	2121 City Line Rd., Bethlehem, PA 18017-2127
Description of Proposed Work	Direct bury 2904 feet of 2" HDPE, 1935 feet of 4" HDPE, 659 feet of 6" HDPE. Insert 288 feet of 2" HDPE inside 4" Steel. Jack and Bore 345 feet of 6" HDPE is being inserted in 8" steel casing pipe. Retiring 1682 feet of 2", 3" and 4" Plastic, 1110 feet of 3" and 4" Bare Steel, 2933 feet of 3" and 4" Coated Steel.
Location of Proposed Work	Analomink St, from S Courtland St to Ransberry Ave. Prospect St, from Analomink St to Normal Street. Ransberry Ave, from Analomink St to Normal St. Fairview St, from Prospect St to dead end. Penn St, from Fairview St to S Kistler St. All of this is in East Stroudsburg in Monroe County.
Type of Facility	Distribution Main
Estimated Starting Date	Estimated Starting Date: 10/1/2025

Design Pressure (MAOP, psi)	60.00
Estimated Cost	Estimated Cost: \$2,700,000
Reporting Gas Company for Project	UGI Central
Project Contact Person(s)	Steward, Timothy; ^{DS}  
Project Contact Person(s) Address & Phone	Project Contact Person(s) Address & Phone: 2121 City Line Rd., Bethlehem, PA 18017; 610-807-3162
Estimated Completion Date	Estimated Completion Date: 2/18/2026 
Actual Completion Date	Actual Completion Date: 
PA PUC Notification Documentation	
Notified By (Proposed)	Steward, Timothy;  
Notifier's Title (Proposed)	Notifier's Title (Proposition): Senior Manager Area Engineering
Notification Date (Proposed)	Notification Date (Proposition): 8/27/2025 
Notified By (Actual Completion)	 
Notifier's Title (Actual Completion)	Notifier's Title (Actual Completion): 
Notification Date (Actual Completion)	Notification Date (Actual Completion): 