

Docket No. M-2025-3052787

REPORT OF MAJOR CONSTRUCTION PROJECT

COMPANY: COLUMBIA GAS OF PENNSYLVANIA, INC. DEPARTMENT: Distribution

ESTIMATED COST OF PROJECT: \$2.4 Million

DESCRIPTION OF PROJECT: 23-0232334-00 (557) – Install ~6,897’-2”/4” PMMP
23-0232335-00 (558) – Abandon ~6,112’-2”/3” PLP, CSLP, BSLP
23-0232336-00 (558) – Abandon ~969’-1”/2” PMMP, CSMP, UNK MP
23-0232501-00 (0001) – Requal ~309’-2” Plastic

LOCATION OF PROJECT: Front St, Dickerson Run Rd, Liberty Ave, Locust St, Highland Rd, Maple Ave, Edwards St, Budd St, Center St, Stephens St, and Hollow Rd in Dickerson Run, Fayette County, PA

ESTIMATED STARTING DATE: October 1, 2024

ESTIMATED COMPLETION DATE: February 1, 2025

PERSON TO BE CONTACTED REGARDING PROJECT: Jenna Hampson

ADDRESS: 12 Sandstone Way, Dunbar, PA 15341 TELEPHONE NUMBER: 724-322-4175

MAXIMUM ALLOWABLE OPERATING PRESSURE: 18 psig

CONSTRUCTION TYPE: Natural Gas Main - Replacement LOCATION CLASS: N/A

PIPE & COATING DESCRIPTION:

- | | | | | |
|-----------------------|-------------------|------------------------------------|-----|---------------------|
| a. Nominal Diameter | 2” PMMP & 4” PMMP | b. 0.216” and 0.391”, respectively | | |
| c. Pipe Specification | PE2406/2708 | d. Grade | N/A | e. Type SDR 11/11.5 |
| f. Coating Type | N/A | g. Method of Application | | Direct Bury |

TEST DATA:

- | | | | |
|----------------|-----|-------------|----------|
| a. Test Medium | Air | b. Duration | 16 hours |
|----------------|-----|-------------|----------|

Submit to:

COMPLETION DATE: 10/15/25

Safety Division, Bureau of Investigation & Enforcement
Pennsylvania Public Utility Commission
Post Office Box 3265
Harrisburg, Pennsylvania 17120