

Angelina Umstead, Esq.

(610) 921-6202  
Fax: (330) 315-9263

January 14, 2026

**VIA ELECTRONIC FILING**

Matthew Homsher, Secretary  
Pennsylvania Public Utility Commission  
Commonwealth Keystone Building  
400 North Street, 2<sup>nd</sup> Floor  
Harrisburg, PA 17120

**Re: 3<sup>rd</sup> Quarter 2025 Reliability Report – FirstEnergy Pennsylvania  
Electric Company on behalf of Met-Ed Rate District, Penelec Rate District,  
Penn Power Rate District and West Penn Rate District;  
Public Version; Docket No. M-2023-3039027**


Dear Secretary Homsher:

Pursuant to 52 Pa. Code § 57.195(d) and (e), enclosed for filing by FirstEnergy Pennsylvania Electric Company (“FE PA” or the “Company”) on behalf of Met-Ed Rate District (“Met-Ed”), Penelec Rate District (“Penelec”), Penn Power Rate District (“Penn Power”), and West Penn Rate District (“West Penn”) is the revised 3<sup>rd</sup> Quarter 2025 Reliability Report – Public Version (“Report”). Please note that a revised report is being filed at this time to reflect the major event exclusion that was granted in Penelec on December 8, 2025, at Docket No. M-2025-3058252.

On December 22, 2004, the Company filed an Application for Protective Order at Docket No. L-00030161. The Application was granted, allowing the Company to file proprietary versions of the quarterly reliability reports. The Proprietary Version of this Report is being filed under separate cover.

Please feel free to contact me if you have any questions or need additional information regarding this matter.

Sincerely,



Angelina Umstead

AU/dml

Enclosures

- c: As Per Certificate of Service  
D. Searfoorce - Bureau of Technical Utility Services (via email and first-class mail)  
J. Van Zant – Bureau of Technical Utility Services (via email and first-class mail)  
Derek Ruhl - PaPUC Bureau of Technical Utility Services (via electronic mail)

**BEFORE THE  
PENNSYLVANIA PUBLIC UTILITY COMMISSION**

**3<sup>rd</sup> Quarter 2025 Reliability Report –** :  
**FirstEnergy Pennsylvania Electric** :  
**Company on behalf of Met-Ed Rate** :  
**District, Penelec Rate District, Penn Power** : **Docket No. M-2023-3039027**  
**Rate District and West Penn Rate District –** :  
**Public Version** :

**CERTIFICATE OF SERVICE**

I hereby certify that I have this day served a true and correct copy of the foregoing document upon the individuals listed below, in accordance with the requirements of 52 Pa. Code § 1.54 (relating to service by a participant).

Service by electronic mail, as follows:

NazAarah Sabree  
Office of Small Business Advocate  
Suite 1102, Commerce Building  
300 North Second Street  
Harrisburg, PA 17101  
[ra-sba@pa.gov](mailto:ra-sba@pa.gov)

Allison Kaster  
Bureau of Investigation and Enforcement  
Pennsylvania Public Utility Commission  
400 North Street 2nd Floor West  
Harrisburg, PA 17105-3265  
[akaster@pa.gov](mailto:akaster@pa.gov)

Harrison W. Breitman  
Darryl A. Lawrence  
Office of Consumer Advocate  
555 Walnut Street – 5<sup>th</sup> Floor  
Harrisburg, PA 17101-1923  
[HBreitman@paoca.org](mailto:HBreitman@paoca.org)  
[DLawrence@paoca.org](mailto:DLawrence@paoca.org)

Byron Farnsworth, Jr., Chief Operating Officer  
Tyler Meade, Director of Operations  
Wellsboro Electric Company  
33 Austin Street  
Wellsboro, PA 16901  
[barneyf@ctenterprises.org](mailto:barneyf@ctenterprises.org)  
[tylerm@actennterprises.org](mailto:tylerm@actennterprises.org)

Eric Sorber  
UGI Utilities, Inc.  
One UGI Center  
Wilkes-Barre, PA 18711  
[esorber@ugi.com](mailto:esorber@ugi.com)

Kimberly A. Klock, Esquire  
PPL Services Corp.  
2 North 9<sup>th</sup> Street  
Allentown, PA 18101  
[kklock@pplweb.com](mailto:kklock@pplweb.com)


Patrick F. Anderson, Sr. Director  
Citizens' Electric Company of Lewisburg, PA  
1775 Industrial Boulevard  
Lewisburg, PA 17837  
[andersonp@citizenselectric.com](mailto:andersonp@citizenselectric.com)

Thomas J. Sniscak, Esquire  
Whitney E. Snyder, Esquire  
Hawke McKeon and Sniscak LLP  
100 N. Tenth Street  
Harrisburg, PA 17101  
[tjsniscak@hmslegal.com](mailto:tjsniscak@hmslegal.com)  
[wesnyder@hmslegal.com](mailto:wesnyder@hmslegal.com)

Lindsay Baxter, Analyst  
Mary Kellam  
Duquesne Light Company  
411 Seventh Avenue  
Pittsburgh, PA 15219  
[lbaxter@duqlight.com](mailto:lbaxter@duqlight.com)  
[mkellam@duqlight.com](mailto:mkellam@duqlight.com)

Richard G. Webster, Jr.  
Director of Rates  
Peco Energy Company  
2301 Market Street, S15  
Philadelphia, PA 19103  
[Dick.webster@peco-energy.com](mailto:Dick.webster@peco-energy.com)

Dated: January 14, 2026



---

Angelina Umstead  
Attorney No. 309615  
FirstEnergy Service Company  
341 White Pond Drive  
Akron, OH 44320  
(610) 921-6202  
[aumstead@firstenergycorp.com](mailto:aumstead@firstenergycorp.com)

Counsel for:  
FirstEnergy Pennsylvania Electric Company on  
behalf of Met-Ed Rate District, Penelec Rate  
District, Penn Power Rate District and West Penn  
Rate District



## 2025 3<sup>rd</sup> Quarter Reliability Report

FirstEnergy Pennsylvania Electric Company on behalf of  
Met-Ed Rate District,  
Penelec Rate District,  
Penn Power Rate District, and  
West Penn Rate District

Pursuant to 52 Pa. Code § 57.195(d) and (e)

**3<sup>rd</sup> Quarter 2025 Reliability Report –  
 FirstEnergy Pennsylvania Electric Company (“FE PA”) on behalf of  
 Met-Ed Rate District (“Met-Ed”),  
 Penelec Rate District (“Penelec”),  
 Penn Power Rate District (“Penn Power”), and  
 West Penn Rate District (“West Penn”)**

*Section 57.195(e)(1):*

*A description of each major event that occurred during the preceding quarter, including the time and duration of the event, the number of customers affected, the cause of the event and any modified procedures adopted in order to avoid or minimize the impact of similar events in the future.<sup>1</sup>*

*Major Event(s)*

| FE PA Rate District | Customers Affected | Time and Duration of the Event |                      | Cause of the Event           | Commission Approval Status |
|---------------------|--------------------|--------------------------------|----------------------|------------------------------|----------------------------|
| Penelec             | 7,755              | Duration                       | 130 hours 47 minutes | Heavy rain and extreme winds | December 8, 2025           |
|                     |                    | Start Date/Time                | July 3, 2025/1510    |                              |                            |
|                     |                    | End Date/Time                  | July 9, 2025/0157    |                              |                            |

---

<sup>1</sup> For purposes of this Report, all reliability reporting is based upon the Pennsylvania Public Utility Commission’s definitions for momentary outages and major events pursuant to 52 Pa. Code § 57.192.

Submitted Pursuant to 52 Pa. Code § 57.195(d) and (e)

*Section 57.195(e)(2): Rolling 12-month reliability index values (SAIFI, CAIDI, SAIDI, and if available MAIFI) for the EDC's service territory for the preceding quarter. The report shall include the data used in calculating the indices, namely the average number of customers served, the number of sustained customer interruptions, the number of customers affected, and the customer minutes of interruption. If MAIFI values are provided, the report shall also include the number of customer momentary interruptions.*

*Reliability Index Values*

| 3Q 2025<br>(12-Mo Rolling)                        | Met-Ed      |                   |                 | Penelec     |                   |                 | Penn Power |                   |                 | West Penn   |                   |                 |
|---|-------------|-------------------|-----------------|-------------|-------------------|-----------------|------------|-------------------|-----------------|-------------|-------------------|-----------------|
|   | Benchmark   | 12-Month Standard | 12-Month Actual | Benchmark   | 12-Month Standard | 12-Month Actual | Benchmark  | 12-Month Standard | 12-Month Actual | Benchmark   | 12-Month Standard | 12-Month Actual |
| <b>SAIFI</b>                                      | 1.15        | 1.38              | 1.56            | 1.26        | 1.52              | 1.64            | 1.12       | 1.34              | 1.17            | 1.05        | 1.26              | 1.19            |
| <b>CAIDI</b>                                      | 117         | 140               | 199.46          | 117         | 141               | 190.59          | 101        | 121               | 131.40          | 170         | 204               | 209.07          |
| <b>SAIDI</b>                                      | 135         | 194               | 311.85          | 148         | 213               | 312.86          | 113        | 162               | 153.58          | 179         | 257               | 249.28          |
| <b>MAIFI<sup>2</sup></b>                          |             |                   | 0.444           |             |                   | 0.600           |            |                   | 0.229           |             |                   |                 |
| <b>Customers Served<sup>3</sup></b>               | 584,493     |                   |                 | 591,483     |                   |                 | 175,724    |                   |                 | 729,710     |                   |                 |
| <b>Number of Sustained Interruptions</b>          | 14,001      |                   |                 | 17,666      |                   |                 | 4,037      |                   |                 | 15,387      |                   |                 |
| <b>Customers Affected</b>                         | 913,843     |                   |                 | 970,944     |                   |                 | 205,383    |                   |                 | 870,056     |                   |                 |
| <b>Customer Minutes</b>                           | 182,275,886 |                   |                 | 185,051,014 |                   |                 | 26,987,553 |                   |                 | 181,899,290 |                   |                 |
| <b>Number of Customer Momentary Interruptions</b> | 259,280     |                   |                 | 355,059     |                   |                 | 40,253     |                   |                 |             |                   |                 |

<sup>2</sup> MAIFI values are not available for West Penn.

<sup>3</sup> Represents the average number of customers served during the reporting period.

### **Unique Events Occurring in Q3 2025:**

#### Met-Ed

- Beginning the afternoon of Monday, June 30, 2025, a weather system began moving through Pennsylvania including FE PA's service territory, producing heavy rains and wind gusts of approximately 68 miles per hour on Tuesday, July 1, 2025. Damage as a result of high winds included downed wires, damaged or broken poles, trees, branches, and crossarms. The Reading, Hamburg, and Boyertown districts were the hardest hit areas. Approximately 60.4% of the total outages that occurred were tree related, and an additional 17.2% were line and equipment failures. Data indicates the reliability impact of the storm was 31.3 minutes of SAIDI, 0.07 of SAIFI, and an overall storm CAIDI of 464.34 minutes.
- Beginning the afternoon of Friday, July 25, 2025, a weather system began moving through Pennsylvania including FE PA's service territory, producing heavy rain and wind gusts of approximately 56 mph on Friday, July 25, 2025. Damage as a result of high winds included downed wires, damaged or broken poles, trees, branches, and crossarms. The Boyertown, Hamburg and Reading districts were the hardest hit areas. Approximately 58% of the total outages that occurred were tree related. Data indicates the reliability impact of the storm was 12.0 minutes of SAIDI, 0.02 of SAIFI, and an overall storm CAIDI of 482.65 minutes.

#### Penelec

- Beginning on the afternoon of Thursday, July 3, 2025, a weather system began moving through Pennsylvania including FE PA's service territory, producing heavy rain and wind gusts of approximately 37 miles per hour on Thursday, July 3, 2025, and 38 miles per hour on Monday, July 7, 2025. In addition to the weather that impacted the larger region, the Montrose region was the hardest hit area with widespread damage on July 3, 2025, that was consistent with 65 to 85 mph winds that occurred throughout the Susquehanna area due to a long tracking supercell that caused a large downburst. There were enhanced areas of tree damage where local terrain effects caused funneling of wind and eddies to form. The winds were noticeably higher in these areas, peaking at 90 to 100 mph. In particular, the Susquehanna and Oakland areas sustained significant tree damage. This delayed the restoration of customers until roads were cleared of debris and downed trees. At the onset of the outages, crews assessed the situation and formulated a restoration plan which included quarantining local circuits involved and having personnel staged to engage as soon as the area could be safely accessed. Approximately 41% of the total outages that occurred were tree-related, and an additional 27% were due to line and equipment failure. Damage because of the high winds included downed wires, broken poles, crossarms, and transformers. Data indicates the reliability impact of the storm was 48.3 minutes of SAIDI, 0.056 of SAIFI, and an overall storm CAIDI of 861.3 minutes.

*Section 57.195(e)(3): Rolling 12-month reliability index values (SAIFI, CAIDI, SAIDI, and if available, MAIFI) and other pertinent information such as customers served, number of interruptions, customer minutes interrupted, number of lockouts, and so forth, for the worst performing 5% of the circuits in the system. An explanation of how the EDC defines its worst performing circuits shall be included.*

#### *Worst Performing Circuits – Reliability Indices*

The methodology used to identify worst performing circuits is based on both SAIFI and SAIDI. The methodology consists of the following steps:

1. For each circuit, calculate a circuit SAIFI using only distribution-caused outages.
2. Select the worst 20% of circuits based on the highest circuit SAIFI.
3. Rank the selected circuits based on SAIDI using only distribution-caused customer minutes.
4. Select 5% of the circuits based on the highest customer minutes. These circuits are then identified as the worst performing circuits.

Met-Ed, Penelec, Penn Power, and West Penn's rankings of the 5% Worst Performing Circuits are provided in Attachment A to this report.

Submitted Pursuant to 52 Pa. Code § 57.195(d) and (e)

*Section 57.195(e)(4): Specific remedial efforts taken and planned for the worst performing 5% of the circuits identified in paragraph (3).*

*Worst Performing Circuits – Remedial Actions*

Met-Ed, Penelec, Penn Power, and West Penn’s Remedial Actions for Worst Performing Circuits are provided in Attachment B to this report.

*Section 57.195(e)(5): A rolling 12-month breakdown and analysis of outage causes during the preceding quarter, including the number and percentage of service outages, the number of customers interrupted, and customer interruption minutes categorized by outage cause such as equipment failure, animal contact, tree related, and so forth. Proposed solutions to identified service problems shall be reported.*

**Outages by Cause – Met-Ed**

| <b>Outage by Cause</b>                                  |                         |  |                           |                                    |
|---|-------------------------|--|---------------------------|------------------------------------|
| <b>3<sup>rd</sup> Quarter 2025<br/>12-Month Rolling</b> | <b>Met-Ed</b>           |  |                           |                                    |
| <b>Cause</b>  | <b>Customer Minutes</b> | <b>Number of Sustained Interruptions</b> | <b>Customers Affected</b> | <b>% Based on Customer Minutes</b> |
| Trees Off Row-Tree                                      | 62,399,675              | 2,804                                    | 174,042                   | 34.23%                             |
| Equipment Failure                                       | 50,125,796              | 2,644                                    | 201,527                   | 27.50%                             |
| Trees Off Row-Limb                                      | 11,949,629              | 1,158                                    | 46,181                    | 6.56%                              |
| Trees On Row  | 10,849,254              | 436                                      | 30,116                    | 5.95%                              |
| Line Failure  | 9,468,328               | 780                                      | 46,477                    | 5.19%                              |
| Forced Outage   | 9,465,051               | 716                                      | 152,506                   | 5.19%                              |
| Unknown   | 7,885,339               | 1,227                                    | 68,477                    | 4.33%                              |
| Vehicle   | 6,632,714               | 362                                      | 39,544                    | 3.64%                              |
| Animal  | 3,566,164               | 1,827                                    | 57,706                    | 1.96%                              |
| Wind  | 3,214,114               | 179                                      | 12,932                    | 1.76%                              |
| Lightning   | 1,557,749               | 217                                      | 5,073                     | 0.85%                              |
| Trees - Sec/Service                                     | 1,333,717               | 572                                      | 3,509                     | 0.73%                              |
| Overload  | 874,831                 | 131                                      | 9,491                     | 0.48%                              |
| Bird  | 684,482                 | 601                                      | 10,699                    | 0.38%                              |
| Object Contact With Line                                | 661,466                 | 53                                       | 7,646                     | 0.36%                              |
| Human Error - Company                                   | 598,775                 | 71                                       | 37,430                    | 0.33%                              |
| Human Error -Non-Company                                | 304,585                 | 58                                       | 1,990                     | 0.17%                              |
| Fire  | 228,314                 | 28                                       | 3,011                     | 0.13%                              |
| Other Utility-Non Elec                                  | 142,336                 | 12                                       | 1,336                     | 0.08%                              |
| Ug Dig-Up   | 137,418                 | 34                                       | 411                       | 0.08%                              |
| Contamination   | 79,243                  | 11                                       | 112                       | 0.04%                              |
| Customer Equipment                                      | 55,251                  | 39                                       | 3,403                     | 0.03%                              |
| Ice   | 22,796                  | 4  | 12                        | 0.01%                              |
| Other Electric Utility                                  | 18,407                  | 15                                       | 32                        | 0.01%                              |
| Vandalism   | 12,023                  | 5  | 63                        | 0.01%                              |
| Previous Lightning                                      | 6,665                   | 16                                       | 33                        | 0.00%                              |
| Switching Error   | 1,764                   | 1  | 84                        | 0.00%                              |
| <b>Total</b>  | <b>182,275,886</b>      | <b>14,001</b>                            | <b>913,843</b>            | <b>100%</b>                        |

### Proposed Solutions – Met-Ed

FE PA analyzes its outage data to develop solutions for improving reliability in the Met-Ed rate district. The following paragraphs identify the top outage causes for the rolling twelve-month period ending September 30, 2025, and associated actions designed to address these outage causes.

To improve system reliability, FE PA performs cycle-length tree trimming and enhanced tree trimming in select locations. Enhanced tree trimming removes healthy limbs overhanging primary conductors. FE PA’s options under the law are strictly limited when it comes to all forms of off-corridor tree management. However, FE PA is legally permitted to identify off-corridor priority trees that are dead, dying, diseased, leaning, or significantly encroaching the corridor and remove those trees when customer consent is obtained or easement rights permit. FE PA is active in pursuing this option, when available, to remove the highest risk trees. Trees identified with a high potential to cause a future outage are targeted for removal to prevent an interruption of electrical service to FE PA’s customers. Furthermore, FE PA continues its program to mitigate trees subject to damage from the Emerald Ash Borer. FE PA will also review areas off-cycle to mitigate tree risk in high impact areas.

To reduce the likelihood of equipment failure outages, FE PA follows inspection and maintenance (“I&M”) programs<sup>4</sup> that set forth schedules for regular inspections of distribution and substation facilities. These programs are geared towards specific components such as capacitors, poles, circuits, transformers, radio-controlled switches, substations, and reclosers. Equipment identified is repaired or replaced as appropriate. FE PA has executed Long-Term Infrastructure Improvement Plans (“LTIIIP”) which include expenditures and programs designed to adequately maintain and improve the efficiency, safety, adequacy, and reliability of the distribution system.

---

<sup>4</sup> Pursuant to Pa. Code § 57.198(a), every two years an electric distribution company shall file with the Commission a biennial plan for the periodic inspection, maintenance, repair, and replacement of its facilities. The Company submitted their Biennial Inspection, Maintenance, Repair and Replacement Plan for the period January 1, 2025 through December 31, 2026 on April 19, 2024 which was deemed approved on April 24, 2024 pursuant to 52 Pa. Code § 57.198(i) by the Commission at Docket No. M-2009-2094773 and M-2023-3039027.

Outages by Cause – Penelec

| <b>Outage by Cause</b>                                  |                             |  |                               |  |
|---|-----------------------------|--|-------------------------------|--|
| <b>3<sup>rd</sup> Quarter 2025<br/>12-Month Rolling</b> | <b>Penelec</b>              |  |                               |  |
| <b>Cause</b>  | <b>Customer<br/>Minutes</b> | <b>Number of<br/>Sustained<br/>Interruptions</b> | <b>Customers<br/>Affected</b> | <b>% Based on<br/>Customer<br/>Minutes</b> |
| Trees Off Row-Tree                                      | 60,816,789                  | 3,120  | 224,354                       | 32.86%                                     |
| Ice   | 36,798,158                  | 486  | 28,222                        | 19.89%                                     |
| Equipment Failure                                       | 21,725,352                  | 2,796  | 175,884                       | 11.74%                                     |
| Line Failure  | 17,947,102                  | 2,204  | 136,844                       | 9.70%                                      |
| Unknown   | 12,508,646                  | 2,696  | 142,453                       | 6.76%                                      |
| Forced Outage   | 10,302,183                  | 1,226  | 56,666                        | 5.57%                                      |
| Vehicle   | 6,262,931                   | 476  | 31,266                        | 3.38%                                      |
| Trees Off Row-Limb                                      | 4,479,030                   | 515  | 22,774                        | 2.42%                                      |
| Animal  | 3,891,792                   | 1,684  | 42,367                        | 2.10%                                      |
| Wind  | 3,557,011                   | 296  | 22,615                        | 1.92%                                      |
| Lightning   | 2,150,867                   | 309  | 15,638                        | 1.16%                                      |
| Bird  | 1,018,162                   | 507  | 15,507                        | 0.55%                                      |
| Trees - Sec/Service                                     | 799,487                     | 724  | 2,242                         | 0.43%                                      |
| Human Error -Non-Company                                | 743,830                     | 111  | 8,449                         | 0.40%                                      |
| Other Electric Utility                                  | 731,813                     | 93   | 2,954                         | 0.40%                                      |
| Human Error - Company                                   | 541,698                     | 86   | 31,992                        | 0.29%                                      |
| Trees On Row  | 304,679                     | 76   | 1,752                         | 0.16%                                      |
| Ug Dig-Up   | 122,937                     | 77   | 565                           | 0.07%                                      |
| Object Contact With Line                                | 85,412                      | 34   | 1,709                         | 0.05%                                      |
| Overload  | 85,061                      | 26   | 2,294                         | 0.05%                                      |
| Fire  | 73,451                      | 24   | 237                           | 0.04%                                      |
| Customer Equipment                                      | 39,935                      | 21   | 2,020                         | 0.02%                                      |
| Switching Error   | 26,082                      | 8  | 1,833                         | 0.01%                                      |
| Vandalism   | 16,594                      | 7  | 83                            | 0.01%                                      |
| Contamination   | 13,262                      | 47   | 109                           | 0.01%                                      |
| Other Utility-Non Elec                                  | 6,211                       | 5  | 91                            | 0.00%                                      |
| Previous Lightning                                      | 2,539                       | 12   | 24                            | 0.00%                                      |
| <b>Total</b>  | <b>185,051,014</b>          | <b>17,666</b>                                    | <b>970,944</b>                | <b>100%</b>                                |

### Proposed Solutions – Penelec

FE PA analyzes its outage data to develop solutions for improving reliability in the Penelec rate district. The following paragraphs identify the top outage causes for the rolling twelve-month period ending September 30, 2025, and the associated actions designed to address these outage causes.

To improve system reliability, FE PA performs cycle-length tree trimming and enhanced tree trimming in select locations. Enhanced tree trimming removes healthy limbs overhanging primary conductors. FE PA's options under the law are strictly limited when it comes to all forms of off-corridor tree management. However, FE PA is legally permitted to identify off-corridor priority trees that are dead, dying, diseased, leaning, or significantly encroaching the corridor and remove those trees when customer consent is obtained or easement rights permit. FE PA is active in pursuing this option, when available, to remove the highest risk trees. Trees identified with a high potential to cause a future outage are targeted for removal to prevent an interruption of electrical service to FE PA's customers. Furthermore, FE PA continues its program to mitigate trees subject to damage from the Emerald Ash Borer. FE PA will also review areas off-cycle to mitigate tree risk in high impact areas.

To reduce the likelihood of outages caused by equipment and line failure, FE PA follows I&M programs that set forth schedules for regular inspections of distribution and substation facilities. These programs are geared towards specific components such as capacitors, poles, circuits, transformers, radio-controlled switches, substations, and reclosers. Equipment identified is repaired or replaced as appropriate. In addition, FE PA has executed LTIIPs which include expenditures and programs designed to adequately maintain and improve the efficiency, safety, adequacy, and reliability of the distribution system.

Outages by Cause – Penn Power

| <b>Outage by Cause</b>                                  |                             |  |                               |  |
|---|-----------------------------|--|-------------------------------|--|
| <b>3<sup>rd</sup> Quarter 2025<br/>12-Month Rolling</b> | <b>Penn Power</b>           |  |                               |  |
| <b>Cause</b>  | <b>Customer<br/>Minutes</b> | <b>Number of<br/>Sustained<br/>Interruptions</b> | <b>Customers<br/>Affected</b> | <b>% Based on<br/>Customer<br/>Minutes</b> |
| Trees off ROW - tree                                    | 11,107,933                  | 847  | 49,932                        | 41.16%                                     |
| Equipment Failure                                       | 3,109,592                   | 425  | 22,436                        | 11.52%                                     |
| Line Failure  | 2,583,223                   | 531  | 14,729                        | 9.57%                                      |
| Unknown   | 2,544,862                   | 374  | 47,331                        | 9.43%                                      |
| Trees Off Row-Limb                                      | 2,279,129                   | 278  | 9,681                         | 8.45%                                      |
| Vehicle   | 1,599,771                   | 113  | 8,828                         | 5.93%                                      |
| Forced Outage   | 1,136,093                   | 242  | 23,271                        | 4.21%                                      |
| Animal  | 631,858                     | 425  | 7,430                         | 2.34%                                      |
| Human Error - Company                                   | 473,740                     | 18   | 6,960                         | 1.76%                                      |
| Bird  | 460,906                     | 371  | 4,104                         | 1.71%                                      |
| Lightning   | 326,684                     | 123  | 1,498                         | 1.21%                                      |
| Trees On Row  | 139,422                     | 34   | 366                           | 0.52%                                      |
| Trees - Sec/Service                                     | 138,040                     | 122  | 347                           | 0.51%                                      |
| Overload  | 131,183                     | 46   | 1,493                         | 0.49%                                      |
| Other Utility-Non Elec                                  | 63,186                      | 8  | 3,685                         | 0.23%                                      |
| Customer Equipment                                      | 55,374                      | 8  | 701                           | 0.23%                                      |
| Human Error -Non-Company                                | 48,573                      | 15   | 1,045                         | 0.18%                                      |
| Object Contact With Line                                | 40,779                      | 12   | 194                           | 0.15%                                      |
| Fire  | 35,115                      | 6  | 138                           | 0.13%                                      |
| Wind  | 34,343                      | 13   | 196                           | 0.13%                                      |
| Ug Dig-Up   | 25,328                      | 16   | 227                           | 0.09%                                      |
| Other Electric Utility                                  | 17,828                      | 5  | 770                           | 0.07%                                      |
| Vandalism   | 3,945                       | 1  | 15                            | 0.01%                                      |
| Previous Lightning                                      | 333                         | 1  | 3                             | 0.00%                                      |
| Ice   | 313                         | 3  | 3                             | 0.00%                                      |
| Contamination   | 0                           | 0  | 0                             | 0.00%                                      |
| Switching Error   | 0                           | 0  | 0                             | 0.00%                                      |
| <b>Total</b>  | <b>26,987,553</b>           | <b>4,037</b>                                     | <b>205,383</b>                | <b>100%</b>                                |

### Proposed Solutions – Penn Power

FE PA analyzes its outage data to develop solutions for improving reliability in the Penn Power rate district. The following paragraphs identify the top outage causes for the rolling twelve-month period ending September 30, 2025, and the associated actions designed to address these outage causes.

To improve system reliability, FE PA performs cycle-length tree trimming and enhanced tree trimming in select locations. Enhanced tree trimming removes healthy limbs overhanging primary conductors. FE PA's options under the law are strictly limited when it comes to all forms of off-corridor tree management. However, FE PA is legally permitted to identify off-corridor priority trees that are dead, dying, diseased, leaning, or significantly encroaching the corridor and remove those trees when customer consent is obtained or easement rights permit. FE PA is active in pursuing this option, when available, to remove the highest risk trees. Trees identified with a high potential to cause a future outage are targeted for removal to prevent an interruption of electrical service to FE PA's customers. Furthermore, FE PA continues its program to mitigate trees subject to damage from the Emerald Ash Borer. FE PA will also review areas off-cycle to mitigate tree risk in high impact areas.

To reduce the likelihood of outages caused by equipment and line failure outages, FE PA follows I&M programs that set forth schedules for regular inspections of distribution facilities. These programs are geared towards specific components such as capacitors, poles, circuits, transformers, and reclosers. Equipment identified is repaired or replaced as appropriate. FE PA has executed LTIPs which include expenditures and programs designed to adequately maintain and improve the efficiency, safety, adequacy, and reliability of the distribution system.

Outages by Cause – West Penn

| <b>Outage by Cause</b>                                  |                         |  |                           |                                    |
|---|-------------------------|--|---------------------------|------------------------------------|
| <b>3<sup>rd</sup> Quarter 2025<br/>12-Month Rolling</b> | <b>West Penn</b>        |  |                           |                                    |
| <b>Cause</b>  | <b>Customer Minutes</b> | <b>Number of Sustained Interruptions</b> | <b>Customers Affected</b> | <b>% Based on Customer Minutes</b> |
| Trees Off Row-Tree                                      | 85,547,301              | 4,254                                    | 265,327                   | 47.03%                             |
| Wind  | 19,570,976              | 389                                      | 46,078                    | 10.76%                             |
| Unknown   | 16,420,952              | 1,479                                    | 131,994                   | 9.03%                              |
| Equipment Failure                                       | 16,266,727              | 2,058                                    | 108,602                   | 8.94%                              |
| Line Failure  | 13,715,571              | 1,983                                    | 67,682                    | 7.54%                              |
| Forced Outage   | 8,038,149               | 1,120                                    | 108,954                   | 4.42%                              |
| Vehicle   | 6,260,842               | 502                                      | 35,493                    | 3.44%                              |
| Trees Off Row-Limb                                      | 6,054,021               | 579                                      | 32,342                    | 3.33%                              |
| Animal  | 4,002,484               | 1,613                                    | 37,671                    | 2.20%                              |
| Lightning   | 1,412,873               | 202                                      | 7,523                     | 0.78%                              |
| Trees On Row  | 1,196,107               | 116                                      | 3,127                     | 0.66%                              |
| Object Contact With Line                                | 673,201                 | 48                                       | 2,047                     | 0.37%                              |
| Bird  | 611,161                 | 425                                      | 4,618                     | 0.34%                              |
| Human Error -Non-Company                                | 574,789                 | 77                                       | 6,369                     | 0.32%                              |
| Trees - Sec/Service                                     | 494,802                 | 368                                      | 896                       | 0.27%                              |
| Other Electric Utility                                  | 396,860                 | 15                                       | 1,430                     | 0.22%                              |
| Human Error - Company                                   | 294,475                 | 34                                       | 7,491                     | 0.16%                              |
| Ug Dig-Up   | 98,196                  | 50                                       | 1,200                     | 0.05%                              |
| Overload  | 82,130                  | 16                                       | 396                       | 0.05%                              |
| Fire  | 73,760                  | 19                                       | 320                       | 0.04%                              |
| Customer Equipment                                      | 42,991                  | 19                                       | 147                       | 0.02%                              |
| Contamination   | 30,822                  | 3  | 113                       | 0.02%                              |
| Ice   | 20,752                  | 8  | 118                       | 0.01%                              |
| Other Utility-Non Elec                                  | 17,611                  | 4  | 107                       | 0.01%                              |
| Vandalism   | 1,203                   | 3  | 4                         | 0.00%                              |
| Previous Lightning                                      | 534                     | 3  | 7                         | 0.00%                              |
| Switching Error   | 0                       | 0  | 0                         | 0.00%                              |
| <b>Total</b>  | <b>181,899,290</b>      | <b>15,387</b>                            | <b>870,056</b>            | <b>100%</b>                        |

### Proposed Solutions – West Penn

FE PA analyzes its outage data to develop solutions for improving reliability in the West Penn rate district. The following paragraphs identify the top outage causes for the rolling twelve-month period ending September 30, 2025, and the associated actions designed to address these outage causes.

To improve system reliability, FE PA performs cycle-length tree trimming and enhanced tree trimming in select locations. Enhanced tree trimming removes healthy limbs overhanging primary conductors. FE PA's options under the law are strictly limited when it comes to all forms of off-corridor tree management. However, FE PA is legally permitted to identify off-corridor priority trees that are dead, dying, diseased, leaning, or significantly encroaching the corridor and remove those trees when customer consent is obtained or easement rights permit. FE PA is active in pursuing this option, when available, to remove the highest risk trees. Trees identified with a high potential to cause a future outage are targeted for removal to prevent an interruption of electrical service to FE PA's customers. Furthermore, FE PA continues its program to mitigate trees subject to damage from the Emerald Ash Borer. FE PA will also review areas off-cycle to mitigate tree risk in high impact areas.

To reduce the likelihood of equipment and line failures, FE PA follows I&M programs that set forth schedules for regular inspections of distribution and substation facilities. These programs are geared towards specific components such as capacitors, poles, circuits, transformers, substations, and reclosers. Equipment identified is repaired or replaced as appropriate. FE PA has executed LTIPs which include expenditures and programs designed to adequately maintain and improve the efficiency, safety, adequacy, and reliability of the distribution system.

*Section 57.195(e)(6): Quarterly and year-to-date information on progress toward meeting transmission and distribution inspection and maintenance goals/objectives (for first, second, and third quarter reports only).*

| Inspection and Maintenance |                                | Met-Ed  |           |       | Penelec |           |       | Penn Power                                  |           |       | West Penn                                  |           |       |
|----------------------------|--------------------------------|---------|-----------|-------|---------|-----------|-------|---|-----------|-------|--|-----------|-------|
| 2025                       |                                | Planned | Completed |       | Planned | Completed |       | Planned                                     | Completed |       | Planned                                    | Completed |       |
|                            |                                | Annual  | 3Q        | YTD   | Annual  | 3Q        | YTD   | Annual                                      | 3Q        | YTD   | Annual                                     | 3Q        | YTD   |
| Forestry                   | Transmission (Miles)           | 288     | 235       | 81.6% | 491     | 464       | 94.5% | 56  | 51        | 90.1% | 180  | 138       | 76.4% |
|                            | Distribution (Miles)           | 2,998   | 2,294     | 76.5% | 3,755   | 2,791     | 74%   | 1,424                                       | 1,106     | 77.7% | 4,358                                      | 3,185     | 73%   |
| Transmission               | Aerial Patrols                 | 2       | 2         | 100%  | 2       | 1         | 50%   | 2   | 1         | 50%   | 2  | 1         | 50%   |
|                            | Groundline                     | 1,129   | 1,192     | 100%  | 3,572   | 3,118     | 87.3% | 345   | 444       | 100%  | 0  | 0         | -     |
| Substation                 | Substation Inspections Class A | 424     | 424       | 100%  | 782     | 782       | 100%  | 154   | 154       | 100%  | 932  | 932       | 100%  |
|                            | Substation Inspections Class B | 424     | 214       | 50.5% | 782     | 393       | 50.3% | 154   | 77        | 50%   | 932  | 466       | 50.5% |
|                            | Substation Inspections Class C | 1,696   | 1,482     | 87.4% | 3,128   | 2,347     | 75%   | 616   | 462       | 75%   | 3,728                                      | 2,802     | 75.2% |
|                            | Transformers                   | 145     | 109       | 75.2% | 437     | 312       | 71.4% | 14  | 10        | 71.4% | 342  | 304       | 88.9% |
|                            | Breakers                       | 75      | 37        | 49.3% | 418     | 244       | 58.4% | 7   | 3         | 42.9% | 372  | 331       | 89%   |
|                            | Relay Schemes                  | 179     | 111       | 62%   | 141     | 73        | 51.8% | 18  | 18        | 100%  | 172  | 118       | 68.6% |
| Distribution               | Capacitors                     | 4,782   | 4,820     | 100%  | 8,529   | 8,420     | 98.7% | 958   | 942       | 98.3% | 3,739                                      | 3,687     | 98.6% |
|                            | Poles                          | 37,000  | 33,696    | 91.1% | 40,000  | 29,857    | 74.6% | 11,092                                      | 11,092    | 100%  | 44,800                                     | 31,135    | 69.5% |
|                            | Reclosers                      | 3,378   | 1,585     | 46.9% | 3,917   | 3,788     | 96.7% | 1,257                                       | 1,251     | 99.5% | 4,074                                      | 3,689     | 90.5% |
|                            | Radio-Controlled Switches      | 1,996   | 1,835     | 91.9% | 2,620   | 1,923     | 73.4% | Penn Power has no radio-controlled switches |           |       | West Penn has no radio-controlled switches |           |       |

Submitted Pursuant to 52 Pa. Code § 57.195(d) and (e)

*Section 57.195(e)(7): Quarterly and year-to-date information on budgeted versus actual transmission and distribution operation and maintenance expenditures in total and detailed by the EDC's own functional account code as available. (For first, second, and third quarter reports only) Budgeted vs. Actual T&D Operation & Maintenance Expenditures<sup>5</sup>*

This portion of the report is confidential.

---

<sup>5</sup> Budgets are subject to change.

Submitted Pursuant to 52 Pa. Code § 57.195(d) and (e)

*Budgeted vs. Actual T&D Operation & Maintenance Expenditures<sup>6</sup>*  
*Section 57.195(e)(8): Quarterly and year-to-date information on budgeted versus actual transmission and distribution capital expenditures in total and detailed by the EDC's own functional account code or FERC account code as available. (For first, second, and third quarter reports only).*

This portion of the report is confidential.

---

<sup>6</sup> Budgets are subject to change.

Submitted Pursuant to 52 Pa. Code § 57.195(d) and (e)

*Section 57.195(e)(9): Dedicated staffing levels for transmission and distribution operation and maintenance at the end of the quarter, in total and by specific category (for example, linemen, technician, and electrician).<sup>7</sup>*

*Staffing Levels*

| Met-Ed 2025  |                     |                             |            |            |    |                        |                     |  |                       |                      |                     |                                   |
|--------------|---------------------|-----------------------------|------------|------------|----|------------------------|---------------------|--|-----------------------|----------------------|---------------------|-----------------------------------|
|              |                     | Staffing Level <sup>8</sup> |            |            |    | Staff Added in Quarter |                     | Staff Movement Quarter                 | Staff lost in Quarter |                      |                     | Plan to Hire in 2025 <sup>9</sup> |
| Department   | Position            | 1Q                          | 2Q         | 3Q         | 4Q | New Hire               | Other <sup>10</sup> | Movement within Position <sup>11</sup> | Retirement            | Voluntary Separation | Other <sup>12</sup> |                                   |
| Distribution | Line Leader         | 43                          | 43         | 38         |    |                        | 3                   |  | 1                     | 2                    | 5                   |                                   |
|              | Line Troubleshooter | 35                          | 36         | 35         |    |                        | 2                   |  | 3                     |                      |                     |                                   |
|              | Lineman             | 131                         | 122        | 106        |    |                        |                     | 18                                     | 1                     | 11                   | 4                   | 43                                |
| Substation   | Substation Leader   | 15                          | 14         | 14         |    |                        | 1                   |  | 1                     |                      |                     |                                   |
|              | Substation Employee | 63                          | 63         | 61         |    |                        |                     | 14                                     |                       |                      | 2                   |                                   |
| Transmission | Line Leader         | 3                           | 3          | 2          |    |                        | 1                   |  | 1                     |                      | 1                   |                                   |
|              | Lineman             | 10                          | 9          | 9          |    |                        | 2                   |  |                       |                      | 2                   |                                   |
| <b>Total</b> |                     | <b>300</b>                  | <b>290</b> | <b>265</b> |    |                        | <b>9</b>            | <b>32</b>                              | <b>7</b>              | <b>13</b>            | <b>14</b>           | <b>43</b>                         |

<sup>7</sup> As ordered on March 30, 2015 at Docket Nos. D-2014-2365991, D-2014-2365992, D-2014-2365993, and D-2014-2365994, *Implementation Plan of the Focused Management Audit of Metropolitan Edison Company, Pennsylvania Electric Company, Pennsylvania Power Company, and West Penn Power Company* (Appendix A) (5), FE PA is directed to provide additional detail as described below in the staff reporting section in the Quarterly Reliability Reports. Specifically, for each staff member added, FE PA provides information on whether they were a new hire, whether they were already at the journeyman level, or whether they had obtained some other experienced level of training. For each staff member lost, FE PA provides the reason for the loss (retirement, voluntary separation, etc.). Additionally, FE PA also discloses the number of staff in each category that each one is planning to hire in the next calendar year.

<sup>8</sup> Staffing level includes active employees with an assignment status of active - payroll eligible, leave of absence - payroll eligible, or military leave - payroll eligible.

<sup>9</sup> Hiring plan to be provided annually in the 4Q report.

<sup>10</sup> Includes transfers and promotions.

<sup>11</sup> Includes transfers, promotions, and progression within a position.

<sup>12</sup> Includes transfers, involuntary separations, promotions, and assignment changes for extended disability and long-term disability.

| Penelec 2025 |                     |                              |            |            |    |                        |                     |  |                       |                      |                     |                                    |
|--------------|---------------------|------------------------------|------------|------------|----|------------------------|---------------------|--|-----------------------|----------------------|---------------------|------------------------------------|
|              |                     | Staffing Level <sup>13</sup> |            |            |    | Staff Added in Quarter |                     | Staff Movement Quarter                 | Staff Lost in Quarter |                      |                     | Plan to Hire in 2025 <sup>14</sup> |
| Department   | Position            | 1Q                           | 2Q         | 3Q         | 4Q | New Hire               | Other <sup>15</sup> | Movement within Position <sup>16</sup> | Retirement            | Voluntary Separation | Other <sup>17</sup> |                                    |
| Distribution | Line Leader         | 60                           | 60         | 60         |    |                        | 2                   |  | 1                     |                      | 1                   |                                    |
|              | Line Troubleshooter | 76                           | 78         | 80         |    |                        | 3                   |  |                       |                      | 1                   |                                    |
|              | Lineman             | 145                          | 141        | 138        |    |                        | 2                   | 1                                      |                       |                      | 5                   | 17                                 |
| Substation   | Substation Leader   | 32                           | 31         | 30         |    |                        |                     |  |                       |                      | 1                   |                                    |
|              | Substation Employee | 56                           | 53         | 53         |    |                        | 1                   | 1                                      | 1                     |                      |                     |                                    |
| Transmission | Line Leader         | 8                            | 8          | 7          |    |                        |                     |  | 1                     |                      |                     |                                    |
|              | Lineman             | 18                           | 17         | 17         |    |                        |                     |  |                       |                      |                     |                                    |
|              | <b>Total</b>        | <b>395</b>                   | <b>388</b> | <b>385</b> |    |                        | <b>8</b>            | <b>2</b>                               | <b>3</b>              |                      | <b>8</b>            | <b>17</b>                          |

<sup>13</sup> Staffing level includes active employees with an assignment status of active - payroll eligible, leave of absence - payroll eligible, or military leave - payroll eligible.

<sup>14</sup> Hiring plan to be provided annually in the 4Q report.

<sup>15</sup> Includes transfers, promotions, and assignment changes for extended disability or long-term disability.

<sup>16</sup> Includes transfers, promotions, and progression within a position.

<sup>17</sup> Includes transfers, involuntary separations, and promotions.

| Penn Power 2025 |                     |                              |            |            |    |                        |                     |  |                       |                      |                     |                                    |
|-----------------|---------------------|------------------------------|------------|------------|----|------------------------|---------------------|--|-----------------------|----------------------|---------------------|------------------------------------|
|                 |                     | Staffing Level <sup>18</sup> |            |            |    | Staff Added in Quarter |                     | Staff Movement Quarter                 | Staff Lost in Quarter |                      |                     | Plan to Hire in 2025 <sup>19</sup> |
| Department      | Position            | 1Q                           | 2Q         | 3Q         | 4Q | New Hire               | Other <sup>20</sup> | Movement within Position <sup>21</sup> | Retirement            | Voluntary Separation | Other <sup>22</sup> |                                    |
| Distribution    | Line Leader         | 24                           | 23         | 23         |    |                        |                     |  |                       |                      |                     |                                    |
|                 | Line Troubleshooter | 15                           | 15         | 15         |    |                        |                     |  |                       |                      |                     |                                    |
|                 | Lineman             | 47                           | 48         | 48         |    |                        |                     |  |                       |                      |                     | 2                                  |
| Substation      | Substation Leader   | 5                            | 5          | 5          |    |                        |                     |  |                       |                      |                     |                                    |
|                 | Substation Employee | 19                           | 19         | 19         |    |                        |                     |  |                       |                      |                     |                                    |
| Transmission    | Line Leader         | 1                            | 1          | 1          |    |                        |                     |  |                       |                      |                     |                                    |
|                 | Lineman             | 6                            | 6          | 6          |    |                        |                     |  |                       |                      |                     |                                    |
| <b>Total</b>    |                     | <b>117</b>                   | <b>117</b> | <b>117</b> |    |                        |                     |  |                       |                      |                     | <b>2</b>                           |

<sup>18</sup> Staffing level includes active employees with an assignment status of active - payroll eligible, leave of absence - payroll eligible, or military leave - payroll eligible.

<sup>19</sup> Hiring plan to be provided annually in the 4Q report.

<sup>20</sup> Includes transfers, promotions, and assignment changes for extended disability or long-term disability.

<sup>21</sup> Includes transfers, promotions, and progression within a position.

<sup>22</sup> Includes transfers, involuntary separations, and assignments changes for extended disability and long-term disability.

| West Penn 2025 |                     |                              |            |            |          |                        |                     |  |                       |                      |                     |                                    |
|----------------|---------------------|------------------------------|------------|------------|----------|------------------------|---------------------|--|-----------------------|----------------------|---------------------|------------------------------------|
|                |                     | Staffing Level <sup>23</sup> |            |            |          | Staff Added in Quarter |                     | Staff Movement Quarter                 | Staff Lost in Quarter |                      |                     |                                    |
| Department     | Position            | 1Q                           | 2Q         | 3Q         | 4Q       | New Hire               | Other <sup>24</sup> | Movement within Position <sup>25</sup> | Retirement            | Voluntary Separation | Other <sup>26</sup> | Plan to Hire in 2025 <sup>27</sup> |
| Distribution   | Line Leader         | 70                           | 69         | 72         |          |                        | 7                   |  | 1                     |                      | 3                   |                                    |
|                | Line Troubleshooter | 49                           | 54         | 53         |          |                        | 6                   |  | 1                     |                      | 6                   |                                    |
|                | Lineman             | 161                          | 156        | 152        |          |                        | 4                   | 1                                      |                       |                      | 8                   | 5                                  |
| Substation     | Substation Leader   | 25                           | 24         | 21         |          |                        |                     |  | 3                     |                      |                     |                                    |
|                | Substation Employee | 81                           | 79         | 79         |          |                        |                     |  |                       |                      |                     |                                    |
| Transmission   | Line Leader         | 2                            | 2          | 2          |          |                        |                     |  |                       |                      |                     |                                    |
|                | Lineman             | 11                           | 11         | 9          |          |                        |                     |  |                       |                      | 2                   |                                    |
| <b>Total</b>   |                     | <b>399</b>                   | <b>395</b> | <b>388</b> | <b>0</b> |                        | <b>17</b>           | <b>1</b>                               | <b>5</b>              | <b>0</b>             | <b>19</b>           | <b>5</b>                           |

<sup>23</sup> Staffing level includes active employees with an assignment status of active - payroll eligible, leave of absence - payroll eligible, or military leave - payroll eligible.

<sup>24</sup> Includes transfers, promotions, and assignment changes for extended disability or long-term disability.

<sup>25</sup> Includes transfers, promotions, and progression within a position.

<sup>26</sup> Includes transfers, promotions, involuntary separations, and assignment changes for extended disability and long-term disability.

<sup>27</sup> Hiring plan to be provided annually in the 4Q report.

Submitted Pursuant to 52 Pa. Code § 57.195(d) and (e)

*Section 57.195(e)(10): Quarterly and year-to-date information on contractor hours and dollars for transmission and distribution operation and maintenance.*

*Contractor Expenditures*

Certain Contractor expenses are billed on a lump-sum basis. As a result, hourly information is not available.

This portion of the report is confidential.

*Section 57.195(e)(11): Monthly call-out acceptance rate for transmission and distribution maintenance workers presented in terms of both the percentage of accepted calls-out and the amount of time it takes the EDC to obtain the necessary personnel. A brief description of the EDC's call-out procedure should be included when appropriate.*

*Call-out Acceptance Rate*

Call-out percentage is defined as the number of workers accepting to total call outs.

This portion of the report is confidential.

*Call-out Response*

This portion of the report is confidential.

**Call-Out Procedure:**

When an event occurs, FE PA dispatches a troubleman to find and assess the cause of the outage. If the troubleman is unable to repair the damage and a crew is required, the troubleman will inform the Distribution Control Center (“DCC”). The on-duty DCC person or Customer Operations Center person, or both, will then initiate the call-out process until desired staffing levels required to complete the restoration have been achieved.

The number of unique workers called for an outage event is recorded and represents the total calls, or opportunities, for an outage event. The number of unique workers who accept the opportunity is recorded and represents the workers accepting. The elapsed time is calculated by taking the date and time of the first employee called for an event minus the date and time of the last accepting employee for that event. The call-out results from all outages experienced during a particular month are added together to derive a total value for each field.

ATTACHMENT A

Worst Performing Circuits - Reliability Indices

| Met-Ed       |                      |         |             |                   |         |          |                  |                    |              |          |        |         |       |
|--------------|----------------------|---------|-------------|-------------------|---------|----------|------------------|--------------------|--------------|----------|--------|---------|-------|
| Circuit Rank | Substation           | Circuit | District    | Average Customers | Outages | Lockouts | Customer Minutes | Customers Affected | SAIDI Impact | SAIDI    | SAIFI  | CAIDI   | MAIFI |
| 1            | Walker Sub           | 00865-3 | Stroudsburg | 2,962             | 84      | 0        | 5,703,805        | 5,801              | 9.76         | 1925.660 | 1.958  | 983.245 | 0.150 |
| 2            | Birdsboro            | 00757-1 | Reading     | 2,043             | 77      | 2        | 3,046,607        | 5,835              | 5.21         | 1491.242 | 2.856  | 522.126 | 1.790 |
| 3            | Bernville Sub        | 00787-1 | Hamburg     | 1,901             | 92      | 0        | 2,593,149        | 4,942              | 4.44         | 1364.097 | 2.600  | 524.717 | 0.000 |
| 4            | Painted Sky          | 00650-1 | Reading     | 1,780             | 23      | 0        | 2,256,942        | 4,249              | 3.86         | 1267.945 | 2.387  | 531.170 | 0.000 |
| 5            | No Bangor            | 00813-3 | Easton      | 1,373             | 74      | 0        | 1,979,164        | 10,033             | 3.39         | 1441.489 | 7.307  | 197.265 | 1.083 |
| 6            | Ringing Rocks Sub    | 00708-1 | Boyertown   | 2,453             | 89      | 1        | 1,732,527        | 7,529              | 2.96         | 706.289  | 3.069  | 230.114 | 0.000 |
| 7            | Ottsville Substation | 00660-3 | Easton      | 890               | 80      | 1        | 1,626,733        | 4,605              | 2.78         | 1827.790 | 5.174  | 353.254 | 0.000 |
| 8            | W Boyertown Sub      | 00484-1 | Boyertown   | 928               | 28      | 2        | 1,587,705        | 2,859              | 2.72         | 1710.889 | 3.081  | 555.336 | 0.706 |
| 9            | Lynnville Sub        | 00737-1 | Hamburg     | 1,092             | 95      | 2        | 1,454,675        | 8,548              | 2.49         | 1332.120 | 7.828  | 170.177 | 5.895 |
| 10           | Barto Sub            | 00705-1 | Boyertown   | 659               | 62      | 1        | 1,389,877        | 3,560              | 2.38         | 2109.070 | 5.402  | 390.415 | 0.000 |
| 11           | Barto Sub            | 00706-1 | Boyertown   | 3,031             | 185     | 0        | 1,388,968        | 7,058              | 2.38         | 458.254  | 2.329  | 196.793 | 0.051 |
| 12           | Lickdale Substation  | 00625-2 | Lebanon     | 1,022             | 66      | 1        | 1,273,613        | 3,474              | 2.18         | 1246.197 | 3.399  | 366.613 | 0.413 |
| 13           | W Boyertown Sub      | 00715-1 | Boyertown   | 1,718             | 67      | 1        | 1,268,539        | 4,941              | 2.17         | 738.381  | 2.876  | 256.737 | 0.027 |
| 14           | Birdsboro            | 00759-1 | Reading     | 928               | 74      | 4        | 1,257,180        | 13,471             | 2.15         | 1354.720 | 14.516 | 93.325  | 5.343 |
| 15           | No Bangor            | 00838-3 | Easton      | 1,714             | 53      | 3        | 1,244,207        | 5,088              | 2.13         | 725.908  | 2.968  | 244.538 | 0.000 |
| 16           | No Bangor            | 00826-3 | Easton      | 3,331             | 118     | 0        | 1,232,761        | 6,843              | 2.11         | 370.087  | 2.054  | 180.149 | 0.131 |
| 17           | Fox Hill Subst       | 00816-3 | Stroudsburg | 3,335             | 44      | 1        | 1,186,846        | 9,646              | 2.03         | 355.876  | 2.892  | 123.040 | 0.980 |
| 18           | Schuylkill Ave       | 00157-1 | Reading     | 1,634             | 12      | 2        | 1,180,403        | 3,110              | 2.02         | 722.401  | 1.903  | 379.551 | 0.000 |
| 19           | Bern Church Sub      | 00789-1 | Reading     | 1,472             | 86      | 0        | 1,180,051        | 4,013              | 2.02         | 801.665  | 2.726  | 294.057 | 0.000 |
| 20           | Huffs Church         | 00600-1 | Boyertown   | 1,517             | 127     | 1        | 1,139,646        | 3,649              | 1.95         | 751.250  | 2.405  | 312.317 | 0.776 |
| 21           | Muhlenberg           | 00511-1 | Reading     | 843               | 5       | 1        | 1,120,416        | 1,689              | 1.92         | 1329.082 | 2.004  | 663.361 | 0.000 |
| 22           | Glendon              | 00819-3 | Easton      | 1,326             | 23      | 5        | 1,072,226        | 5,798              | 1.83         | 808.617  | 4.373  | 184.930 | 0.000 |
| 23           | Pine Lane Sub        | 00712-1 | Boyertown   | 2,019             | 13      | 0        | 1,056,146        | 7,710              | 1.81         | 523.104  | 3.819  | 136.984 | 1.462 |
| 24           | Bushkill Falls       | 00698-3 | Stroudsburg | 1,787             | 22      | 2        | 1,037,504        | 5,629              | 1.78         | 580.584  | 3.150  | 184.314 | 3.947 |
| 25           | Birdsboro            | 00760-1 | Reading     | 2,193             | 43      | 1        | 1,000,115        | 5,328              | 1.71         | 456.049  | 2.430  | 187.709 | 0.311 |

| Met-Ed       |                      |         |           |                   |         |          |                  |                    |              |          |       |         |       |
|--------------|----------------------|---------|-----------|-------------------|---------|----------|------------------|--------------------|--------------|----------|-------|---------|-------|
| Circuit Rank | Substation           | Circuit | District  | Average Customers | Outages | Lockouts | Customer Minutes | Customers Affected | SAIDI Impact | SAIDI    | SAIFI | CAIDI   | MAIFI |
| 26           | Birdsboro            | 00756-1 | Reading   | 1,534             | 109     | 1        | 964,902          | 4,821              | 1.65         | 629.010  | 3.143 | 200.146 | 2.018 |
| 27           | Pleasantville        | 00142-1 | Boyertown | 812               | 76      | 0        | 964,689          | 2,270              | 1.65         | 1188.041 | 2.796 | 424.973 | 0.979 |
| 28           | Pine Lane Sub        | 00720-1 | Boyertown | 1,110             | 55      | 0        | 956,621          | 3,200              | 1.64         | 861.821  | 2.883 | 298.944 | 1.763 |
| 29           | Bath Sub             | 00873-3 | Easton    | 2,070             | 69      | 1        | 953,374          | 9,434              | 1.63         | 460.567  | 4.557 | 101.057 | 2.361 |
| 30           | S Nazareth           | 00809-3 | Easton    | 3,215             | 45      | 2        | 937,016          | 7,014              | 1.60         | 291.451  | 2.182 | 133.592 | 0.814 |
| 31           | Leesport Sub         | 00811-1 | Hamburg   | 1,576             | 61      | 0        | 897,965          | 3,188              | 1.54         | 569.775  | 2.023 | 281.670 | 0.618 |
| 32           | Lorane               | 00562-1 | Reading   | 1,218             | 28      | 2        | 887,479          | 3,630              | 1.52         | 728.636  | 2.980 | 244.485 | 0.989 |
| 33           | North Cornwall Sub   | 00611-2 | Lebanon   | 985               | 36      | 1        | 867,761          | 2,884              | 1.48         | 880.976  | 2.928 | 300.888 | 0.230 |
| 34           | Bernville Sub        | 00786-1 | Hamburg   | 1,594             | 105     | 2        | 858,852          | 4,103              | 1.47         | 538.803  | 2.574 | 209.323 | 1.061 |
| 35           | Friedensburg Sub     | 00770-1 | Reading   | 454               | 26      | 2        | 827,924          | 1,881              | 1.42         | 1823.621 | 4.143 | 440.151 | 1.320 |
| 36           | Ferndale Sub         | 00871-3 | Easton    | 497               | 30      | 2        | 824,851          | 1,346              | 1.41         | 1659.660 | 2.708 | 612.816 | 0.000 |
| 37           | Lorane               | 00560-1 | Reading   | 1,150             | 26      | 1        | 783,318          | 2,982              | 1.34         | 681.146  | 2.593 | 262.682 | 0.353 |
| 38           | Newberry Sub         | 00576-4 | York      | 1,760             | 88      | 0        | 779,610          | 4,322              | 1.33         | 442.960  | 2.456 | 180.382 | 1.079 |
| 39           | Lyons Sub            | 00729-1 | Easton    | 1,366             | 80      | 1        | 770,726          | 3,382              | 1.32         | 564.221  | 2.476 | 227.891 | 0.553 |
| 40           | Ottsville Substation | 00661-3 | Reading   | 616               | 69      | 5        | 765,900          | 1,890              | 1.31         | 1243.344 | 3.068 | 405.238 | 2.734 |

| Penelec      |                      |          |            |                   |         |          |                  |                    |              |           |        |          |        |
|--------------|----------------------|----------|------------|-------------------|---------|----------|------------------|--------------------|--------------|-----------|--------|----------|--------|
| Circuit Rank | Substation           | Circuit  | District   | Average Customers | Outages | Lockouts | Customer Minutes | Customers Affected | SAIDI Impact | SAIDI     | SAIFI  | CAIDI    | MAIFI  |
| 1            | Thompson             | 00436-65 | Montrose   | 1,398             | 106     | 1        | 11,966,069       | 7,590              | 20.23        | 8559.420  | 5.429  | 1576.557 | 0.676  |
| 2            | Lake Como            | 00787-65 | Montrose   | 957               | 78      | 2        | 6,009,560        | 3,676              | 10.16        | 6279.582  | 3.841  | 1634.810 | 0.106  |
| 3            | Thompson             | 00446-65 | Montrose   | 1,300             | 72      | 0        | 4,767,198        | 3,225              | 8.06         | 3667.075  | 2.481  | 1478.201 | 1.323  |
| 4            | Shawville            | 00151-21 | Clearfield | 2,259             | 49      | 0        | 4,110,452        | 7,029              | 6.95         | 1819.589  | 3.112  | 584.785  | 0.295  |
| 5            | Tiffany              | 00435-65 | Montrose   | 1,304             | 46      | 0        | 3,695,349        | 4,259              | 6.25         | 2833.857  | 3.266  | 867.656  | 3.716  |
| 6            | Tiffany              | 00440-65 | Montrose   | 1,247             | 13      | 1        | 3,081,039        | 3,308              | 5.21         | 2470.761  | 2.653  | 931.390  | 0.013  |
| 7            | Lake Como            | 00788-65 | Montrose   | 671               | 55      | 0        | 2,997,122        | 2,276              | 5.07         | 4466.650  | 3.392  | 1316.837 | 0.000  |
| 8            | Thompson             | 00442-65 | Montrose   | 680               | 49      | 2        | 2,687,194        | 3,375              | 4.54         | 3951.756  | 4.963  | 796.206  | 0.524  |
| 9            | Lenox                | 00755-65 | Montrose   | 716               | 38      | 2        | 2,584,316        | 3,413              | 4.37         | 3609.380  | 4.767  | 757.198  | 0.000  |
| 10           | Tunkhannock          | 00533-65 | Montrose   | 1,284             | 66      | 0        | 2,409,639        | 6,855              | 4.07         | 1876.666  | 5.339  | 351.516  | 4.878  |
| 11           | Falls                | 00297-65 | Montrose   | 842               | 43      | 0        | 1,935,272        | 3,084              | 3.27         | 2298.423  | 3.663  | 627.520  | 5.770  |
| 12           | Brooklyn             | 00749-65 | Montrose   | 536               | 35      | 0        | 1,782,869        | 1,325              | 3.01         | 3326.248  | 2.472  | 1345.562 | 0.006  |
| 13           | Northeast            | 00591-31 | Erie       | 643               | 15      | 1        | 1,631,948        | 4,243              | 2.76         | 2538.022  | 6.599  | 384.621  | 1.918  |
| 14           | N Meshoppen Tran     | 00534-65 | Montrose   | 898               | 88      | 0        | 1,495,118        | 4,494              | 2.53         | 1664.942  | 5.004  | 332.692  | 1.802  |
| 15           | Grover               | 00527-63 | Towanda    | 1,099             | 76      | 0        | 1,387,676        | 4,871              | 2.35         | 1262.672  | 4.432  | 284.885  | 1.240  |
| 16           | Pennmar              | 00001-12 | Somerset   | 399               | 17      | 0        | 1,365,200        | 1,856              | 2.31         | 3421.554  | 4.652  | 735.560  | 0.000  |
| 17           | Lake Como            | 00786-65 | Montrose   | 334               | 24      | 1        | 1,247,370        | 1,193              | 2.11         | 3734.641  | 3.572  | 1045.574 | 0.964  |
| 18           | East Sayre           | 00518-61 | Towanda    | 982               | 33      | 0        | 1,143,206        | 1,671              | 1.93         | 1164.161  | 1.702  | 684.145  | 0.001  |
| 19           | Dushore              | 00641-62 | Towanda    | 94                | 42      | 1        | 993,844          | 1,746              | 1.68         | 10572.809 | 18.574 | 569.212  | 16.330 |
| 20           | Springboro           | 00237-52 | Meadville  | 2,808             | 85      | 0        | 932,619          | 6,314              | 1.58         | 332.129   | 2.249  | 147.707  | 0.272  |
| 21           | Laurel Lake Sub Tran | 00449-65 | Montrose   | 538               | 40      | 0        | 923,132          | 1,297              | 1.56         | 1715.859  | 2.411  | 711.744  | 0.052  |
| 22           | Boyer                | 00584-31 | Erie       | 1,717             | 28      | 0        | 848,684          | 11,942             | 1.43         | 494.283   | 6.955  | 71.067   | 0.000  |
| 23           | Laurel Lake Sub Tran | 00448-65 | Montrose   | 209               | 9       | 2        | 832,514          | 453                | 1.41         | 3983.321  | 2.167  | 1837.779 | 0.000  |
| 24           | N Meshoppen Tran     | 00437-65 | Montrose   | 518               | 44      | 0        | 768,851          | 1,197              | 1.30         | 1484.268  | 2.311  | 642.315  | 1.678  |
| 25           | Two Mile             | 00127-42 | Bradford   | 1,318             | 25      | 0        | 763,156          | 2,764              | 1.29         | 579.026   | 2.097  | 276.106  | 0.002  |
| 26           | Pennmar              | 00002-12 | Somerset   | 896               | 31      | 1        | 738,891          | 3,244              | 1.25         | 824.655   | 3.621  | 227.772  | 0.000  |

| Penelec      |                   |          |             |                   |         |          |                  |                    |              |          |        |          |       |
|--------------|-------------------|----------|-------------|-------------------|---------|----------|------------------|--------------------|--------------|----------|--------|----------|-------|
| Circuit Rank | Substation        | Circuit  | District    | Average Customers | Outages | Lockouts | Customer Minutes | Customers Affected | SAIDI Impact | SAIDI    | SAIFI  | CAIDI    | MAIFI |
| 27           | Green Garden      | 00536-31 | Erie        | 870               | 18      | 0        | 705,594          | 2,123              | 1.19         | 811.028  | 2.440  | 332.357  | 0.000 |
| 28           | Dubois Central    | 00119-23 | Dubois      | 1,379             | 45      | 0        | 682,897          | 4,079              | 1.15         | 495.212  | 2.958  | 167.418  | 1.274 |
| 29           | Punxsutawney      | 00830-23 | Dubois      | 923               | 17      | 3        | 676,182          | 2,901              | 1.14         | 732.592  | 3.143  | 233.086  | 0.052 |
| 30           | Birmingham        | 00168-22 | Philipsburg | 1,124             | 53      | 1        | 669,046          | 2,586              | 1.13         | 595.237  | 2.301  | 258.718  | 0.225 |
| 31           | Hooversville      | 00019-12 | Somerset    | 1,651             | 61      | 0        | 659,537          | 4,385              | 1.12         | 399.477  | 2.656  | 150.408  | 1.572 |
| 32           | Philipsburg       | 00162-22 | Philipsburg | 2,797             | 58      | 1        | 646,415          | 6,312              | 1.09         | 231.110  | 2.257  | 102.410  | 1.648 |
| 33           | Bradford South    | 00106-42 | Bradford    | 1,217             | 23      | 2        | 632,473          | 3,777              | 1.07         | 519.698  | 3.104  | 167.454  | 0.000 |
| 34           | East Hickory      | 00201-41 | Warren      | 333               | 20      | 8        | 616,371          | 3,390              | 1.04         | 1850.964 | 10.180 | 181.820  | 2.201 |
| 35           | N Meshoppen Tran  | 00531-65 | Montrose    | 444               | 52      | 2        | 606,474          | 1,331              | 1.03         | 1365.932 | 2.998  | 455.653  | 2.025 |
| 36           | Piney             | 00523-51 | Oil City    | 1,547             | 49      | 1        | 577,081          | 4,610              | 0.98         | 373.032  | 2.980  | 125.180  | 0.037 |
| 37           | Tunkhannock       | 00695-65 | Montrose    | 554               | 22      | 1        | 576,780          | 1,460              | 0.98         | 1041.119 | 2.635  | 395.055  | 0.977 |
| 38           | Green Garden      | 00224-31 | Erie        | 1,956             | 35      | 1        | 565,169          | 7,573              | 0.96         | 288.941  | 3.872  | 74.629   | 2.076 |
| 39           | Millcreek         | 00052-11 | Johnstown   | 1,041             | 32      | 1        | 558,099          | 1,762              | 0.94         | 536.118  | 1.693  | 316.742  | 0.921 |
| 40           | Clearfield        | 00148-21 | Clearfield  | 1,733             | 53      | 3        | 554,486          | 6,551              | 0.94         | 319.957  | 3.780  | 84.641   | 1.502 |
| 41           | North Orwell      | 00300-61 | Towanda     | 397               | 28      | 2        | 551,992          | 1,127              | 0.93         | 1390.408 | 2.839  | 489.789  | 0.000 |
| 42           | Utica Junction    | 00318-51 | Oil City    | 860               | 46      | 1        | 538,843          | 3,126              | 0.91         | 626.562  | 3.635  | 172.375  | 0.007 |
| 43           | Tionesta          | 00344-51 | Oil City    | 516               | 23      | 1        | 538,704          | 2,571              | 0.91         | 1044.000 | 4.983  | 209.531  | 2.366 |
| 44           | Sheridan Street   | 00226-11 | Johnstown   | 1,082             | 5       | 0        | 520,310          | 2,074              | 0.88         | 480.878  | 1.917  | 250.873  | 1.026 |
| 45           | Brookville        | 00125-23 | Dubois      | 635               | 36      | 2        | 518,606          | 2,001              | 0.88         | 816.702  | 3.151  | 259.173  | 6.748 |
| 46           | Philipsburg       | 00161-22 | Philipsburg | 775               | 34      | 0        | 515,444          | 2,148              | 0.87         | 665.089  | 2.772  | 239.965  | 0.009 |
| 47           | Erie South        | 00259-31 | Erie        | 2,713             | 110     | 0        | 491,188          | 6,223              | 0.83         | 181.050  | 2.294  | 78.931   | 2.116 |
| 48           | Lenox             | 00757-65 | Montrose    | 113               | 6       | 0        | 483,058          | 238                | 0.82         | 4274.850 | 2.106  | 2029.655 | 0.000 |
| 49           | Marienville       | 00327-51 | Oil City    | 761               | 36      | 0        | 478,477          | 1,534              | 0.81         | 628.748  | 2.016  | 311.915  | 0.003 |
| 50           | Lenox             | 00434-65 | Montrose    | 287               | 11      | 1        | 473,229          | 516                | 0.80         | 1648.882 | 1.798  | 917.110  | 0.014 |
| 51           | Ehrenfeld Jackson | 00306-72 | Altoona     | 397               | 14      | 1        | 468,235          | 1,029              | 0.79         | 1179.433 | 2.592  | 455.039  | 0.000 |
| 52           | North Warren      | 00207-41 | Warren      | 1,404             | 55      | 1        | 467,310          | 3,076              | 0.79         | 332.842  | 2.191  | 151.921  | 1.813 |
| 53           | Ashville          | 00061-71 | Altoona     | 501               | 14      | 0        | 453,604          | 857                | 0.77         | 905.397  | 1.711  | 529.293  | 0.000 |
| 54           | Montrose          | 00457-65 | Montrose    | 686               | 42      | 0        | 453,201          | 1,527              | 0.77         | 660.643  | 2.226  | 296.792  | 0.001 |

| <b>Penelec</b>      |                   |                |                 |                          |                |                 |                         |                           |                     |              |              |              |              |
|---------------------|-------------------|----------------|-----------------|--------------------------|----------------|-----------------|-------------------------|---------------------------|---------------------|--------------|--------------|--------------|--------------|
| <b>Circuit Rank</b> | <b>Substation</b> | <b>Circuit</b> | <b>District</b> | <b>Average Customers</b> | <b>Outages</b> | <b>Lockouts</b> | <b>Customer Minutes</b> | <b>Customers Affected</b> | <b>SAIDI Impact</b> | <b>SAIDI</b> | <b>SAIFI</b> | <b>CAIDI</b> | <b>MAIFI</b> |
| 55                  | Greenwood         | 00001-71       | Altoona         | 1,147                    | 19             | 3               | 450,214                 | 3,834                     | 0.76                | 392.514      | 3.343        | 117.427      | 0.000        |
| 56                  | French Road       | 00222-31       | Erie            | 1,691                    | 27             | 2               | 446,478                 | 6,926                     | 0.75                | 264.032      | 4.096        | 64.464       | 0.574        |
| 57                  | Mansfield         | 00558-63       | Mansfield Pa    | 882                      | 40             | 0               | 444,023                 | 1,778                     | 0.75                | 503.427      | 2.016        | 249.732      | 0.718        |
| 58                  | Platea            | 00432-34       | Erie            | 645                      | 46             | 0               | 442,771                 | 1,293                     | 0.75                | 686.467      | 2.005        | 342.437      | 0.155        |
| 59                  | Dubois            | 00124-23       | Dubois          | 2,092                    | 31             | 0               | 438,058                 | 5,643                     | 0.74                | 209.397      | 2.697        | 77.629       | 0.010        |
| 60                  | New Albany Sw St  | 00570-62       | Towanda         | 149                      | 13             | 2               | 435,704                 | 583                       | 0.74                | 2924.188     | 3.913        | 747.348      | 0.960        |
| 61                  | Union City        | 00208-43       | Erie            | 1,615                    | 61             | 1               | 425,818                 | 7,689                     | 0.72                | 263.664      | 4.761        | 55.380       | 1.224        |
| 62                  | Logan             | 00700-81       | Lewistown       | 1,020                    | 38             | 0               | 420,750                 | 2,659                     | 0.71                | 412.500      | 2.607        | 158.236      | 0.155        |

| Penn Power   |            |         |            |                   |         |          |                  |                    |              |           |        |         |       |
|--------------|------------|---------|------------|-------------------|---------|----------|------------------|--------------------|--------------|-----------|--------|---------|-------|
| Circuit Rank | Substation | Circuit | District   | Average Customers | Outages | Lockouts | Customer Minutes | Customers Affected | SAIDI Impact | SAIDI     | SAIFI  | CAIDI   | MAIFI |
| 1            | Hartstown  | W-126   | Clark      | 2,298             | 85      | 0        | 923,210          | 2,829              | 5.25         | 401.745   | 1.231  | 326.338 | 0.000 |
| 2            | Darlington | D-536   | Zelienople | 1,179             | 54      | 2        | 848,142          | 3,351              | 4.83         | 719.37405 | 2.842  | 253.101 | 0.014 |
| 3            | Canal      | W-101   | Clark      | 1,596             | 38      | 0        | 673,948          | 6,877              | 3.84         | 422.27318 | 4.309  | 98.000  | 0.176 |
| 4            | Ray Street | D-389   | New Castle | 1,218             | 49      | 0        | 649,046          | 2,717              | 3.69         | 532.87849 | 2.231  | 238.883 | 0.000 |
| 5            | Mercer     | W-129   | Clark      | 1,167             | 57      | 0        | 594,215          | 1,994              | 3.38         | 509.18166 | 1.709  | 298.002 | 0.947 |
| 6            | Seneca     | W700    | Zelienople | 930               | 22      | 2        | 569,131          | 2,919              | 3.24         | 611.96882 | 3.139  | 194.975 | 0.000 |
| 7            | Castlewood | D-325   | New Castle | 1,129             | 6       | 1        | 530,074          | 2,603              | 3.02         | 469.50753 | 2.306  | 203.640 | 0.000 |
| 8            | Hartstown  | W-125   | Clark      | 625               | 59      | 1        | 529,399          | 7,485              | 3.01         | 847.0384  | 11.976 | 70.728  | 0.000 |
| 9            | Mercer     | W-128   | Clark      | 1,249             | 47      | 0        | 485,033          | 1,410              | 2.76         | 388.33707 | 1.129  | 343.995 | 0.954 |
| 10           | Jamestown  | W-161   | Clark      | 758               | 35      | 4        | 462,441          | 3,748              | 5.25         | 401.745   | 1.231  | 123.383 | 0.000 |

| West Penn    |                |                  |                 |                   |         |          |                  |                    |              |          |       |           |
|--------------|----------------|------------------|-----------------|-------------------|---------|----------|------------------|--------------------|--------------|----------|-------|-----------|
| Circuit Rank | Substation     | Circuit          | District        | Average Customers | Outages | Lockouts | Customer Minutes | Customers Affected | SAIDI Impact | SAIDI    | SAIFI | CAIDI     |
| 1            | Rutan          | New Freeport     | Jefferson       | 736               | 66      | 0        | 2,216,064        | 3,453              | 3.041        | 3010.957 | 4.692 | 641.779   |
| 2            | Warfordsburg   | Big Cove         | Mcconnellsburg  | 688               | 41      | 2        | 1,743,724        | 1,918              | 2.393        | 2534.483 | 2.788 | 909.137   |
| 3            | Robbins        | Mt Vernon        | Jeannette       | 1,032             | 19      | 0        | 1,495,897        | 1,566              | 2.053        | 1449.513 | 1.517 | 955.234   |
| 4            | Driftwood      | Driftwood        | St Marys        | 973               | 30      | 0        | 1,434,184        | 2,513              | 1.968        | 1473.982 | 2.583 | 570.706   |
| 5            | Emmaville      | Stoney Break     | Mcconnellsburg  | 380               | 10      | 0        | 1,379,509        | 899                | 1.893        | 3630.287 | 2.366 | 1,534.493 |
| 6            | Buena Vista    | Chicora          | Butler          | 1,149             | 32      | 2        | 1,298,324        | 1,944              | 1.782        | 1129.960 | 1.692 | 667.862   |
| 7            | Flintstone     | Chaneysville     | Hyndman         | 575               | 47      | 0        | 1,273,402        | 1,361              | 1.747        | 2214.612 | 2.367 | 935.637   |
| 8            | Franklin (Wpp) | South Waynesburg | Jefferson       | 2,059             | 43      | 3        | 1,232,969        | 6,447              | 1.692        | 598.819  | 3.131 | 191.247   |
| 9            | Houston        | Weavertown       | Washington Pa   | 2,347             | 36      | 1        | 1,213,628        | 6,647              | 1.665        | 517.098  | 2.832 | 182.583   |
| 10           | Dutch Fork     | Claysville       | Washington Pa   | 1,642             | 59      | 2        | 1,131,013        | 4,738              | 1.552        | 688.802  | 2.886 | 238.711   |
| 11           | Purcell        | Artemas          | Hyndman         | 622               | 38      | 0        | 1,101,916        | 1,027              | 1.512        | 1771.569 | 1.651 | 1,072.946 |
| 12           | Bethlen        | Laurel Valley    | Latrobe         | 1,420             | 55      | 1        | 1,058,889        | 5,051              | 1.453        | 745.696  | 3.557 | 209.639   |
| 13           | Krendale       | Prospect         | Butler          | 1,487             | 28      | 1        | 1,035,302        | 2,871              | 1.421        | 696.235  | 1.931 | 360.607   |
| 14           | Rutan          | Bristoria        | Jefferson       | 409               | 31      | 0        | 1,018,903        | 1,486              | 1.398        | 2491.205 | 3.633 | 685.668   |
| 15           | Levelgreen     | Levelgreen       | Jeannette       | 1,562             | 31      | 2        | 1,000,691        | 4,777              | 1.373        | 640.647  | 3.058 | 209.481   |
| 16           | North Fayette  | Tyre             | Boyce           | 1,929             | 45      | 1        | 944,685          | 8,927              | 1.296        | 489.728  | 4.628 | 105.823   |
| 17           | Vanceville     | Vanceville       | Charleroi       | 1,395             | 57      | 0        | 927,414          | 2,594              | 1.273        | 664.813  | 1.859 | 357.523   |
| 18           | Saltsburg      | Avonmore         | Arnold          | 797               | 30      | 3        | 918,390          | 3,693              | 1.260        | 1152.309 | 4.634 | 248.684   |
| 19           | Dutch Fork     | W Alexander      | Washington Pa   | 1,167             | 56      | 1        | 917,341          | 3,318              | 1.259        | 786.068  | 2.843 | 276.474   |
| 20           | Necessity      | Ohiopyle         | Uniontown       | 881               | 50      | 0        | 889,148          | 2,486              | 1.220        | 1009.249 | 2.822 | 357.662   |
| 21           | Necessity      | Gibbon Glade     | Uniontown       | 541               | 27      | 0        | 876,570          | 1,517              | 1.203        | 1620.277 | 2.804 | 577.831   |
| 22           | Franklin (Wpp) | Rogersville      | Jefferson       | 831               | 46      | 1        | 857,927          | 1,717              | 1.177        | 1032.403 | 2.066 | 499.666   |
| 23           | Donegal        | Champion         | Pleasant Valley | 1,187             | 29      | 2        | 857,321          | 3,239              | 1.176        | 722.259  | 2.729 | 264.687   |
| 24           | Charleroi      | Speers           | Charleroi       | 1,436             | 39      | 2        | 836,263          | 4,606              | 1.148        | 582.356  | 3.208 | 181.559   |
| 25           | Saltsburg      | Saltsburg        | Arnold          | 1,396             | 44      | 2        | 808,263          | 3,595              | 1.109        | 578.985  | 2.575 | 224.830   |
| 26           | Howard         | Town             | State College   | 1,155             | 58      | 1        | 793,486          | 3,276              | 1.087        | 687.001  | 2.836 | 242.212   |
| 27           | Smith          | Florence         | Washington Pa   | 806               | 59      | 0        | 793,045          | 1,923              | 1.088        | 983.927  | 2.386 | 412.400   |

| West Penn    |                      |                |                 |                   |         |          |                  |                    |              |          |       |         |
|--------------|----------------------|----------------|-----------------|-------------------|---------|----------|------------------|--------------------|--------------|----------|-------|---------|
| Circuit Rank | Substation           | Circuit        | District        | Average Customers | Outages | Lockouts | Customer Minutes | Customers Affected | SAIDI Impact | SAIDI    | SAIFI | CAIDI   |
| 28           | Hickory              | Hickory        | Washington Pa   | 956               | 31      | 0        | 764,241          | 2,140              | 1.049        | 799.415  | 2.238 | 357.122 |
| 29           | Huntingdon (Wpp)     | Shawtown       | Jeannette       | 1,798             | 21      | 1        | 749,180          | 4,509              | 1.028        | 416.674  | 2.508 | 166.152 |
| 30           | Roundhill            | Roundhill      | Charleroi       | 953               | 35      | 2        | 748,515          | 4,061              | 1.027        | 785.430  | 4.261 | 184.318 |
| 31           | Kiski Valley Distrib | Kittanning Rd  | Arnold          | 1,759             | 42      | 0        | 731,952          | 2,722              | 1.004        | 416.118  | 1.547 | 268.902 |
| 32           | Lardin               | Edenborn       | Uniontown       | 1,394             | 18      | 2        | 713,888          | 3,209              | 0.980        | 512.115  | 2.302 | 222.464 |
| 33           | Waterville           | Waterville     | State College   | 364               | 19      | 1        | 697,351          | 2,063              | 0.957        | 1915.799 | 5.668 | 338.028 |
| 34           | Lagonda              | Lagonda        | Washington Pa   | 1,472             | 45      | 2        | 695,157          | 4,610              | 0.954        | 472.253  | 3.132 | 150.793 |
| 35           | Donegal              | Bear Rocks     | Pleasant Valley | 1,281             | 44      | 1        | 680,380          | 2,746              | 0.934        | 531.132  | 2.144 | 247.771 |
| 36           | Thompson Farm        | Village 12Kv   | State College   | 1,397             | 3       | 1        | 680,121          | 3,051              | 0.933        | 486.844  | 2.184 | 222.917 |
| 37           | Piney Fork           | Stoltz         | Charleroi       | 2,088             | 29      | 2        | 666,835          | 7,076              | 0.915        | 319.365  | 3.389 | 94.239  |
| 38           | Hempfield            | Cool Valley    | Jeannette       | 1,202             | 14      | 1        | 660,440          | 3,871              | 0.906        | 549.451  | 3.220 | 170.612 |
| 39           | Westraver            | West Newton    | Charleroi       | 1,710             | 21      | 2        | 646,701          | 4,122              | 0.887        | 378.188  | 2.411 | 156.890 |
| 40           | Cecil                | Hendersonville | Boyce           | 2,034             | 21      | 2        | 638,688          | 4,894              | 0.876        | 314.006  | 2.406 | 130.504 |
| 41           | Guilford             | Dixie          | Waynesboro      | 1,604             | 37      | 1        | 636,845          | 2,662              | 0.874        | 397.036  | 1.660 | 239.236 |

| Met-Ed |   |           |                        |                      |                          |
|--------|---|-----------|------------------------|----------------------|--------------------------|
| Rank   | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 1      | Walker Sub                              | 00865-3   | Stroudsburg            | 2,962                | 84                       |
|        | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact                            | 9.76      | Trees Off Row-Tree     | 69%                  | Q4 2024                  |
|        | SAIDI                                   | 1,925.66  | Trees Off Row-Limb     | 17%                  | Q1 2025                  |
|        | SAIFI                                   | 1.96      | Trees On Row           | 7%                   | Q2 2025                  |
|        | CAIDI                                   | 983.25    | All Other              | 7%                   | Q3 2025                  |
|        | Customer Minutes                        | 5,703,805 |                        |                      |                          |
|        | Customers Affected                      | 5,801     |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|        | LTIIIP pole replacement                 |           |                        | Complete             | Nov-24                   |
|        | On Cycle Tree Trimming                  |           |                        | Complete             | Feb-24                   |
|        | LTIIIP Circuit rehab zone 2             |           |                        | To be completed 2025 | 50%                      |
|        | PARC TripSaver Installation             |           |                        | To Be Completed 2025 | 50%                      |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
| Rank   | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 2      | Birdsboro                               | 00757-1   | Reading                | 2,043                | 77                       |
|        | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact                            | 5.21      | Trees On Row           | 68%                  | Q3 2025                  |
|        | SAIDI                                   | 1,491.24  | Trees Off Row-Tree     | 16%                  |                          |
|        | SAIFI                                   | 2.86      | Vehicle                | 4%                   |                          |
|        | CAIDI                                   | 522.13    | All Other              | 12%                  |                          |
|        | Customer Minutes                        | 3,046,607 |                        |                      |                          |
|        | Customers Affected                      | 5,835     |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|        | Mainline circuit rehab                  |           |                        | Complete             | Jul-25                   |
|        | Upgrade recloser                        |           |                        | Complete             | Jul-25                   |
|        | Replace priority poles                  |           |                        | Complete             | Aug-25                   |
|        | Install TripSavers                      |           |                        | To be completed 2025 | 50%                      |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
| Rank   | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 3      | Bernville Sub                           | 00787-1   | Hamburg                | 1,901                | 92                       |
|        | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact                            | 4.44      | Trees Off Row-Tree     | 43%                  | Q2 2025                  |
|        | SAIDI                                   | 1,364.10  | Equipment Failure      | 26%                  | Q3 2025                  |
|        | SAIFI                                   | 2.60      | Trees Off Row-Limb     | 15%                  |                          |
|        | CAIDI                                   | 524.72    | All Other              | 16%                  |                          |
|        | Customer Minutes                        | 2,593,149 |                        |                      |                          |
|        | Customers Affected                      | 4,942     |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|        | PARC tripsaver installation             |           |                        | Complete             | Sep-25                   |
|        | Prime Pole Replacement                  |           |                        | Complete             | Aug-25                   |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |

| Met-Ed |  |            |                        |                      |                          |
|--------|--|------------|------------------------|----------------------|--------------------------|
| Rank   | Substation                               | Circuit    | District               | Customers            | Outages                  |
| 4      | Painted Sky                              | 00650-1    | Reading                | 1,780                | 23                       |
|        | <b>Reliability</b>                       |            | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact                             | 3.86       | Trees Off Row-Tree     | 55%                  | Q3 2025                  |
|        | SAIDI                                    | 1,267.94   | Trees On Row           | 37%                  |                          |
|        | SAIFI                                    | 2.39       | Equipment Failure      | 7%                   |                          |
|        | CAIDI                                    | 531.17     | All Other              | 1%                   |                          |
|        | Customer Minutes                         | 2,256,942  |                        |                      |                          |
|        | Customers Affected                       | 4,249      |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b>  |            |                        | <b>Status</b>        | <b>Progress</b>          |
|        | Install SCADA Recloser                   |            |                        | Complete             | Jul-25                   |
|        | Install SCADA Recloser                   |            |                        | Complete             | Aug-25                   |
|        | Overhead circuit inspection              |            |                        | To be completed 2025 | 0%                       |
|        |  |            |                        |                      |                          |
|        | Rank                                     | Substation | Circuit                | District             | Customers                |
| 5      | No Bangor                                | 00813-3    | Easton                 | 1,373                | 74                       |
|        | <b>Reliability</b>                       |            | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact                             | 3.39       | Trees Off Row-Tree     | 47%                  | Q4 2024                  |
|        | SAIDI                                    | 1,441.49   | Equipment Failure      | 26%                  | Q1 2025                  |
|        | SAIFI                                    | 7.31       | Trees Off Row-Limb     | 9%                   | Q2 2025                  |
|        | CAIDI                                    | 197.27     | All Other              | 18%                  | Q3 2025                  |
|        | Customer Minutes                         | 1,979,164  |                        |                      |                          |
|        | Customers Affected                       | 10,033     |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b>  |            |                        | <b>Status</b>        | <b>Progress</b>          |
|        | LTIIP Line relocation project            |            |                        | Complete             | Dec-24                   |
|        | LTIIP line conversion engineering review |            |                        | Complete             | Feb-25                   |
|        | Replace priority poles                   |            |                        | Complete             | Mar-25                   |
|        | LTIIP Voltage conversion                 |            |                        | Complete             | Jul-25                   |
|        | Upgrade SCADA device                     |            |                        | Complete             | Aug-25                   |
|        |  |            |                        |                      |                          |
|        |  |            |                        |                      |                          |
| Rank   | Substation                               | Circuit    | District               | Customers            | Outages                  |
| 6      | Ringling Rocks Sub                       | 00708-1    | Boyertown              | 2,453                | 89                       |
|        | <b>Reliability</b>                       |            | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact                             | 2.96       | Trees Off Row-Tree     | 73%                  | Q2 2025                  |
|        | SAIDI                                    | 706.29     | Vehicle                | 8%                   | Q3 2025                  |
|        | SAIFI                                    | 3.07       | Trees Off Row-Limb     | 6%                   |                          |
|        | CAIDI                                    | 230.11     | All Other              | 12%                  |                          |
|        | Customer Minutes                         | 1,732,527  |                        |                      |                          |
|        | Customers Affected                       | 7,529      |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b>  |            |                        | <b>Status</b>        | <b>Progress</b>          |
|        | Install TripSavers on circuit            |            |                        | Complete             | Sep-25                   |
|        | Upgrade Recloser                         |            |                        | Complete             | Aug-25                   |
|        | Cycle tree trimming                      |            |                        | Complete             | Aug-25                   |
|        |  |            |                        |                      |                          |
|        |  |            |                        |                      |                          |

| Met-Ed |   |            |                        |               |                          |
|--------|---|------------|------------------------|---------------|--------------------------|
| Rank   | Substation                              | Circuit    | District               | Customers     | Outages                  |
| 7      | Ottsville Substation                    | 00660-3    | Easton                 | 890           | 80                       |
|        | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|        | SAIDI Impact                            | 2.78       | Trees Off Row-Tree     | 62%           | Q4 2024                  |
|        | SAIDI                                   | 1,827.79   | Equipment Failure      | 16%           | Q1 2025                  |
|        | SAIFI                                   | 5.17       | Trees On Row           | 11%           | Q2 2025                  |
|        | CAIDI                                   | 353.25     | All Other              | 12%           | Q3 2025                  |
|        | Customer Minutes                        | 1,626,733  |                        |               |                          |
|        | Customers Affected                      | 4,605      |                        |               |                          |
|        | <b>Remedial Action Planned or Taken</b> |            |                        | <b>Status</b> | <b>Progress</b>          |
|        | Post Storm Forestry Circuit Patrol      |            |                        | Complete      | Jul-24                   |
|        | Cycle tree trimming                     |            |                        | Complete      | Aug-25                   |
|        | PARC TripSaver Installation             |            |                        | Complete      | Aug-25                   |
|        |   |            |                        |               |                          |
|        |   |            |                        |               |                          |
| Rank   | Substation                              | Circuit    | District               | Customers     | Outages                  |
| 8      | W Boyertown Sub                         | 00484-1    | Boyertown              | 928           | 28                       |
|        | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|        | SAIDI Impact                            | 2.72       | Trees Off Row-Tree     | 78%           | Q3 2025                  |
|        | SAIDI                                   | 1,710.89   | Equipment Failure      | 9%            |                          |
|        | SAIFI                                   | 3.08       | Line Failure           | 7%            |                          |
|        | CAIDI                                   | 555.34     | All Other              | 6%            |                          |
|        | Customer Minutes                        | 1,587,705  |                        |               |                          |
|        | Customers Affected                      | 2,859      |                        |               |                          |
|        | <b>Remedial Action Planned or Taken</b> |            |                        | <b>Status</b> | <b>Progress</b>          |
|        | Repair damage caused by a tree          |            |                        | Complete      | Jul-25                   |
|        | Repair line failure                     |            |                        | Complete      | Aug-25                   |
|        |   |            |                        |               |                          |
|        |   |            |                        |               |                          |
|        | Rank                                    | Substation | Circuit                | District      | Customers                |
| 9      | Lynnville Sub                           | 00737-1    | Hamburg                | 1,092         | 95                       |
|        | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|        | SAIDI Impact                            | 2.49       | Equipment Failure      | 44%           | Q4 2024                  |
|        | SAIDI                                   | 1,332.12   | Trees Off Row-Tree     | 23%           | Q1 2025                  |
|        | SAIFI                                   | 7.83       | Unknown                | 14%           | Q2 2025                  |
|        | CAIDI                                   | 170.18     | All Other              | 19%           | Q3 2025                  |
|        | Customer Minutes                        | 1,454,675  |                        |               |                          |
|        | Customers Affected                      | 8,548      |                        |               |                          |
|        | <b>Remedial Action Planned or Taken</b> |            |                        | <b>Status</b> | <b>Progress</b>          |
|        | Overhead circuit inspection             |            |                        | Complete      | Nov-24                   |
|        | PARC tripsaver installation             |            |                        | Complete      | Nov-24                   |
|        | PARC tripsaver installation             |            |                        | Complete      | Aug-25                   |
|        |   |            |                        |               |                          |
|        |   |            |                        |               |                          |

| Met-Ed              |   |           |                        |                      |                          |
|---------------------|---|-----------|------------------------|----------------------|--------------------------|
| Rank                | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 10                  | Barto Sub                               | 00705-1   | Boyertown              | 659                  | 62                       |
|                     | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                     | SAIDI Impact                            | 2.38      | Trees Off Row-Tree     | 57%                  | Q2 2025                  |
|                     | SAIDI                                   | 2,109.07  | Equipment Failure      | 16%                  | Q3 2025                  |
|                     | SAIFI                                   | 5.40      | Trees On Row           | 10%                  |                          |
|                     | CAIDI                                   | 390.41    | All Other              | 17%                  |                          |
|                     | Customer Minutes                        | 1,389,877 |                        |                      |                          |
|                     | Customers Affected                      | 3,560     |                        |                      |                          |
|                     | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|                     | Cycle tree trimming                     |           |                        | Complete             | Nov-24                   |
|                     | Overhead circuit inspection             |           |                        | To be completed 2025 | 0%                       |
|                     |   |           |                        |                      |                          |
|                     |   |           |                        |                      |                          |
| Rank                | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 11                  | Barto Sub                               | 00706-1   | Boyertown              | 3,031                | 185                      |
|                     | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                     | SAIDI Impact                            | 2.38      | Trees Off Row-Tree     | 47%                  | Q4 2024                  |
|                     | SAIDI                                   | 458.25    | Wind                   | 16%                  | Q2 2025                  |
|                     | SAIFI                                   | 2.33      | Trees On Row           | 14%                  | Q3 2025                  |
|                     | CAIDI                                   | 196.79    | All Other              | 23%                  |                          |
|                     | Customer Minutes                        | 1,388,968 |                        |                      |                          |
|                     | Customers Affected                      | 7,058     |                        |                      |                          |
|                     | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|                     | Cycle tree trimming                     |           |                        | Complete             | Nov-24                   |
|                     | LTIIP Circuit tie                       |           |                        | To be completed 2025 | 25%                      |
|                     | Overhead circuit inspection             |           |                        | To be completed 2025 | 0%                       |
|                     |   |           |                        |                      |                          |
|                     |   |           |                        |                      |                          |
| Rank                | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 12                  | Lickdale Substation                     | 00625-2   | Lebanon                | 1,022                | 66                       |
|                     | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                     | SAIDI Impact                            | 2.18      | Trees Off Row-Tree     | 72%                  | Q4 2024                  |
|                     | SAIDI                                   | 1,246.20  | Forced Outage          | 17%                  | Q2 2025                  |
|                     | SAIFI                                   | 3.40      | Trees Off Row-Limb     | 4%                   | Q3 2025                  |
|                     | CAIDI                                   | 366.61    | All Other              | 7%                   |                          |
|                     | Customer Minutes                        | 1,273,613 |                        |                      |                          |
|                     | Customers Affected                      | 3,474     |                        |                      |                          |
|                     | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|                     | PARC TripSavers Installation            |           |                        | Complete             | Nov-24                   |
|                     | PARC TripSavers Installation            |           |                        | Complete             | Sep-25                   |
|                     | Primary pole replacement                |           |                        | Complete             | Mar-25                   |
| Overhead Inspection |   |           | To Be Completed 2025   | 99%                  |                          |
|                     |   |           |                        |                      |                          |
|                     |   |           |                        |                      |                          |
|                     |   |           |                        |                      |                          |

| Met-Ed                 |   |           |                        |               |                          |
|------------------------|---|-----------|------------------------|---------------|--------------------------|
| Rank                   | Substation                              | Circuit   | District               | Customers     | Outages                  |
| 13                     | W Boyertown Sub                         | 00715-1   | Boyertown              | 1,718         | 67                       |
|                        | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|                        | SAIDI Impact                            | 2.17      | Trees On Row           | 38%           | Q4 2024                  |
|                        | SAIDI                                   | 738.38    | Trees Off Row-Tree     | 33%           | Q3 2025                  |
|                        | SAIFI                                   | 2.88      | Forced Outage          | 12%           |                          |
|                        | CAIDI                                   | 256.74    | All Other              | 1%            |                          |
|                        | Customer Minutes                        | 1,268,539 |                        |               |                          |
|                        | Customers Affected                      | 4,941     |                        |               |                          |
|                        | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b> | <b>Progress</b>          |
|                        | Cycle Tree Trimming                     |           |                        | Complete      | Aug-25                   |
|                        |   |           |                        |               |                          |
|                        |   |           |                        |               |                          |
| Rank                   | Substation                              | Circuit   | District               | Customers     | Outages                  |
| 14                     | Birdsboro                               | 00759-1   | Reading                | 928           | 74                       |
|                        | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|                        | SAIDI Impact                            | 2.15      | Unknown                | 24%           | Q3 2025                  |
|                        | SAIDI                                   | 1,354.72  | Trees Off Row-Tree     | 21%           |                          |
|                        | SAIFI                                   | 14.52     | Line Failure           | 17%           |                          |
|                        | CAIDI                                   | 93.32     | All Other              | 38%           |                          |
|                        | Customer Minutes                        | 1,257,180 |                        |               |                          |
|                        | Customers Affected                      | 13,471    |                        |               |                          |
|                        | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b> | <b>Progress</b>          |
|                        | Install SCADA Recloser                  |           |                        | Complete      | Jul-25                   |
|                        | Mainline reconductoring                 |           |                        | Complete      | Aug-25                   |
| Install SCADA Recloser |   |           | Complete               | Aug-25        |                          |
| Install SCADA Recloser |   |           | Complete               | Aug-25        |                          |
|                        |   |           |                        |               |                          |
|                        |   |           |                        |               |                          |
| Rank                   | Substation                              | Circuit   | District               | Customers     | Outages                  |
| 15                     | No Bangor                               | 00838-3   | Easton                 | 1,714         | 53                       |
|                        | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|                        | SAIDI Impact                            | 2.13      | Equipment Failure      | 43%           | Q2 2025                  |
|                        | SAIDI                                   | 725.91    | Trees Off Row-Tree     | 23%           | Q3 2025                  |
|                        | SAIFI                                   | 2.97      | Trees On Row           | 17%           |                          |
|                        | CAIDI                                   | 244.54    | All Other              | 17%           |                          |
|                        | Customer Minutes                        | 1,244,207 |                        |               |                          |
|                        | Customers Affected                      | 5,088     |                        |               |                          |
|                        | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b> | <b>Progress</b>          |
|                        | On Cycle Tree Trimming                  |           |                        | Complete      | Feb-25                   |
|                        | LTIIP GOAB installation                 |           |                        | Complete      | Mar-25                   |
| OH Circuit Inspection  |   |           | Complete               | Jun-25        |                          |
|                        |   |           |                        |               |                          |
|                        |   |           |                        |               |                          |
|                        |   |           |                        |               |                          |

| Met-Ed                                  |  |                        |                        |                          |                          |         |
|---|--|------------------------|------------------------|--------------------------|--------------------------|---------|
| Rank                                    | Substation   | Circuit                | District               | Customers                | Outages                  |         |
| 16                                      | No Bangor  | 00826-3                | Easton                 | 3,331                    | 118                      |         |
|   | <b>Reliability</b>                                 |                        | <b>Outage by Cause</b> |                          | <b>Previously Ranked</b> |         |
|   | SAIDI Impact                                       | 2.11                   | Trees Off Row-Tree     | 59%                      | Q4 2024                  |         |
|   | SAIDI  | 370.09                 | Forced Outage          | 13%                      | Q1 2025                  |         |
|   | SAIFI  | 2.05                   | Equipment Failure      | 10%                      | Q2 2025                  |         |
|   | CAIDI  | 180.15                 | All Other              | 18%                      | Q3 2025                  |         |
|   | Customer Minutes                                   | 1,232,761              |                        |                          |                          |         |
|   | Customers Affected                                 | 6,843                  |                        |                          |                          |         |
|   | <b>Remedial Action Planned or Taken</b>            |                        |                        | <b>Status</b>            | <b>Progress</b>          |         |
|   | Forestry Aerial Patrol                             |                        |                        | Complete                 | Jul-24                   |         |
|   | Replace priority pole identified during inspection |                        |                        | Complete                 | Oct-24                   |         |
|   | LTIIP Underground replacement                      |                        |                        | Complete                 | Dec-24                   |         |
|   | LTIIP Circuit Loop Engineering Review              |                        |                        | Complete                 | Feb-25                   |         |
|   | Replace priority pole                              |                        |                        | Complete                 | Mar-25                   |         |
|   | Line relocation                                    |                        |                        | Complete                 | Apr-25                   |         |
|   |  |                        |                        |                          |                          |         |
|   |  |                        |                        |                          |                          |         |
| Rank                                    | Substation   | Circuit                | District               | Customers                | Outages                  |         |
| 17                                      | Fox Hill Subst                                     | 00816-3                | Stroudsburg            | 3,335                    | 44                       |         |
|   | <b>Reliability</b>                                 |                        | <b>Outage by Cause</b> |                          | <b>Previously Ranked</b> |         |
|   | SAIDI Impact                                       | 2.03                   | Trees Off Row-Tree     | 49%                      | Q4 2024                  |         |
|   | SAIDI  | 355.88                 | Vehicle                | 21%                      | Q1 2025                  |         |
|   | SAIFI  | 2.89                   | Trees On Row           | 13%                      | Q2 2025                  |         |
|   | CAIDI  | 123.04                 | All Other              | 16%                      | Q3 2025                  |         |
|   | Customer Minutes                                   | 1,186,846              |                        |                          |                          |         |
|   | Customers Affected                                 | 9,646                  |                        |                          |                          |         |
|   | <b>Remedial Action Planned or Taken</b>            |                        |                        | <b>Status</b>            | <b>Progress</b>          |         |
|   | Replace UG items identified during inspection      |                        |                        | Complete                 | Dec-24                   |         |
|   | LTIIP GOAB switch replacement                      |                        |                        | Complete                 | Feb-25                   |         |
|   | On Cycle Tree Trimming                             |                        |                        | Complete                 | Jun-24                   |         |
|   |  |                        |                        |                          |                          |         |
|   |  |                        |                        |                          |                          |         |
|   | Rank   | Substation             | Circuit                | District                 | Customers                | Outages |
|   | 18   | Schuylkill Ave         | 00157-1                | Reading                  | 1,634                    | 12      |
| <b>Reliability</b>                      |  | <b>Outage by Cause</b> |                        | <b>Previously Ranked</b> |                          |         |
| SAIDI Impact                            |  | 2.02                   | Trees Off Row-Tree     | 65%                      | Q3 2025                  |         |
| SAIDI                                   |  | 722.40                 | Forced Outage          | 31%                      |                          |         |
| SAIFI                                   |  | 1.90                   | Line Failure           | 3%                       |                          |         |
| CAIDI                                   |  | 379.55                 | All Other              | 1%                       |                          |         |
| Customer Minutes                        |  | 1,180,403              |                        |                          |                          |         |
| Customers Affected                      |  | 3,110                  |                        |                          |                          |         |
| <b>Remedial Action Planned or Taken</b> |  |                        | <b>Status</b>          | <b>Progress</b>          |                          |         |
| Repair damage caused by a tree          |  |                        | Complete               | Jul-25                   |                          |         |
|   |  |                        |                        |                          |                          |         |
|   |  |                        |                        |                          |                          |         |
|   |  |                        |                        |                          |                          |         |

| Met-Ed |   |           |                        |                      |                          |
|--------|---|-----------|------------------------|----------------------|--------------------------|
| Rank   | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 19     | Bern Church Sub                         | 00789-1   | Reading                | 1,472                | 86                       |
|        | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact                            | 2.02      | Trees Off Row-Tree     | 46%                  | Q2 2025                  |
|        | SAIDI                                   | 801.67    | Trees On Row           | 36%                  | Q3 2025                  |
|        | SAIFI                                   | 2.73      | Equipment Failure      | 10%                  |                          |
|        | CAIDI                                   | 294.06    | All Other              | 8%                   |                          |
|        | Customer Minutes                        | 1,180,051 |                        |                      |                          |
|        | Customers Affected                      | 4,013     |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|        | Overhead circuit inspection             |           |                        | Complete             | Mar-25                   |
|        | Cycle tree trimming                     |           |                        | To be completed 2025 | 98%                      |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
| Rank   | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 20     | Huffs Church                            | 00600-1   | Boyertown              | 1,517                | 127                      |
|        | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact                            | 1.95      | Trees Off Row-Tree     | 59%                  | Q4 2024                  |
|        | SAIDI                                   | 751.25    | Forced Outage          | 10%                  | Q1 2025                  |
|        | SAIFI                                   | 2.41      | Equipment Failure      | 7%                   | Q2 2025                  |
|        | CAIDI                                   | 312.32    | All Other              | 24%                  | Q3 2025                  |
|        | Customer Minutes                        | 1,139,646 |                        |                      |                          |
|        | Customers Affected                      | 3,649     |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|        | Cycle tree trimming                     |           |                        | Complete             | Feb-25                   |
|        | Zone 2 Overhead Circuit Rehab           |           |                        | Complete             | Sep-25                   |
|        | Zone 2 Overhead Circuit Rehab           |           |                        | Complete             | Sep-25                   |
|        | Overhead circuit inspection             |           |                        | To be completed 2025 | 99%                      |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
| Rank   | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 21     | Muhlenberg                              | 00511-1   | Reading                | 843                  | 5                        |
|        | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact                            | 1.92      | Unknown                | 99%                  | Q2 2025                  |
|        | SAIDI                                   | 1,329.08  | Trees - Sec/Service    | 0%                   | Q3 2025                  |
|        | SAIFI                                   | 2.00      | Equipment Failure      | 0%                   |                          |
|        | CAIDI                                   | 663.36    | All Other              | 0%                   |                          |
|        | Customer Minutes                        | 1,120,416 |                        |                      |                          |
|        | Customers Affected                      | 1,689     |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|        | Restore unknown outage                  |           |                        | Complete             | Jun-25                   |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |

| Met-Ed                                  |   |                        |                        |                          |                          |         |
|---|---|------------------------|------------------------|--------------------------|--------------------------|---------|
| Rank                                    | Substation  | Circuit                | District               | Customers                | Outages                  |         |
| 22                                      | Glendon   | 00819-3                | Easton                 | 1,326                    | 23                       |         |
|   | <b>Reliability</b>                                  |                        | <b>Outage by Cause</b> |                          | <b>Previously Ranked</b> |         |
|   | SAIDI Impact  | 1.83                   | Equipment Failure      | 56%                      | Q4 2024                  |         |
|   | SAIDI   | 808.62                 | Forced Outage          | 24%                      | Q1 2025                  |         |
|   | SAIFI   | 4.37                   | Unknown                | 13%                      | Q2 2025                  |         |
|   | CAIDI   | 184.93                 | All Other              | 7%                       | Q3 2025                  |         |
|   | Customer Minutes                                    | 1,072,226              |                        |                          |                          |         |
|   | Customers Affected                                  | 5,798                  |                        |                          |                          |         |
|   | <b>Remedial Action Planned or Taken</b>             |                        |                        | <b>Status</b>            | <b>Progress</b>          |         |
|   | Forestry Aerial Patrol                              |                        |                        | Complete                 | Jul-24                   |         |
|   | Replace priority items identified during inspection |                        |                        | Complete                 | Nov-24                   |         |
|   | LTIIP circuit rehab engineering review              |                        |                        | Complete                 | Feb-25                   |         |
|   | On cycle tree trimming                              |                        |                        | To be completed 2025     | 99%                      |         |
|   |   |                        |                        |                          |                          |         |
|   |   |                        |                        |                          |                          |         |
| Rank                                    | Substation  | Circuit                | District               | Customers                | Outages                  |         |
| 23                                      | Pine Lane Sub                                       | 00712-1                | Boyertown              | 2,019                    | 13                       |         |
|   | <b>Reliability</b>                                  |                        | <b>Outage by Cause</b> |                          | <b>Previously Ranked</b> |         |
|   | SAIDI Impact  | 1.81                   | Line Failure           | 60%                      | Q3 2025                  |         |
|   | SAIDI   | 523.10                 | Equipment Failure      | 23%                      |                          |         |
|   | SAIFI   | 3.82                   | Overload               | 10%                      |                          |         |
|   | CAIDI   | 136.98                 | All Other              | 6%                       |                          |         |
|   | Customer Minutes                                    | 1,056,146              |                        |                          |                          |         |
|   | Customers Affected                                  | 7,710                  |                        |                          |                          |         |
|   | <b>Remedial Action Planned or Taken</b>             |                        |                        | <b>Status</b>            | <b>Progress</b>          |         |
|   | Mainline reconductoring                             |                        |                        | Complete                 | Aug-25                   |         |
|   | PARC TripSavers Installation                        |                        |                        | To be completed 2025     | 75%                      |         |
|   |   |                        |                        |                          |                          |         |
|   |   |                        |                        |                          |                          |         |
|   | Rank  | Substation             | Circuit                | District                 | Customers                | Outages |
|   | 24  | Bushkill Falls         | 00698-3                | Stroudsburg              | 1,787                    | 22      |
| <b>Reliability</b>                      |   | <b>Outage by Cause</b> |                        | <b>Previously Ranked</b> |                          |         |
| SAIDI Impact                            |   | 1.78                   | Trees Off Row-Tree     | 35%                      | Q2 2025                  |         |
| SAIDI                                   |   | 580.58                 | Line Failure           | 32%                      | Q3 2025                  |         |
| SAIFI                                   |   | 3.15                   | Equipment Failure      | 9%                       |                          |         |
| CAIDI                                   |   | 184.31                 | All Other              | 23%                      |                          |         |
| Customer Minutes                        |   | 1,037,504              |                        |                          |                          |         |
| Customers Affected                      |   | 5,629                  |                        |                          |                          |         |
| <b>Remedial Action Planned or Taken</b> |   |                        | <b>Status</b>          | <b>Progress</b>          |                          |         |
| Overhead circuit inspection             |   |                        | Complete               | Jun-25                   |                          |         |
| Underground inspection                  |   |                        | Complete               | Mar-25                   |                          |         |
| LTIIP - circuit protection              |   |                        | Complete               | Aug-25                   |                          |         |
|   |   |                        |                        |                          |                          |         |
|   |   |                        |                        |                          |                          |         |

| Met-Ed |   |           |                        |                      |                          |
|--------|---|-----------|------------------------|----------------------|--------------------------|
| Rank   | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 25     | Birdsboro                               | 00760-1   | Reading                | 2,193                | 43                       |
|        | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact                            | 1.71      | Line Failure           | 47%                  | Q3 2025                  |
|        | SAIDI                                   | 456.05    | Trees Off Row-Tree     | 26%                  |                          |
|        | SAIFI                                   | 2.43      | Trees On Row           | 11%                  |                          |
|        | CAIDI                                   | 187.71    | All Other              | 15%                  |                          |
|        | Customer Minutes                        | 1,000,115 |                        |                      |                          |
|        | Customers Affected                      | 5,328     |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|        | Install TripSavers on circuit           |           |                        | Complete             | Feb-25                   |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
| Rank   | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 26     | Birdsboro                               | 00756-1   | Reading                | 1,534                | 109                      |
|        | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact                            | 1.65      | Trees Off Row-Tree     | 61%                  | Q4 2024                  |
|        | SAIDI                                   | 629.01    | Trees Off Row-Limb     | 30%                  | Q2 2025                  |
|        | SAIFI                                   | 3.14      | Unknown                | 2%                   | Q3 2025                  |
|        | CAIDI                                   | 200.15    | All Other              | 6%                   |                          |
|        | Customer Minutes                        | 964,902   |                        |                      |                          |
|        | Customers Affected                      | 4,821     |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|        | Targeted tree trimming and removals     |           |                        | Complete             | Sep-24                   |
|        | Install TripSavers on circuit           |           |                        | To be completed 2025 | 75%                      |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
| Rank   | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 27     | Pleasantville                           | 00142-1   | Boyertown              | 812                  | 76                       |
|        | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact                            | 1.65      | Trees Off Row-Tree     | 53%                  | Q1 2025                  |
|        | SAIDI                                   | 1,188.04  | Trees Off Row-Limb     | 19%                  | Q3 2025                  |
|        | SAIFI                                   | 2.80      | Forced Outage          | 6%                   |                          |
|        | CAIDI                                   | 424.97    | All Other              | 22%                  |                          |
|        | Customer Minutes                        | 964,689   |                        |                      |                          |
|        | Customers Affected                      | 2,270     |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|        | Repair damage caused by a tree          |           |                        | Complete             | Dec-24                   |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |
|        |   |           |                        |                      |                          |

| Met-Ed                                  |   |                        |                        |                          |                          |                          |
|---|---|------------------------|------------------------|--------------------------|--------------------------|--------------------------|
| Rank                                    | Substation                              | Circuit                | District               | Customers                | Outages                  |                          |
| 28                                      | Pine Lane Sub                           | 00720-1                | Boyertown              | 1,110                    | 55                       |                          |
|   | <b>Reliability</b>                      |                        | <b>Outage by Cause</b> |                          | <b>Previously Ranked</b> |                          |
|   | SAIDI Impact                            | 1.64                   | Trees Off Row-Tree     | 73%                      | Q2 2025                  |                          |
|   | SAIDI                                   | 861.82                 | Trees Off Row-Limb     | 15%                      | Q3 2025                  |                          |
|   | SAIFI                                   | 2.88                   | Equipment Failure      | 7%                       |                          |                          |
|   | CAIDI                                   | 298.94                 | All Other              | 6%                       |                          |                          |
|   | Customer Minutes                        | 956,621                |                        |                          |                          |                          |
|   | Customers Affected                      | 3,200                  |                        |                          |                          |                          |
|   | <b>Remedial Action Planned or Taken</b> |                        |                        | <b>Status</b>            | <b>Progress</b>          |                          |
|   | Install TripsSavers on Circuit          |                        |                        | Complete                 | Jan-25                   |                          |
|   | Repair items from overhead inspection   |                        |                        | Complete                 | Jun-25                   |                          |
|   | Upgrade Recloser                        |                        |                        | To be completed 2025     | 75%                      |                          |
|   |   |                        |                        |                          |                          |                          |
|   | 29                                      | Bath Sub               | 00873-3                | Easton                   | 2,070                    | 69                       |
| <b>Reliability</b>                      |   | <b>Outage by Cause</b> |                        | <b>Previously Ranked</b> |                          |                          |
| SAIDI Impact                            |   | 1.63                   | Trees Off Row-Tree     | 44%                      | Q4 2024                  |                          |
| SAIDI                                   |   | 460.57                 | Forced Outage          | 17%                      | Q1 2025                  |                          |
| SAIFI                                   |   | 4.56                   | Vehicle                | 17%                      | Q2 2025                  |                          |
| CAIDI                                   |   | 101.06                 | All Other              | 22%                      | Q3 2025                  |                          |
| Customer Minutes                        |   | 953,374                |                        |                          |                          |                          |
| Customers Affected                      |   | 9,434                  |                        |                          |                          |                          |
| <b>Remedial Action Planned or Taken</b> |   |                        | <b>Status</b>          | <b>Progress</b>          |                          |                          |
| Upgrade SCADA devices                   |   |                        | Complete               | Mar-25                   |                          |                          |
| Overhead circuit inspection             |   |                        | Complete               | Mar-25                   |                          |                          |
|   |   |                        |                        |                          |                          |                          |
| 30                                      |   | S Nazareth             | 00809-3                | Easton                   | 3,215                    | 45                       |
|   |   | <b>Reliability</b>     |                        | <b>Outage by Cause</b>   |                          | <b>Previously Ranked</b> |
|   | SAIDI Impact                            | 1.60                   | Vehicle                | 50%                      | Q4 2024                  |                          |
|   | SAIDI                                   | 291.45                 | Equipment Failure      | 18%                      | Q1 2025                  |                          |
|   | SAIFI                                   | 2.18                   | Trees Off Row-Tree     | 11%                      | Q2 2025                  |                          |
|   | CAIDI                                   | 133.59                 | All Other              | 21%                      | Q3 2025                  |                          |
|   | Customer Minutes                        | 937,016                |                        |                          |                          |                          |
|   | Customers Affected                      | 7,014                  |                        |                          |                          |                          |
|   | <b>Remedial Action Planned or Taken</b> |                        |                        | <b>Status</b>            | <b>Progress</b>          |                          |
|   | Cycle tree trimming                     |                        |                        | Complete                 | Sep-24                   |                          |
|   | Overhead circuit inspection             |                        |                        | Complete                 | Mar-25                   |                          |
|   | LTIP circuit rehab engineering review   |                        |                        | Complete                 | Mar-25                   |                          |
|   |   |                        |                        |                          |                          |                          |
|   |   |                        |                        |                          |                          |                          |
|   |   |                        |                        |                          |                          |                          |
|   |   |                        |                        |                          |                          |                          |

| Met-Ed             |   |         |                        |                      |                          |
|--------------------|---|---------|------------------------|----------------------|--------------------------|
| Rank               | Substation                              | Circuit | District               | Customers            | Outages                  |
| 31                 | Leesport Sub                            | 00811-1 | Hamburg                | 1,576                | 61                       |
|                    | <b>Reliability</b>                      |         | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                    | SAIDI Impact                            | 1.54    | Equipment Failure      | 39%                  | Q1 2025                  |
|                    | SAIDI                                   | 569.77  | Trees Off Row-Tree     | 35%                  | Q2 2025                  |
|                    | SAIFI                                   | 2.02    | Vehicle                | 12%                  | Q3 2025                  |
|                    | CAIDI                                   | 281.67  | All Other              | 15%                  |                          |
|                    | Customer Minutes                        | 897,965 |                        |                      |                          |
|                    | Customers Affected                      | 3,188   |                        |                      |                          |
|                    | <b>Remedial Action Planned or Taken</b> |         |                        | <b>Status</b>        | <b>Progress</b>          |
|                    | PARC TripSavers Installation            |         |                        | Complete             | Feb-25                   |
|                    | Recloser inspection                     |         |                        | Complete             | Jun-25                   |
|                    |   |         |                        |                      |                          |
|                    |   |         |                        |                      |                          |
| Rank               | Substation                              | Circuit | District               | Customers            | Outages                  |
| 32                 | Lorane                                  | 00562-1 | Reading                | 1,218                | 28                       |
|                    | <b>Reliability</b>                      |         | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                    | SAIDI Impact                            | 1.52    | Trees Off Row-Tree     | 77%                  | Q3 2025                  |
|                    | SAIDI                                   | 728.64  | Animal                 | 11%                  |                          |
|                    | SAIFI                                   | 2.98    | Trees Off Row-Limb     | 6%                   |                          |
|                    | CAIDI                                   | 244.48  | All Other              | 6%                   |                          |
|                    | Customer Minutes                        | 887,479 |                        |                      |                          |
|                    | Customers Affected                      | 3,630   |                        |                      |                          |
|                    | <b>Remedial Action Planned or Taken</b> |         |                        | <b>Status</b>        | <b>Progress</b>          |
|                    | Install SCADA Recloser                  |         |                        | Complete             | Mar-25                   |
|                    | Install SCADA Recloser                  |         |                        | Complete             | Mar-25                   |
|                    | PARC tripsaver installation             |         |                        | To be completed 2025 | 50%                      |
|                    |   |         |                        |                      |                          |
|                    |   |         |                        |                      |                          |
| Rank               | Substation                              | Circuit | District               | Customers            | Outages                  |
| 33                 | North Cornwall Sub                      | 00611-2 | Lebanon                | 985                  | 36                       |
|                    | <b>Reliability</b>                      |         | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                    | SAIDI Impact                            | 1.48    | Trees Off Row-Tree     | 79%                  | Q1 2025                  |
|                    | SAIDI                                   | 880.98  | Equipment Failure      | 9%                   | Q2 2025                  |
|                    | SAIFI                                   | 2.93    | Unknown                | 7%                   | Q3 2025                  |
|                    | CAIDI                                   | 300.89  | All Other              | 4%                   |                          |
|                    | Customer Minutes                        | 867,761 |                        |                      |                          |
|                    | Customers Affected                      | 2,884   |                        |                      |                          |
|                    | <b>Remedial Action Planned or Taken</b> |         |                        | <b>Status</b>        | <b>Progress</b>          |
|                    | Cycle Tree trimming                     |         |                        | Complete             | Dec-24                   |
|                    | Return INOP Reclosers to service        |         |                        | Complete             | Jul-25                   |
|                    | PARC tripsaver installation             |         |                        | Complete             | Sep-25                   |
|                    | CEMI - line upgrade                     |         |                        | To be completed 2025 | 50%                      |
| Voltage conversion |   |         | Complete               | Aug-25               |                          |
|                    |   |         |                        |                      |                          |
|                    |   |         |                        |                      |                          |
|                    |   |         |                        |                      |                          |

| Met-Ed |   |          |                        |           |                          |                 |
|--------|---|----------|------------------------|-----------|--------------------------|-----------------|
| Rank   | Substation                              | Circuit  | District               | Customers | Outages                  |                 |
| 34     | Bernville Sub                           | 00786-1  | Hamburg                | 1,594     | 105                      |                 |
|        | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|        | SAIDI Impact                            | 1.47     | Trees Off Row-Tree     | 38%       | Q3 2025                  |                 |
|        | SAIDI                                   | 538.80   | Trees Off Row-Limb     | 22%       |                          |                 |
|        | SAIFI                                   | 2.57     | Trees On Row           | 13%       |                          |                 |
|        | CAIDI                                   | 209.32   | All Other              | 28%       |                          |                 |
|        | Customer Minutes                        | 858,852  |                        |           |                          |                 |
|        | Customers Affected                      | 4,103    |                        |           |                          |                 |
|        | <b>Remedial Action Planned or Taken</b> |          |                        |           | <b>Status</b>            | <b>Progress</b> |
|        | PARC tripsaver installation             |          |                        |           | Complete                 | Nov-24          |
|        | PARC tripsaver installation             |          |                        |           | Complete                 | Sep-25          |
|        |   |          |                        |           |                          |                 |
|        |   |          |                        |           |                          |                 |
| Rank   | Substation                              | Circuit  | District               | Customers | Outages                  |                 |
| 35     | Friedensburg Sub                        | 00770-1  | Reading                | 454       | 26                       |                 |
|        | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|        | SAIDI Impact                            | 1.42     | Trees On Row           | 52%       | Q3 2025                  |                 |
|        | SAIDI                                   | 1,823.62 | Trees Off Row-Tree     | 38%       |                          |                 |
|        | SAIFI                                   | 4.14     | Line Failure           | 6%        |                          |                 |
|        | CAIDI                                   | 440.15   | All Other              | 5%        |                          |                 |
|        | Customer Minutes                        | 827,924  |                        |           |                          |                 |
|        | Customers Affected                      | 1,881    |                        |           |                          |                 |
|        | <b>Remedial Action Planned or Taken</b> |          |                        |           | <b>Status</b>            | <b>Progress</b> |
|        | Overhead circuit inspection             |          |                        |           | Complete                 | May-25          |
|        |   |          |                        |           |                          |                 |
|        |   |          |                        |           |                          |                 |
|        |   |          |                        |           |                          |                 |
| Rank   | Substation                              | Circuit  | District               | Customers | Outages                  |                 |
| 36     | Ferndale Sub                            | 00871-3  | Easton                 | 497       | 30                       |                 |
|        | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|        | SAIDI Impact                            | 1.41     | Trees Off Row-Tree     | 90%       | Q4 2024                  |                 |
|        | SAIDI                                   | 1,659.66 | Equipment Failure      | 6%        | Q1 2025                  |                 |
|        | SAIFI                                   | 2.71     | Vehicle                | 2%        | Q2 2025                  |                 |
|        | CAIDI                                   | 612.82   | All Other              | 2%        | Q3 2025                  |                 |
|        | Customer Minutes                        | 824,851  |                        |           |                          |                 |
|        | Customers Affected                      | 1,346    |                        |           |                          |                 |
|        | <b>Remedial Action Planned or Taken</b> |          |                        |           | <b>Status</b>            | <b>Progress</b> |
|        | Post Storm Forestry Circuit Patrol      |          |                        |           | Complete                 | Jul-24          |
|        | Cycle tree trimming                     |          |                        |           | Complete                 | Aug-24          |
|        | LTIP pole replacements                  |          |                        |           | Complete                 | Nov-24          |
|        | Repair mainline broken neutral          |          |                        |           | Complete                 | Jan-25          |
|        |   |          |                        |           |                          |                 |
|        |   |          |                        |           |                          |                 |
|        |   |          |                        |           |                          |                 |

| Met-Ed |   |         |                        |                      |                          |
|--------|---|---------|------------------------|----------------------|--------------------------|
| Rank   | Substation  | Circuit | District               | Customers            | Outages                  |
| 37     | Lorane  | 00560-1 | Reading                | 1,150                | 26                       |
|        | <b>Reliability</b>                                    |         | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact  | 1.34    | Trees Off Row-Tree     | 71%                  | Q3 2025                  |
|        | SAIDI   | 681.15  | Trees On Row           | 27%                  |                          |
|        | SAIFI   | 2.59    | Trees Off Row-Limb     | 1%                   |                          |
|        | CAIDI   | 262.68  | All Other              | 1%                   |                          |
|        | Customer Minutes                                      | 783,318 |                        |                      |                          |
|        | Customers Affected                                    | 2,982   |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b>               |         |                        | <b>Status</b>        | <b>Progress</b>          |
|        | PARC tripsaver installation                           |         |                        | To be completed 2025 | 50%                      |
|        |   |         |                        |                      |                          |
|        |   |         |                        |                      |                          |
| Rank   | Substation  | Circuit | District               | Customers            | Outages                  |
| 38     | Newberry Sub  | 00576-4 | York                   | 1,760                | 88                       |
|        | <b>Reliability</b>                                    |         | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact  | 1.33    | Trees Off Row-Tree     | 42%                  | Q2 2025                  |
|        | SAIDI   | 442.96  | Trees Off Row-Limb     | 23%                  | Q3 2025                  |
|        | SAIFI   | 2.46    | Wind                   | 12%                  |                          |
|        | CAIDI   | 180.38  | All Other              | 23%                  |                          |
|        | Customer Minutes                                      | 779,610 |                        |                      |                          |
|        | Customers Affected                                    | 4,322   |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b>               |         |                        | <b>Status</b>        | <b>Progress</b>          |
|        | LTIIP25 Circuit Protection Newberry 576-4 25690-29169 |         |                        | Complete             | Mar-25                   |
|        | Replace priority items identified during inspection   |         |                        | Complete             | Jul-25                   |
|        | Additional forestry patrol                            |         |                        | Complete             | Apr-25                   |
|        | Additional forestry patrol                            |         |                        | Complete             | Aug-25                   |
|        |   |         |                        |                      |                          |
| Rank   | Substation  | Circuit | District               | Customers            | Outages                  |
| 39     | Lyons Sub   | 00729-1 | Easton                 | 1,366                | 80                       |
|        | <b>Reliability</b>                                    |         | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact  | 1.32    | Trees Off Row-Tree     | 38%                  | Q3 2025                  |
|        | SAIDI   | 564.22  | Wind                   | 19%                  |                          |
|        | SAIFI   | 2.48    | Lightning              | 8%                   |                          |
|        | CAIDI   | 227.89  | All Other              | 35%                  |                          |
|        | Customer Minutes                                      | 770,726 |                        |                      |                          |
|        | Customers Affected                                    | 3,382   |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b>               |         |                        | <b>Status</b>        | <b>Progress</b>          |
|        | Install TripSavers on circuit                         |         |                        | To be completed 2025 | 75%                      |
|        |   |         |                        |                      |                          |
|        |   |         |                        |                      |                          |

| Met-Ed |   |          |                        |                      |                          |
|--------|---|----------|------------------------|----------------------|--------------------------|
| Rank   | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 40     | Ottsville Substation                    | 00661-3  | Reading                | 616                  | 69                       |
|        | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|        | SAIDI Impact                            | 1.31     | Trees Off Row-Tree     | 61%                  | Q4 2024                  |
|        | SAIDI                                   | 1,243.34 | Equipment Failure      | 24%                  | Q1 2025                  |
|        | SAIFI                                   | 3.07     | Trees On Row           | 9%                   | Q2 2025                  |
|        | CAIDI                                   | 405.24   | All Other              | 7%                   | Q3 2025                  |
|        | Customer Minutes                        | 765,900  |                        |                      |                          |
|        | Customers Affected                      | 1,890    |                        |                      |                          |
|        | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|        | Targeted Overhead Circuit Inspection    |          |                        | Complete             | Oct-24                   |
|        | Replace priority pole                   |          |                        | Complete             | Jan-25                   |
|        | LTIIP Line rehab                        |          |                        | To be completed 2025 | 50%                      |
|        | Cycle tree trimming                     |          |                        | Complete             | Aug-25                   |
|        |   |          |                        |                      |                          |
|        |   |          |                        |                      |                          |
|        |   |          |                        |                      |                          |
|        |   |          |                        |                      |                          |

| <b>Met-Ed</b>  |                |                |                |                |               |
|--|----------------|----------------|----------------|----------------|---------------|
| <b>Unranked circuits appearing 2 or more quarters in the last 4 quarters</b> |                |                |                |                |               |
| <b>Substation</b>  | <b>Circuit</b> | <b>4Q 2024</b> | <b>1Q 2025</b> | <b>2Q 2025</b> | <b>Q32025</b> |
| Mountain Substation  | 00744-4        | X              |                | X              |               |
| Mountain Substation  | 00743-4        | X              | X              |                |               |
| Shawnee Sub  | 00822-3        | X              | X              |                |               |
| Shawnee Sub  | 00895-3        | X              | X              |                |               |
| Shawnee Sub  | 00837-3        | X              | X              | X              |               |
| Shawnee Sub  | 00860-3        | X              | X              |                |               |
| Glendon  | 00818-3        | X              | X              | X              |               |
| Glendon  | 00820-3        | X              | X              | X              |               |
| Bridgeton Sub  | 00117-3        | X              | X              |                |               |
| Bridgeton Sub  | 00116-3        |                | X              | X              |               |
| Lyons Sub  | 00725-1        |                | X              | X              |               |
| North Cornwall Sub   | 00610-2        | X              | X              |                |               |
| Ferndale Sub   | 00076-3        | X              | X              | X              |               |
| Ferndale Sub   | 00839-3        |                | X              | X              |               |
| Stroudsburg  | 00610-3        | X              | X              |                |               |
| Northwood Sub  | 00802-3        | X              | X              |                |               |
| Fleetwood Sub  | 00161-1        | X              | X              |                |               |
| Windsor  | 00797-4        |                | X              | X              |               |
| Birchwood Sub  | 00624-3        | X              | X              | X              |               |
| Cly  | 00722-4        |                | X              | X              |               |

| <b>Met-Ed</b>  |                |   |  |  |
|--|----------------|---|--|--|
| <b>Unranked circuits with remedial actions scheduled to be or recently completed</b> |                |   |  |  |
| <b>Substation</b>  | <b>Circuit</b> | <b>Remedial Action Planned or Taken</b>             | <b>Status of Remedial Work Completed</b> | <b>Progress of Remedial Work or Date Completed</b> |
| Shawnee  | 00895-3        | Cycle tree trimming                                 | To be completed 2025                     | 99%  |
| Flying Hills Sub   | 00776-1        | Cycle tree trimming                                 | Complete                                 | Aug-25   |
| S Hamb Sub   | 00740-1        | Cycle tree trimming                                 | To be completed 2025                     | 99%  |
| Mc Knights Gap Sub   | 00774-1        | Cycle tree trimming                                 | To be completed 2025                     | 99%  |
| S Hamb Sub   | 00743-1        | Cycle tree trimming                                 | Complete                                 | Sep-25   |
| Glendon  | 00818-3        | Cycle tree trimming                                 | To be completed 2025                     | 58%  |
| Flying Hills   | 00777-1        | Cycle tree trimming                                 | Complete                                 | Sep-25   |
| North Cornwall   | 00610-2        | PARC tripsaver installation                         | Complete                                 | Sep-25   |
| Glendon  | 00820-3        | Cycle tree trimming                                 | Complete                                 | Aug-25   |
| Glendon  | 00820-3        | LTIP voltage conversion                             | To be completed 2025                     | 25%  |
| Glendon  | 00805-3        | LTIP voltage conversion                             | Complete                                 | Aug-25   |
| Birchwood Sub  | 00624-3        | LTIP load balancing                                 | To be completed 2025                     | 50%  |
| Birchwood Sub  | 00624-3        | LTIP circuit tie                                    | To be completed 2025                     | 25%  |
| Shawnee  | 00899-3        | LTIP circuit rehab zone 1 & 2                       | To be completed 2025                     | 50%  |
| Lyons Sub  | 00725-1        | Cycle tree trimming                                 | Complete                                 | Sep-25   |
| Cly  | 00722-4        | Overhead circuit inspection                         | Complete                                 | Jul-25   |
| Bridgeton Sub  | 00116-3        | Cycle tree trimming                                 | To be completed 2025                     | 99%  |
| Northwood Sub  | 00803-3        | Overhead circuit inspection                         | To be completed 2025                     | 98%  |
| Windsor  | 00797-4        | LTIP - CEMI   | Complete                                 | Jul-25   |
| Windsor  | 00797-4        | Cycle tree trimming                                 | To be completed 2025                     | 87%  |
| Ferndale Sub   | 00076-3        | Overhead circuit inspection                         | To be completed 2025                     | 95%  |
| Shawnee Sub  | 00837-3        | Overhead circuit inspection                         | To be completed 2025                     | 0%   |
| Shawnee Sub  | 00837-3        | PARC tripsaver installation                         | To be completed 2025                     | 75%  |
| Windsor  | 00797-4        | CEMI  | Complete                                 | Jul-25   |
| Windsor  | 00797-4        | CEMI  | Complete                                 | Jul-25   |
| Ferndale Sub   | 00839-3        | Overhead circuit inspection                         | To be completed 2025                     | 98%  |
| Moselem Sub  | 00779-1        | Install tripsavers                                  | Complete                                 | Sep-25   |
| Moselem Sub  | 00779-1        | Overhead circuit inspection                         | Complete                                 | Jul-25   |
| Glades   | 00581-4        | Replace priority items identified during inspection | Complete                                 | Jul-25   |

| Penelec |   |            |                        |                      |                          |
|---------|---|------------|------------------------|----------------------|--------------------------|
| Rank    | Substation                              | Circuit    | District               | Customers            | Outages                  |
| 1       | Thompson                                | 00436-65   | Montrose               | 1,398                | 106                      |
|         | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 20.23      | Forced Outage          | 34%                  | Q4 2024                  |
|         | SAIDI                                   | 8,559.42   | Trees Off Row-Tree     | 28%                  | Q1 2025                  |
|         | SAIFI                                   | 5.43       | Ice                    | 18%                  | Q2 2025                  |
|         | CAIDI                                   | 1,576.56   | All Other              | 19%                  | Q3 2025                  |
|         | Customer Minutes                        | 11,966,069 |                        |                      |                          |
|         | Customers Affected                      | 7,590      |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |            |                        | <b>Status</b>        | <b>Progress</b>          |
|         | Vac Switch Replacement                  |            |                        | Complete             | Feb-25                   |
|         | PARC Tripsavers                         |            |                        | To Be Completed 2025 | 50%                      |
|         | LTIP New Tie Point                      |            |                        | Complete             | Jul-25                   |
|         |   |            |                        |                      |                          |
|         |   |            |                        |                      |                          |
|         |   |            |                        |                      |                          |
| Rank    | Substation                              | Circuit    | District               | Customers            | Outages                  |
| 2       | Lake Como                               | 00787-65   | Montrose               | 957                  | 78                       |
|         | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 10.16      | Trees Off Row-Tree     | 75%                  | Q4 2024                  |
|         | SAIDI                                   | 6,279.58   | Ice                    | 14%                  | Q1 2025                  |
|         | SAIFI                                   | 3.84       | Trees Off Row-Limb     | 7%                   | Q2 2025                  |
|         | CAIDI                                   | 1,634.81   | All Other              | 3%                   | Q3 2025                  |
|         | Customer Minutes                        | 6,009,560  |                        |                      |                          |
|         | Customers Affected                      | 3,676      |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |            |                        | <b>Status</b>        | <b>Progress</b>          |
|         | PARC Tripsavers                         |            |                        | To Be Completed 2025 | 50%                      |
|         |   |            |                        |                      |                          |
|         |   |            |                        |                      |                          |
|         |   |            |                        |                      |                          |
|         |   |            |                        |                      |                          |
| Rank    | Substation                              | Circuit    | District               | Customers            | Outages                  |
| 3       | Thompson                                | 00446-65   | Montrose               | 1,300                | 72                       |
|         | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 8.06       | Ice                    | 62%                  | Q4 2024                  |
|         | SAIDI                                   | 3,667.08   | Trees Off Row-Tree     | 29%                  | Q1 2025                  |
|         | SAIFI                                   | 2.48       | Unknown                | 3%                   | Q2 2025                  |
|         | CAIDI                                   | 1,478.20   | All Other              | 6%                   | Q3 2025                  |
|         | Customer Minutes                        | 4,767,198  |                        |                      |                          |
|         | Customers Affected                      | 3,225      |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |            |                        | <b>Status</b>        | <b>Progress</b>          |
|         | On cycle tree trimming                  |            |                        | Complete             | Feb-25                   |
|         | Replace regulator                       |            |                        | Complete             | Feb-25                   |
|         | PARC Tripsavers                         |            |                        | To Be Completed 2025 | 50%                      |
|         | LTIP step tx upgrade                    |            |                        | To Be Completed 2025 | 50%                      |

| Penelec |   |           |                        |                      |                          |
|---------|---|-----------|------------------------|----------------------|--------------------------|
| Rank    | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 4       | Shawville                               | 00151-21  | Clearfield             | 2,259                | 49                       |
|         | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 6.95      | Trees Off Row-Tree     | 82%                  | Q2 2025                  |
|         | SAIDI                                   | 1,819.59  | Equipment Failure      | 9%                   | Q3 2025                  |
|         | SAIFI                                   | 3.11      | Animal                 | 3%                   |                          |
|         | CAIDI                                   | 584.78    | All Other              | 6%                   |                          |
|         | Customer Minutes                        | 4,110,452 |                        |                      |                          |
|         | Customers Affected                      | 7,029     |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|         | Overhead circuit inspection             |           |                        | Complete             | Apr-25                   |
|         | PARC tripsaver installation             |           |                        | Complete             | Sep-25                   |
|         | 2.4-34.5kV Conversion                   |           |                        | To Be Completed 2025 | 50%                      |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
| Rank    | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 5       | Tiffany                                 | 00435-65  | Montrose               | 1,304                | 46                       |
|         | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 6.25      | Ice                    | 86%                  | Q4 2024                  |
|         | SAIDI                                   | 2,833.86  | Trees Off Row-Tree     | 10%                  | Q1 2025                  |
|         | SAIFI                                   | 3.27      | Lightning              | 2%                   | Q2 2025                  |
|         | CAIDI                                   | 867.66    | All Other              | 2%                   | Q3 2025                  |
|         | Customer Minutes                        | 3,695,349 |                        |                      |                          |
|         | Customers Affected                      | 4,259     |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|         | PARC tripsaver installation             |           |                        | Complete             | Sep-25                   |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
| Rank    | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 6       | Tiffany                                 | 00440-65  | Montrose               | 1,247                | 13                       |
|         | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 5.21      | Ice                    | 99%                  | Q4 2024                  |
|         | SAIDI                                   | 2,470.76  | Forced Outage          | 0%                   | Q1 2025                  |
|         | SAIFI                                   | 2.65      | Line Failure           | 0%                   | Q2 2025                  |
|         | CAIDI                                   | 931.39    | All Other              | 0%                   | Q3 2025                  |
|         | Customer Minutes                        | 3,081,039 |                        |                      |                          |
|         | Customers Affected                      | 3,308     |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|         | LTIIIP Vac Switch                       |           |                        | Complete             | Apr-25                   |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |

| Penelec                     |   |           |                        |                      |                          |
|-----------------------------|---|-----------|------------------------|----------------------|--------------------------|
| Rank                        | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 7                           | Lake Como                               | 00788-65  | Montrose               | 671                  | 55                       |
|                             | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                             | SAIDI Impact                            | 5.07      | Trees Off Row-Tree     | 51%                  | Q4 2024                  |
|                             | SAIDI                                   | 4,466.65  | Ice                    | 35%                  | Q1 2025                  |
|                             | SAIFI                                   | 3.39      | Line Failure           | 6%                   | Q2 2025                  |
|                             | CAIDI                                   | 1,316.84  | All Other              | 7%                   | Q3 2025                  |
|                             | Customer Minutes                        | 2,997,122 |                        |                      |                          |
|                             | Customers Affected                      | 2,276     |                        |                      |                          |
|                             | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|                             | PARC tripsaver installation             |           |                        | To Be Completed 2025 | 50%                      |
|                             |   |           |                        |                      |                          |
|                             |   |           |                        |                      |                          |
|                             |   |           |                        |                      |                          |
| Rank                        | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 8                           | Thompson                                | 00442-65  | Montrose               | 680                  | 49                       |
|                             | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                             | SAIDI Impact                            | 4.54      | Ice                    | 36%                  | Q4 2024                  |
|                             | SAIDI                                   | 3,951.76  | Unknown                | 31%                  | Q1 2025                  |
|                             | SAIFI                                   | 4.96      | Trees Off Row-Tree     | 27%                  | Q2 2025                  |
|                             | CAIDI                                   | 796.21    | All Other              | 5%                   | Q3 2025                  |
|                             | Customer Minutes                        | 2,687,194 |                        |                      |                          |
|                             | Customers Affected                      | 3,375     |                        |                      |                          |
|                             | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|                             | On cycle tree trimming                  |           |                        | Complete             | Oct-24                   |
|                             | PARC Tripsavers                         |           |                        | To Be Completed 2025 | 50%                      |
| LTIIIP Recloser Replacement |   |           | To Be Completed 2025   | 75%                  |                          |
|                             |   |           |                        |                      |                          |
| Rank                        | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 9                           | Lenox                                   | 00755-65  | Montrose               | 716                  | 38                       |
|                             | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                             | SAIDI Impact                            | 4.37      | Trees Off Row-Tree     | 51%                  | Q4 2024                  |
|                             | SAIDI                                   | 3,609.38  | Ice                    | 24%                  | Q1 2025                  |
|                             | SAIFI                                   | 4.77      | Equipment Failure      | 11%                  | Q2 2025                  |
|                             | CAIDI                                   | 757.20    | All Other              | 14%                  | Q3 2025                  |
|                             | Customer Minutes                        | 2,584,316 |                        |                      |                          |
|                             | Customers Affected                      | 3,413     |                        |                      |                          |
|                             | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|                             | LTIIIP Line Rehab                       |           |                        | To Be Completed 2025 | 75%                      |
|                             | PARC tripsaver installation             |           |                        | To Be Completed 2025 | 50%                      |
|                             |   |           |                        |                      |                          |
|                             |   |           |                        |                      |                          |
|                             |   |           |                        |                      |                          |
|                             |   |           |                        |                      |                          |

| Penelec |   |           |                        |                      |                          |
|---------|---|-----------|------------------------|----------------------|--------------------------|
| Rank    | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 10      | Tunkhannock                             | 00533-65  | Montrose               | 1,284                | 66                       |
|         | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 4.07      | Ice                    | 69%                  | Q4 2024                  |
|         | SAIDI                                   | 1,876.67  | Unknown                | 14%                  | Q1 2025                  |
|         | SAIFI                                   | 5.34      | Lightning              | 6%                   | Q2 2025                  |
|         | CAIDI                                   | 351.52    | All Other              | 11%                  | Q3 2025                  |
|         | Customer Minutes                        | 2,409,639 |                        |                      |                          |
|         | Customers Affected                      | 6,855     |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|         | On cycle tree trimming                  |           |                        | Complete             | Sep-24                   |
|         | LTIIIP Replace recloser                 |           |                        | To Be Completed 2025 | 75%                      |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
| Rank    | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 11      | Falls                                   | 00297-65  | Montrose               | 842                  | 43                       |
|         | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 3.27      | Ice                    | 66%                  | Q4 2024                  |
|         | SAIDI                                   | 2,298.42  | Trees Off Row-Tree     | 24%                  | Q1 2025                  |
|         | SAIFI                                   | 3.66      | Forced Outage          | 5%                   | Q2 2025                  |
|         | CAIDI                                   | 627.52    | All Other              | 6%                   | Q3 2025                  |
|         | Customer Minutes                        | 1,935,272 |                        |                      |                          |
|         | Customers Affected                      | 3,084     |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|         | On cycle tree trimming                  |           |                        | Complete             | Jul-25                   |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
| Rank    | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 12      | Brooklyn                                | 00749-65  | Montrose               | 536                  | 35                       |
|         | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 3.01      | Trees Off Row-Tree     | 58%                  | Q4 2024                  |
|         | SAIDI                                   | 3,326.25  | Equipment Failure      | 28%                  | Q1 2025                  |
|         | SAIFI                                   | 2.47      | Ice                    | 7%                   | Q2 2025                  |
|         | CAIDI                                   | 1,345.56  | All Other              | 7%                   | Q3 2025                  |
|         | Customer Minutes                        | 1,782,869 |                        |                      |                          |
|         | Customers Affected                      | 1,325     |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|         | PARC tripsaver installation             |           |                        | To Be Completed 2025 | 50%                      |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |

| Penelec |   |           |                        |                      |                          |
|---------|---|-----------|------------------------|----------------------|--------------------------|
| Rank    | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 13      | Northeast                               | 00591-31  | Erie                   | 643                  | 15                       |
|         | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 2.76      | Vehicle                | 99%                  | Q4 2024                  |
|         | SAIDI                                   | 2,538.02  | Forced Outage          | 0%                   | Q1 2025                  |
|         | SAIFI                                   | 6.60      | Unknown                | 0%                   | Q2 2025                  |
|         | CAIDI                                   | 384.62    | All Other              | 1%                   | Q3 2025                  |
|         | Customer Minutes                        | 1,631,948 |                        |                      |                          |
|         | Customers Affected                      | 4,243     |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|         | Repair damage from vehicle              |           |                        | Complete             | Oct-24                   |
|         | Repair bad UG cable                     |           |                        | Complete             | Jan-25                   |
|         | Repair damage from vehicle              |           |                        | Complete             | Apr-25                   |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
| Rank    | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 14      | N Meshoppen Tran                        | 00534-65  | Montrose               | 898                  | 88                       |
|         | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 2.53      | Ice                    | 29%                  | Q4 2024                  |
|         | SAIDI                                   | 1,664.94  | Trees Off Row-Tree     | 26%                  | Q1 2025                  |
|         | SAIFI                                   | 5.00      | Equipment Failure      | 20%                  | Q2 2025                  |
|         | CAIDI                                   | 332.69    | All Other              | 25%                  | Q3 2025                  |
|         | Customer Minutes                        | 1,495,118 |                        |                      |                          |
|         | Customers Affected                      | 4,494     |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|         | Replace Regulator                       |           |                        | Complete             | Feb-25                   |
|         | PARC tripsaver installation             |           |                        | To Be Completed 2025 | 99%                      |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
| Rank    | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 15      | Grover                                  | 00527-63  | Towanda                | 1,099                | 76                       |
|         | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 2.35      | Trees Off Row-Tree     | 88%                  | Q4 2024                  |
|         | SAIDI                                   | 1,262.67  | Unknown                | 4%                   | Q1 2025                  |
|         | SAIFI                                   | 4.43      | Equipment Failure      | 3%                   | Q2 2025                  |
|         | CAIDI                                   | 284.89    | All Other              | 5%                   | Q3 2025                  |
|         | Customer Minutes                        | 1,387,676 |                        |                      |                          |
|         | Customers Affected                      | 4,871     |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|         | LTIIIP switch replacement with Viper    |           |                        | Complete             | Jun-25                   |
|         | On cycle tree trimming                  |           |                        | To Be Completed 2025 | 21%                      |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |

| Penelec |   |           |                        |                      |                          |
|---------|---|-----------|------------------------|----------------------|--------------------------|
| Rank    | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 16      | Pennmar                                 | 00001-12  | Somerset               | 399                  | 17                       |
|         | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 2.31      | Trees Off Row-Tree     | 88%                  | Q2 2025                  |
|         | SAIDI                                   | 3,421.55  | Unknown                | 4%                   | Q3 2025                  |
|         | SAIFI                                   | 4.65      | Trees Off Row-Limb     | 3%                   |                          |
|         | CAIDI                                   | 735.56    | All Other              | 5%                   |                          |
|         | Customer Minutes                        | 1,365,200 |                        |                      |                          |
|         | Customers Affected                      | 1,856     |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|         | On cycle tree trimming                  |           |                        | Complete             | Oct-24                   |
|         | Overhead circuit inspection             |           |                        | Complete             | May-25                   |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
| Rank    | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 17      | Lake Como                               | 00786-65  | Montrose               | 334                  | 24                       |
|         | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 2.11      | Trees Off Row-Tree     | 73%                  | Q4 2024                  |
|         | SAIDI                                   | 3,734.64  | Trees Off Row-Limb     | 14%                  | Q1 2025                  |
|         | SAIFI                                   | 3.57      | Unknown                | 7%                   | Q2 2025                  |
|         | CAIDI                                   | 1,045.57  | All Other              | 6%                   | Q3 2025                  |
|         | Customer Minutes                        | 1,247,370 |                        |                      |                          |
|         | Customers Affected                      | 1,193     |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|         | LTIIP Line rehab                        |           |                        | To Be Completed 2025 | 75%                      |
|         | PARC tripsaver installation             |           |                        | Complete             | Sep-25                   |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
| Rank    | Substation                              | Circuit   | District               | Customers            | Outages                  |
| 18      | East Sayre                              | 00518-61  | Towanda                | 982                  | 33                       |
|         | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 1.93      | Ice                    | 85%                  | Q4 2024                  |
|         | SAIDI                                   | 1,164.16  | Trees Off Row-Limb     | 12%                  | Q1 2025                  |
|         | SAIFI                                   | 1.70      | Trees Off Row-Tree     | 1%                   | Q3 2025                  |
|         | CAIDI                                   | 684.14    | All Other              | 2%                   |                          |
|         | Customer Minutes                        | 1,143,206 |                        |                      |                          |
|         | Customers Affected                      | 1,671     |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |           |                        | <b>Status</b>        | <b>Progress</b>          |
|         | LTIIP Animal guarding                   |           |                        | Complete             | Jul-25                   |
|         | PARC Tripsavers                         |           |                        | Complete             | Sep-25                   |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |
|         |   |           |                        |                      |                          |

| Penelec                     |   |           |                        |                      |                          |
|-----------------------------|---|-----------|------------------------|----------------------|--------------------------|
| Rank                        | Substation                                | Circuit   | District               | Customers            | Outages                  |
| 19                          | Dushore                                   | 00641-62  | Towanda                | 94                   | 42                       |
|                             | <b>Reliability</b>                        |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                             | SAIDI Impact                              | 1.68      | Ice                    | 54%                  | Q4 2024                  |
|                             | SAIDI                                     | 10,572.81 | Trees Off Row-Tree     | 34%                  | Q1 2025                  |
|                             | SAIFI                                     | 18.57     | Trees Off Row-Limb     | 7%                   | Q2 2025                  |
|                             | CAIDI                                     | 569.21    | All Other              | 5%                   | Q3 2025                  |
|                             | Customer Minutes                          | 993,844   |                        |                      |                          |
|                             | Customers Affected                        | 1,746     |                        |                      |                          |
|                             | <b>Remedial Action Planned or Taken</b>   |           |                        | <b>Status</b>        | <b>Progress</b>          |
|                             | LTIIIP Line rehab                         |           |                        | To Be Completed 2025 | 75%                      |
|                             | PARC tripsaver installation               |           |                        | Complete             | Sep-25                   |
|                             |   |           |                        |                      |                          |
|                             |   |           |                        |                      |                          |
| Rank                        | Substation                                | Circuit   | District               | Customers            | Outages                  |
| 20                          | Springboro                                | 00237-52  | Meadville              | 2,808                | 85                       |
|                             | <b>Reliability</b>                        |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                             | SAIDI Impact                              | 1.58      | Trees Off Row-Tree     | 51%                  | Q4 2024                  |
|                             | SAIDI                                     | 332.13    | Line Failure           | 28%                  | Q1 2025                  |
|                             | SAIFI                                     | 2.25      | Equipment Failure      | 12%                  | Q2 2025                  |
|                             | CAIDI                                     | 147.71    | All Other              | 9%                   | Q3 2025                  |
|                             | Customer Minutes                          | 932,619   |                        |                      |                          |
|                             | Customers Affected                        | 6,314     |                        |                      |                          |
|                             | <b>Remedial Action Planned or Taken</b>   |           |                        | <b>Status</b>        | <b>Progress</b>          |
|                             | Repair damage caused by trees             |           |                        | Complete             | Dec-24                   |
|                             | Repair line failure                       |           |                        | Complete             | Feb-25                   |
|                             | LTIIIP - replace recloser                 |           |                        | To Be Completed 2025 | 50%                      |
|                             | Repair damage caused by trees             |           |                        | Complete             | Apr-25                   |
| PARC tripsaver installation |   |           | Complete               | Sep-25               |                          |
|                             |   |           |                        |                      |                          |
|                             |   |           |                        |                      |                          |
| Rank                        | Substation                                | Circuit   | District               | Customers            | Outages                  |
| 21                          | Laurel Lake Sub Tran                      | 00449-65  | Montrose               | 538                  | 40                       |
|                             | <b>Reliability</b>                        |           | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                             | SAIDI Impact                              | 1.56      | Ice                    | 77%                  | Q4 2024                  |
|                             | SAIDI                                     | 1,715.86  | Trees Off Row-Tree     | 13%                  | Q1 2025                  |
|                             | SAIFI                                     | 2.41      | Equipment Failure      | 5%                   | Q3 2025                  |
|                             | CAIDI                                     | 711.74    | All Other              | 5%                   |                          |
|                             | Customer Minutes                          | 923,132   |                        |                      |                          |
|                             | Customers Affected                        | 1,297     |                        |                      |                          |
|                             | <b>Remedial Action Planned or Taken</b>   |           |                        | <b>Status</b>        | <b>Progress</b>          |
|                             | LTIIIP Replace sectionalizers with Vipers |           |                        | To Be Completed 2025 | 75%                      |
|                             | PARC tripsaver installation               |           |                        | Complete             | Sep-25                   |
|                             |   |           |                        |                      |                          |

| Penelec |  |          |                        |                      |                          |
|---------|--|----------|------------------------|----------------------|--------------------------|
| Rank    | Substation                               | Circuit  | District               | Customers            | Outages                  |
| 22      | Boyer                                    | 00584-31 | Erie                   | 1,717                | 28                       |
|         | <b>Reliability</b>                       |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                             | 1.43     | Line Failure           | 42%                  | Q4 2024                  |
|         | SAIDI                                    | 494.28   | Unknown                | 35%                  | Q1 2025                  |
|         | SAIFI                                    | 6.96     | Forced Outage          | 14%                  | Q2 2025                  |
|         | CAIDI                                    | 71.07    | All Other              | 9%                   | Q3 2025                  |
|         | Customer Minutes                         | 848,684  |                        |                      |                          |
|         | Customers Affected                       | 11,942   |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b>  |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | Repair equipment failure                 |          |                        | Complete             | Nov-24                   |
|         | Repair substation equipment              |          |                        | Complete             | Feb-25                   |
|         | Repair line failure                      |          |                        | Complete             | Nov-24                   |
|         | Forced outage to repair damage from tree |          |                        | Complete             | Apr-25                   |
|         |  |          |                        |                      |                          |
|         |  |          |                        |                      |                          |
|         |  |          |                        |                      |                          |
| Rank    | Substation                               | Circuit  | District               | Customers            | Outages                  |
| 23      | Laurel Lake Sub Tran                     | 00448-65 | Montrose               | 209                  | 9                        |
|         | <b>Reliability</b>                       |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                             | 1.41     | Ice                    | 96%                  | Q4 2024                  |
|         | SAIDI                                    | 3,983.32 | Line Failure           | 3%                   | Q1 2025                  |
|         | SAIFI                                    | 2.17     | Trees Off Row-Tree     | 1%                   | Q2 2025                  |
|         | CAIDI                                    | 1,837.78 | All Other              | 0%                   | Q3 2025                  |
|         | Customer Minutes                         | 832,514  |                        |                      |                          |
|         | Customers Affected                       | 453      |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b>  |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | PARC Tripsaver                           |          |                        | Complete             | Sep-25                   |
|         |  |          |                        |                      |                          |
|         |  |          |                        |                      |                          |
|         |  |          |                        |                      |                          |
|         |  |          |                        |                      |                          |
| Rank    | Substation                               | Circuit  | District               | Customers            | Outages                  |
| 24      | N Meshoppen Tran                         | 00437-65 | Montrose               | 518                  | 44                       |
|         | <b>Reliability</b>                       |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                             | 1.30     | Ice                    | 76%                  | Q4 2024                  |
|         | SAIDI                                    | 1,484.27 | Trees Off Row-Tree     | 13%                  | Q1 2025                  |
|         | SAIFI                                    | 2.31     | Wind                   | 5%                   | Q3 2025                  |
|         | CAIDI                                    | 642.31   | All Other              | 5%                   |                          |
|         | Customer Minutes                         | 768,851  |                        |                      |                          |
|         | Customers Affected                       | 1,197    |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b>  |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | PARC tripsaver installation              |          |                        | To Be Completed 2025 | 50%                      |
|         |  |          |                        |                      |                          |
|         |  |          |                        |                      |                          |

| Penelec                     |   |          |                        |               |                          |
|-----------------------------|---|----------|------------------------|---------------|--------------------------|
| Rank                        | Substation                              | Circuit  | District               | Customers     | Outages                  |
| 25                          | Two Mile                                | 00127-42 | Bradford               | 1,318         | 25                       |
|                             | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|                             | SAIDI Impact                            | 1.29     | Equipment Failure      | 87%           | Q3 2025                  |
|                             | SAIDI                                   | 579.03   | Vehicle                | 9%            |                          |
|                             | SAIFI                                   | 2.10     | Trees Off Row-Tree     | 1%            |                          |
|                             | CAIDI                                   | 276.11   | All Other              | 2%            |                          |
|                             | Customer Minutes                        | 763,156  |                        |               |                          |
|                             | Customers Affected                      | 2,764    |                        |               |                          |
|                             | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b> | <b>Progress</b>          |
|                             | Repair equipment failure                |          |                        | Complete      | Jul-25                   |
|                             | Overhead circuit inspection             |          |                        | Complete      | Sep-25                   |
|                             |   |          |                        |               |                          |
|                             |   |          |                        |               |                          |
|                             |   |          |                        |               |                          |
| Rank                        | Substation                              | Circuit  | District               | Customers     | Outages                  |
| 26                          | Pennmar                                 | 00002-12 | Somerset               | 896           | 31                       |
|                             | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|                             | SAIDI Impact                            | 1.25     | Trees Off Row-Tree     | 71%           | Q2 2025                  |
|                             | SAIDI                                   | 824.66   | Forced Outage          | 11%           | Q3 2025                  |
|                             | SAIFI                                   | 3.62     | Trees - Sec/Service    | 11%           |                          |
|                             | CAIDI                                   | 227.77   | All Other              | 8%            |                          |
|                             | Customer Minutes                        | 738,891  |                        |               |                          |
|                             | Customers Affected                      | 3,244    |                        |               |                          |
|                             | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b> | <b>Progress</b>          |
|                             | On cycle tree trimming                  |          |                        | Complete      | Oct-24                   |
|                             |   |          |                        |               |                          |
|                             |   |          |                        |               |                          |
|                             |   |          |                        |               |                          |
|                             |   |          |                        |               |                          |
| Rank                        | Substation                              | Circuit  | District               | Customers     | Outages                  |
| 27                          | Green Garden                            | 00536-31 | Erie                   | 870           | 18                       |
|                             | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|                             | SAIDI Impact                            | 1.19     | Line Failure           | 86%           | Q3 2025                  |
|                             | SAIDI                                   | 811.03   | Vehicle                | 8%            |                          |
|                             | SAIFI                                   | 2.44     | Unknown                | 3%            |                          |
|                             | CAIDI                                   | 332.36   | All Other              | 3%            |                          |
|                             | Customer Minutes                        | 705,594  |                        |               |                          |
|                             | Customers Affected                      | 2,123    |                        |               |                          |
|                             | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b> | <b>Progress</b>          |
|                             | Repair burnt jumper                     |          |                        | Complete      | Jul-25                   |
| Overhead circuit inspection |   |          | Complete               | Sep-25        |                          |



| Penelec |   |          |                        |                      |                          |
|---------|---|----------|------------------------|----------------------|--------------------------|
| Rank    | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 31      | Hooversville                            | 00019-12 | Somerset               | 1,651                | 61                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 1.12     | Line Failure           | 41%                  | Q4 2024                  |
|         | SAIDI                                   | 399.48   | Unknown                | 36%                  | Q1 2025                  |
|         | SAIFI                                   | 2.66     | Trees Off Row-Tree     | 14%                  | Q2 2025                  |
|         | CAIDI                                   | 150.41   | All Other              | 9%                   | Q3 2025                  |
|         | Customer Minutes                        | 659,537  |                        |                      |                          |
|         | Customers Affected                      | 4,385    |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | On cycle tree trimming                  |          |                        | To Be Completed 2025 | 99%                      |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
| Rank    | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 32      | Philipsburg                             | 00162-22 | Philipsburg            | 2,797                | 58                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 1.09     | Trees Off Row-Tree     | 65%                  | Q4 2024                  |
|         | SAIDI                                   | 231.11   | Equipment Failure      | 17%                  | Q1 2025                  |
|         | SAIFI                                   | 2.26     | Vehicle                | 7%                   | Q2 2025                  |
|         | CAIDI                                   | 102.41   | All Other              | 11%                  | Q3 2025                  |
|         | Customer Minutes                        | 646,415  |                        |                      |                          |
|         | Customers Affected                      | 6,312    |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | Repair damage caused by a tree          |          |                        | Complete             | Dec-24                   |
|         | Overhead circuit inspection             |          |                        | Complete             | May-25                   |
|         | Underground circuit inspection          |          |                        | Complete             | May-25                   |
|         | LTIIP - circuit rehab                   |          |                        | Complete             | Aug-25                   |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
| Rank    | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 33      | Bradford South                          | 00106-42 | Bradford               | 1,217                | 23                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 1.07     | Trees Off Row-Tree     | 78%                  | Q1 2025                  |
|         | SAIDI                                   | 519.70   | Line Failure           | 11%                  | Q2 2025                  |
|         | SAIFI                                   | 3.10     | Unknown                | 7%                   | Q3 2025                  |
|         | CAIDI                                   | 167.45   | All Other              | 4%                   |                          |
|         | Customer Minutes                        | 632,473  |                        |                      |                          |
|         | Customers Affected                      | 3,777    |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | Repair damage caused by trees           |          |                        | Complete             | Feb-25                   |
|         | Repair damage caused by off ROW trees   |          |                        | Complete             | Apr-25                   |
|         | Overhead circuit inspection             |          |                        | Complete             | Sep-25                   |
|         | Underground circuit inspection          |          |                        | Complete             | Sep-25                   |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |

| Penelec |   |            |                        |               |                          |
|---------|---|------------|------------------------|---------------|--------------------------|
| Rank    | Substation                                | Circuit    | District               | Customers     | Outages                  |
| 34      | East Hickory                              | 00201-41   | Warren                 | 333           | 20                       |
|         | <b>Reliability</b>                        |            | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|         | SAIDI Impact                              | 1.04       | Trees Off Row-Tree     | 75%           | Q4 2024                  |
|         | SAIDI                                     | 1,850.96   | Line Failure           | 15%           | Q1 2025                  |
|         | SAIFI                                     | 10.18      | Unknown                | 9%            | Q2 2025                  |
|         | CAIDI                                     | 181.82     | All Other              | 1%            | Q3 2025                  |
|         | Customer Minutes                          | 616,371    |                        |               |                          |
|         | Customers Affected                        | 3,390      |                        |               |                          |
|         | <b>Remedial Action Planned or Taken</b>   |            |                        | <b>Status</b> | <b>Progress</b>          |
|         | Repair damage caused by off ROW trees     |            |                        | Complete      | Dec-24                   |
|         | Repair damage caused by off ROW trees     |            |                        | Complete      | May-25                   |
|         | Overhead Line Rehab                       |            |                        | Complete      | Sep-25                   |
|         | Overhead circuit inspection               |            |                        | Complete      | Aug-25                   |
|         |   |            |                        |               |                          |
|         |   |            |                        |               |                          |
| Rank    | Substation                                | Circuit    | District               | Customers     | Outages                  |
| 35      | N Meshoppen Tran                          | 00531-65   | Montrose               | 444           | 52                       |
|         | <b>Reliability</b>                        |            | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|         | SAIDI Impact                              | 1.03       | Equipment Failure      | 39%           | Q4 2024                  |
|         | SAIDI                                     | 1,365.93   | Ice                    | 34%           | Q1 2025                  |
|         | SAIFI                                     | 3.00       | Line Failure           | 14%           | Q2 2025                  |
|         | CAIDI                                     | 455.65     | All Other              | 12%           | Q3 2025                  |
|         | Customer Minutes                          | 606,474    |                        |               |                          |
|         | Customers Affected                        | 1,331      |                        |               |                          |
|         | <b>Remedial Action Planned or Taken</b>   |            |                        | <b>Status</b> | <b>Progress</b>          |
|         | PARC tripsaver installation               |            |                        | Complete      | Sep-25                   |
|         |   |            |                        |               |                          |
|         |   |            |                        |               |                          |
|         |   |            |                        |               |                          |
|         | Rank                                      | Substation | Circuit                | District      | Customers                |
| 36      | Piney                                     | 00523-51   | Oil City               | 1,547         | 49                       |
|         | <b>Reliability</b>                        |            | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|         | SAIDI Impact                              | 0.98       | Trees Off Row-Tree     | 46%           | Q4 2024                  |
|         | SAIDI                                     | 373.03     | Equipment Failure      | 16%           | Q1 2025                  |
|         | SAIFI                                     | 2.98       | Forced Outage          | 16%           | Q2 2025                  |
|         | CAIDI                                     | 125.18     | All Other              | 22%           | Q3 2025                  |
|         | Customer Minutes                          | 577,081    |                        |               |                          |
|         | Customers Affected                        | 4,610      |                        |               |                          |
|         | <b>Remedial Action Planned or Taken</b>   |            |                        | <b>Status</b> | <b>Progress</b>          |
|         | Tripsaver deployment at one site          |            |                        | Complete      | Nov-24                   |
|         | Repair damage caused by equipment failure |            |                        | Complete      | Jan-25                   |
|         | LTIIIP - install new bridge switch        |            |                        | Complete      | Sep-25                   |
|         |   |            |                        |               |                          |
|         |   |            |                        |               |                          |

| Penelec |   |          |                        |                      |                          |
|---------|---|----------|------------------------|----------------------|--------------------------|
| Rank    | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 37      | Tunkhannock                             | 00695-65 | Montrose               | 554                  | 22                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.98     | Ice                    | 40%                  | Q2 2025                  |
|         | SAIDI                                   | 1,041.12 | Unknown                | 31%                  | Q3 2025                  |
|         | SAIFI                                   | 2.64     | Line Failure           | 23%                  |                          |
|         | CAIDI                                   | 395.05   | All Other              | 6%                   |                          |
|         | Customer Minutes                        | 576,780  |                        |                      |                          |
|         | Customers Affected                      | 1,460    |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | PARC tripsaver installation             |          |                        | To Be Completed 2025 | 50%                      |
|         | LTIIIP - replace sectionalizer          |          |                        | To Be Completed 2025 | 75%                      |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
| Rank    | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 38      | Green Garden                            | 00224-31 | Erie                   | 1,956                | 35                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.96     | Forced Outage          | 50%                  | Q3 2025                  |
|         | SAIDI                                   | 288.94   | Unknown                | 32%                  |                          |
|         | SAIFI                                   | 3.87     | Trees Off Row-Tree     | 17%                  |                          |
|         | CAIDI                                   | 74.63    | All Other              | 2%                   |                          |
|         | Customer Minutes                        | 565,169  |                        |                      |                          |
|         | Customers Affected                      | 7,573    |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | Repair damage caused by a vehicle       |          |                        | Complete             | Sep-25                   |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
| Rank    | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 39      | Millcreek                               | 00052-11 | Johnstown              | 1,041                | 32                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.94     | Trees Off Row-Tree     | 96%                  | Q3 2025                  |
|         | SAIDI                                   | 536.12   | Equipment Failure      | 3%                   |                          |
|         | SAIFI                                   | 1.69     | Lightning              | 1%                   |                          |
|         | CAIDI                                   | 316.74   | All Other              | 1%                   |                          |
|         | Customer Minutes                        | 558,099  |                        |                      |                          |
|         | Customers Affected                      | 1,762    |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | PARC tripsaver installation             |          |                        | To Be Completed 2025 | 50%                      |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |

| Penelec |   |          |                        |               |                          |
|---------|---|----------|------------------------|---------------|--------------------------|
| Rank    | Substation                              | Circuit  | District               | Customers     | Outages                  |
| 40      | Clearfield                              | 00148-21 | Clearfield             | 1,733         | 53                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.94     | Trees Off Row-Tree     | 41%           | Q2 2025                  |
|         | SAIDI                                   | 319.96   | Line Failure           | 33%           | Q3 2025                  |
|         | SAIFI                                   | 3.78     | Wind                   | 14%           |                          |
|         | CAIDI                                   | 84.64    | All Other              | 12%           |                          |
|         | Customer Minutes                        | 554,486  |                        |               |                          |
|         | Customers Affected                      | 6,551    |                        |               |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b> | <b>Progress</b>          |
|         | Underground circuit inspection          |          |                        | Complete      | Apr-25                   |
|         | Overhead circuit inspection             |          |                        | Complete      | May-25                   |
|         | PARC tripsaver installation             |          |                        | Complete      | Sep-25                   |
|         |   |          |                        |               |                          |
|         |   |          |                        |               |                          |
| Rank    | Substation                              | Circuit  | District               | Customers     | Outages                  |
| 41      | North Orwell                            | 00300-61 | Towanda                | 397           | 28                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.93     | Ice                    | 45%           | Q4 2024                  |
|         | SAIDI                                   | 1,390.41 | Line Failure           | 27%           | Q3 2025                  |
|         | SAIFI                                   | 2.84     | Unknown                | 18%           |                          |
|         | CAIDI                                   | 489.79   | All Other              | 10%           |                          |
|         | Customer Minutes                        | 551,992  |                        |               |                          |
|         | Customers Affected                      | 1,127    |                        |               |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b> | <b>Progress</b>          |
|         | Repair line failure                     |          |                        | Complete      | Nov-24                   |
|         | PARC tripsaver installation             |          |                        | Complete      | Sep-25                   |
|         |   |          |                        |               |                          |
|         |   |          |                        |               |                          |
|         |   |          |                        |               |                          |
| Rank    | Substation                              | Circuit  | District               | Customers     | Outages                  |
| 42      | Utica Junction                          | 00318-51 | Oil City               | 860           | 46                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.91     | Line Failure           | 63%           | Q1 2025                  |
|         | SAIDI                                   | 626.56   | Line Failure           | 23%           | Q2 2025                  |
|         | SAIFI                                   | 3.63     | Trees Off Row-Limb     | 5%            | Q3 2025                  |
|         | CAIDI                                   | 172.37   | All Other              | 8%            |                          |
|         | Customer Minutes                        | 538,843  |                        |               |                          |
|         | Customers Affected                      | 3,126    |                        |               |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b> | <b>Progress</b>          |
|         | Repair damage caused by line failure    |          |                        | Complete      | Jan-25                   |
|         | Repair damage caused by off ROW trees   |          |                        | Complete      | Apr-25                   |
|         | Overhead Circuit Inspection             |          |                        | Complete      | Jul-25                   |
|         | Underground circuit inspection          |          |                        | Complete      | Jul-25                   |
|         |   |          |                        |               |                          |
|         |   |          |                        |               |                          |

| Penelec                        |   |          |                        |                      |                          |
|--------------------------------|---|----------|------------------------|----------------------|--------------------------|
| Rank                           | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 43                             | Tionesta                                | 00344-51 | Oil City               | 516                  | 23                       |
|                                | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                                | SAIDI Impact                            | 0.91     | Trees Off Row-Tree     | 66%                  | Q3 2025                  |
|                                | SAIDI                                   | 1,044.00 | Unknown                | 17%                  |                          |
|                                | SAIFI                                   | 4.98     | Line Failure           | 10%                  |                          |
|                                | CAIDI                                   | 209.53   | All Other              | 7%                   |                          |
|                                | Customer Minutes                        | 538,704  |                        |                      |                          |
|                                | Customers Affected                      | 2,571    |                        |                      |                          |
|                                | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|                                | Repair damage caused by trees           |          |                        | Complete             | Aug-25                   |
|                                | PARC tripsaver installation             |          |                        | To Be Completed 2025 | 75%                      |
|                                |   |          |                        |                      |                          |
|                                |   |          |                        |                      |                          |
| Rank                           | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 44                             | Sheridan Street                         | 00226-11 | Johnstown              | 1,082                | 5                        |
|                                | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                                | SAIDI Impact                            | 0.88     | Forced Outage          | 53%                  | Q3 2025                  |
|                                | SAIDI                                   | 480.88   | Trees Off Row-Tree     | 25%                  |                          |
|                                | SAIFI                                   | 1.92     | Vehicle                | 21%                  |                          |
|                                | CAIDI                                   | 250.87   | All Other              | 1%                   |                          |
|                                | Customer Minutes                        | 520,310  |                        |                      |                          |
|                                | Customers Affected                      | 2,074    |                        |                      |                          |
|                                | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|                                | ESS work requests                       |          |                        | Complete             | Feb-25                   |
|                                |   |          |                        |                      |                          |
|                                |   |          |                        |                      |                          |
|                                |   |          |                        |                      |                          |
| Rank                           | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 45                             | Brookville                              | 00125-23 | Dubois                 | 635                  | 36                       |
|                                | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                                | SAIDI Impact                            | 0.88     | Trees Off Row-Tree     | 67%                  | Q4 2024                  |
|                                | SAIDI                                   | 816.70   | Vehicle                | 23%                  | Q1 2025                  |
|                                | SAIFI                                   | 3.15     | Equipment Failure      | 4%                   | Q2 2025                  |
|                                | CAIDI                                   | 259.17   | All Other              | 5%                   | Q3 2025                  |
|                                | Customer Minutes                        | 518,606  |                        |                      |                          |
|                                | Customers Affected                      | 2,001    |                        |                      |                          |
|                                | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|                                | Repair line failure                     |          |                        | Complete             | Nov-24                   |
|                                | Repair damage caused by a tree          |          |                        | Complete             | Nov-24                   |
|                                | On cycle tree trimming                  |          |                        | Complete             | Mar-25                   |
| Underground circuit inspection |   |          | Complete               | Apr-25               |                          |
| Overhead circuit inspection    |   |          | Complete               | May-25               |                          |
|                                |   |          |                        |                      |                          |

| Penelec                     |   |          |                        |                      |                          |
|-----------------------------|---|----------|------------------------|----------------------|--------------------------|
| Rank                        | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 46                          | Philipsburg                             | 00161-22 | Philipsburg            | 775                  | 34                       |
|                             | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                             | SAIDI Impact                            | 0.87     | Trees Off Row-Tree     | 58%                  | Q3 2025                  |
|                             | SAIDI                                   | 665.09   | Forced Outage          | 15%                  |                          |
|                             | SAIFI                                   | 2.77     | Equipment Failure      | 12%                  |                          |
|                             | CAIDI                                   | 239.96   | All Other              | 15%                  |                          |
|                             | Customer Minutes                        | 515,444  |                        |                      |                          |
|                             | Customers Affected                      | 2,148    |                        |                      |                          |
|                             | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|                             | PARC tripsaver installation             |          |                        | To Be Completed 2025 | 50%                      |
|                             |   |          |                        |                      |                          |
|                             |   |          |                        |                      |                          |
| Rank                        | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 47                          | Erie South                              | 00259-31 | Erie                   | 2,713                | 110                      |
|                             | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                             | SAIDI Impact                            | 0.83     | Trees Off Row-Tree     | 34%                  | Q4 2024                  |
|                             | SAIDI                                   | 181.05   | Unknown                | 26%                  | Q1 2025                  |
|                             | SAIFI                                   | 2.29     | Equipment Failure      | 21%                  | Q2 2025                  |
|                             | CAIDI                                   | 78.93    | All Other              | 19%                  | Q3 2025                  |
|                             | Customer Minutes                        | 491,188  |                        |                      |                          |
|                             | Customers Affected                      | 6,223    |                        |                      |                          |
|                             | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|                             | Remove tree and reset pole              |          |                        | Complete             | Dec-24                   |
|                             | Repair damage caused by a tree          |          |                        | Complete             | Feb-25                   |
|                             | Repair majore damage caused by trees    |          |                        | Complete             | Jun-25                   |
|                             | Replace insulator                       |          |                        | Complete             | Jan-25                   |
|                             | Repair damaged UG cable                 |          |                        | Complete             | Sep-25                   |
| Overhead circuit inspection |   |          | Complete               | Sep-25               |                          |
|                             |   |          |                        |                      |                          |
|                             |   |          |                        |                      |                          |
| Rank                        | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 48                          | Lenox                                   | 00757-65 | Montrose               | 113                  | 6                        |
|                             | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                             | SAIDI Impact                            | 0.82     | Trees Off Row-Tree     | 95%                  | Q4 2024                  |
|                             | SAIDI                                   | 4,274.85 | Line Failure           | 3%                   | Q1 2025                  |
|                             | SAIFI                                   | 2.11     | Unknown                | 1%                   | Q2 2025                  |
|                             | CAIDI                                   | 2,029.66 | All Other              | 1%                   | Q3 2025                  |
|                             | Customer Minutes                        | 483,058  |                        |                      |                          |
|                             | Customers Affected                      | 238      |                        |                      |                          |
|                             | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|                             | Overhead circuit inspection             |          |                        | Complete             | May-25                   |
|                             |   |          |                        |                      |                          |
|                             |   |          |                        |                      |                          |
|                             |   |          |                        |                      |                          |

| Penelec |   |          |                        |                      |                          |
|---------|---|----------|------------------------|----------------------|--------------------------|
| Rank    | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 49      | Marienville                             | 00327-51 | Oil City               | 761                  | 36                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.81     | Trees Off Row-Tree     | 59%                  | Q3 2025                  |
|         | SAIDI                                   | 628.75   | Unknown                | 23%                  |                          |
|         | SAIFI                                   | 2.02     | Equipment Failure      | 11%                  |                          |
|         | CAIDI                                   | 311.91   | All Other              | 6%                   |                          |
|         | Customer Minutes                        | 478,477  |                        |                      |                          |
|         | Customers Affected                      | 1,534    |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | Repair damage caused by trees           |          |                        | Complete             | Jul-25                   |
|         | On cycle tree trimming                  |          |                        | To Be Completed 2025 | 84%                      |
|         | Overhead circuit inspection             |          |                        | Complete             | Jun-25                   |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
| Rank    | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 50      | Lenox                                   | 00434-65 | Montrose               | 287                  | 11                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.80     | Ice                    | 80%                  | Q1 2025                  |
|         | SAIDI                                   | 1,648.88 | Trees Off Row-Limb     | 12%                  | Q3 2025                  |
|         | SAIFI                                   | 1.80     | Line Failure           | 4%                   |                          |
|         | CAIDI                                   | 917.11   | All Other              | 4%                   |                          |
|         | Customer Minutes                        | 473,229  |                        |                      |                          |
|         | Customers Affected                      | 516      |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | Overhead inspection repairs             |          |                        | Complete             | Feb-25                   |
|         | PARC tripsaver installation             |          |                        | Complete             | Sep-25                   |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
| Rank    | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 51      | Ehrenfeld Jackson                       | 00306-72 | Altoona                | 397                  | 14                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.79     | Trees Off Row-Tree     | 73%                  | Q3 2025                  |
|         | SAIDI                                   | 1,179.43 | Trees Off Row-Limb     | 26%                  |                          |
|         | SAIFI                                   | 2.59     | Vehicle                | 1%                   |                          |
|         | CAIDI                                   | 455.04   | All Other              | 1%                   |                          |
|         | Customer Minutes                        | 468,235  |                        |                      |                          |
|         | Customers Affected                      | 1,029    |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | Overhead circuit inspection             |          |                        | Complete             | May-25                   |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |

| Penelec |   |            |                        |               |                          |
|---------|---|------------|------------------------|---------------|--------------------------|
| Rank    | Substation                              | Circuit    | District               | Customers     | Outages                  |
| 52      | North Warren                            | 00207-41   | Warren                 | 1,404         | 55                       |
|         | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.79       | Trees Off Row-Tree     | 73%           | Q3 2025                  |
|         | SAIDI                                   | 332.84     | Forced Outage          | 12%           |                          |
|         | SAIFI                                   | 2.19       | Line Failure           | 5%            |                          |
|         | CAIDI                                   | 151.92     | All Other              | 10%           |                          |
|         | Customer Minutes                        | 467,310    |                        |               |                          |
|         | Customers Affected                      | 3,076      |                        |               |                          |
|         | <b>Remedial Action Planned or Taken</b> |            |                        | <b>Status</b> | <b>Progress</b>          |
|         | Repair damage caused by trees           |            |                        | Complete      | May-25                   |
|         | LTIIIP - install tripsaver              |            |                        | Complete      | Feb-25                   |
|         | LTIIIP - install tripsaver              |            |                        | Complete      | May-25                   |
|         | Overhead circuit inspection             |            |                        | Complete      | Aug-25                   |
|         | Rank                                    | Substation | Circuit                | District      | Customers                |
| 53      | Ashville                                | 00061-71   | Altoona                | 501           | 14                       |
|         | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.77       | Trees Off Row-Tree     | 77%           | Q2 2025                  |
|         | SAIDI                                   | 905.40     | Forced Outage          | 17%           | Q3 2025                  |
|         | SAIFI                                   | 1.71       | Vehicle                | 5%            |                          |
|         | CAIDI                                   | 529.29     | All Other              | 0%            |                          |
|         | Customer Minutes                        | 453,604    |                        |               |                          |
|         | Customers Affected                      | 857        |                        |               |                          |
|         | <b>Remedial Action Planned or Taken</b> |            |                        | <b>Status</b> | <b>Progress</b>          |
|         | Overhead circuit inspection             |            |                        | Complete      | Apr-25                   |
|         | Underground circuit inspection          |            |                        | Complete      | Apr-25                   |
|         |   |            |                        |               |                          |
|         |   |            |                        |               |                          |
|         |   |            |                        |               |                          |
| Rank    | Substation                              | Circuit    | District               | Customers     | Outages                  |
| 54      | Montrose                                | 00457-65   | Montrose               | 686           | 42                       |
|         | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.77       | Ice                    | 51%           | Q3 2025                  |
|         | SAIDI                                   | 660.64     | Trees Off Row-Tree     | 26%           |                          |
|         | SAIFI                                   | 2.23       | Line Failure           | 13%           |                          |
|         | CAIDI                                   | 296.79     | All Other              | 10%           |                          |
|         | Customer Minutes                        | 453,201    |                        |               |                          |
|         | Customers Affected                      | 1,527      |                        |               |                          |
|         | <b>Remedial Action Planned or Taken</b> |            |                        | <b>Status</b> | <b>Progress</b>          |
|         | Overhead circuit inspection             |            |                        | Complete      | May-25                   |
|         |   |            |                        |               |                          |
|         |   |            |                        |               |                          |
|         |   |            |                        |               |                          |
|         |   |            |                        |               |                          |

| Penelec                              |   |          |                        |                      |                          |
|--------------------------------------|---|----------|------------------------|----------------------|--------------------------|
| Rank                                 | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 55                                   | Greenwood                               | 00001-71 | Altoona                | 1,147                | 19                       |
|                                      | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                                      | SAIDI Impact                            | 0.76     | Equipment Failure      | 42%                  | Q3 2025                  |
|                                      | SAIDI                                   | 392.51   | Trees Off Row-Tree     | 40%                  |                          |
|                                      | SAIFI                                   | 3.34     | Trees Off Row-Limb     | 15%                  |                          |
|                                      | CAIDI                                   | 117.43   | All Other              | 3%                   |                          |
|                                      | Customer Minutes                        | 450,214  |                        |                      |                          |
|                                      | Customers Affected                      | 3,834    |                        |                      |                          |
|                                      | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|                                      | PARC tripsaver installation             |          |                        | To Be Completed 2025 | 50%                      |
|                                      |   |          |                        |                      |                          |
|                                      |   |          |                        |                      |                          |
|                                      |   |          |                        |                      |                          |
| Rank                                 | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 56                                   | French Road                             | 00222-31 | Erie                   | 1,691                | 27                       |
|                                      | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                                      | SAIDI Impact                            | 0.75     | Line Failure           | 66%                  | Q1 2025                  |
|                                      | SAIDI                                   | 264.03   | Equipment Failure      | 23%                  | Q3 2025                  |
|                                      | SAIFI                                   | 4.10     | Unknown                | 8%                   |                          |
|                                      | CAIDI                                   | 64.46    | All Other              | 3%                   |                          |
|                                      | Customer Minutes                        | 446,478  |                        |                      |                          |
|                                      | Customers Affected                      | 6,926    |                        |                      |                          |
|                                      | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|                                      | Repair damaged equipment                |          |                        | Complete             | Feb-25                   |
|                                      | Repair line failure                     |          |                        | Complete             | Mar-25                   |
| Forced outage to replace transformer |   |          | Complete               | Jul-25               |                          |
| Overhead circuit inspection          |   |          | Complete               | Sep-25               |                          |
|                                      |   |          |                        |                      |                          |
|                                      |   |          |                        |                      |                          |
|                                      |   |          |                        |                      |                          |
| Rank                                 | Substation                              | Circuit  | District               | Customers            | Outages                  |
| 57                                   | Mansfield                               | 00558-63 | Mansfield Pa           | 882                  | 40                       |
|                                      | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                                      | SAIDI Impact                            | 0.75     | Equipment Failure      | 59%                  | Q3 2025                  |
|                                      | SAIDI                                   | 503.43   | Trees Off Row-Tree     | 26%                  |                          |
|                                      | SAIFI                                   | 2.02     | Ice                    | 8%                   |                          |
|                                      | CAIDI                                   | 249.73   | All Other              | 6%                   |                          |
|                                      | Customer Minutes                        | 444,023  |                        |                      |                          |
|                                      | Customers Affected                      | 1,778    |                        |                      |                          |
|                                      | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b>        | <b>Progress</b>          |
|                                      | PARC tripsaver installation             |          |                        | To Be Completed 2025 | 50%                      |
|                                      | LTIIIP - replace recloser               |          |                        | To Be Completed 2025 | 75%                      |
|                                      |   |          |                        |                      |                          |
|                                      |   |          |                        |                      |                          |
|                                      |   |          |                        |                      |                          |
|                                      |   |          |                        |                      |                          |

| Penelec |   |          |                        |                      |                          |
|---------|---|----------|------------------------|----------------------|--------------------------|
| Rank    | Substation  | Circuit  | District               | Customers            | Outages                  |
| 58      | Platea  | 00432-34 | Erie                   | 645                  | 46                       |
|         | <b>Reliability</b>  |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact  | 0.75     | Trees Off Row-Tree     | 86%                  | Q4 2024                  |
|         | SAIDI   | 686.47   | Vehicle                | 4%                   | Q1 2025                  |
|         | SAIFI   | 2.00     | Unknown                | 3%                   | Q2 2025                  |
|         | CAIDI   | 342.44   | All Other              | 7%                   | Q3 2025                  |
|         | Customer Minutes  | 442,771  |                        |                      |                          |
|         | Customers Affected  | 1,293    |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b>                   |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | Remove tree and make repairs                              |          |                        | Complete             | Dec-24                   |
|         | Repair damage caused by a tree                            |          |                        | Complete             | Feb-25                   |
|         | Repair damage caused by truck pulling down wire and poles |          |                        | Complete             | Jun-25                   |
|         |   |          |                        |                      |                          |
| Rank    | Substation  | Circuit  | District               | Customers            | Outages                  |
| 59      | Dubois  | 00124-23 | Dubois                 | 2,092                | 31                       |
|         | <b>Reliability</b>  |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact  | 0.74     | Trees Off Row-Tree     | 80%                  | Q2 2025                  |
|         | SAIDI   | 209.40   | Line Failure           | 10%                  | Q3 2025                  |
|         | SAIFI   | 2.70     | Equipment Failure      | 6%                   |                          |
|         | CAIDI   | 77.63    | All Other              | 4%                   |                          |
|         | Customer Minutes  | 438,058  |                        |                      |                          |
|         | Customers Affected  | 5,643    |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b>                   |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | PARC tripsaver installation                               |          |                        | To Be Completed 2025 | 50%                      |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
| Rank    | Substation  | Circuit  | District               | Customers            | Outages                  |
| 60      | New Albany Sw St  | 00570-62 | Towanda                | 149                  | 13                       |
|         | <b>Reliability</b>  |          | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|         | SAIDI Impact  | 0.74     | Equipment Failure      | 46%                  | Q3 2025                  |
|         | SAIDI   | 2,924.19 | Trees Off Row-Tree     | 37%                  |                          |
|         | SAIFI   | 3.91     | Ice                    | 17%                  |                          |
|         | CAIDI   | 747.35   | All Other              | 0%                   |                          |
|         | Customer Minutes  | 435,704  |                        |                      |                          |
|         | Customers Affected  | 583      |                        |                      |                          |
|         | <b>Remedial Action Planned or Taken</b>                   |          |                        | <b>Status</b>        | <b>Progress</b>          |
|         | Overhead circuit inspection                               |          |                        | Complete             | Aug-25                   |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |
|         |   |          |                        |                      |                          |

| Penelec |   |          |                        |               |                          |
|---------|---|----------|------------------------|---------------|--------------------------|
| Rank    | Substation                              | Circuit  | District               | Customers     | Outages                  |
| 61      | Union City                              | 00208-43 | Erie                   | 1,615         | 61                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.72     | Trees Off Row-Tree     | 40%           | Q4 2024                  |
|         | SAIDI                                   | 263.66   | Equipment Failure      | 37%           | Q1 2025                  |
|         | SAIFI                                   | 4.76     | Vehicle                | 9%            | Q2 2025                  |
|         | CAIDI                                   | 55.38    | All Other              | 14%           | Q3 2025                  |
|         | Customer Minutes                        | 425,818  |                        |               |                          |
|         | Customers Affected                      | 7,689    |                        |               |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b> | <b>Progress</b>          |
|         | Repair damage caused by a tree          |          |                        | Complete      | Mar-25                   |
|         | Replace failed insulator                |          |                        | Complete      | Jan-25                   |
|         |   |          |                        |               |                          |
|         |   |          |                        |               |                          |
| Rank    | Substation                              | Circuit  | District               | Customers     | Outages                  |
| 62      | Logan                                   | 00700-81 | Lewistown              | 1,020         | 38                       |
|         | <b>Reliability</b>                      |          | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|         | SAIDI Impact                            | 0.71     | Trees Off Row-Tree     | 70%           | Q2 2025                  |
|         | SAIDI                                   | 412.50   | Lightning              | 11%           | Q3 2025                  |
|         | SAIFI                                   | 2.61     | Line Failure           | 10%           |                          |
|         | CAIDI                                   | 158.24   | All Other              | 8%            |                          |
|         | Customer Minutes                        | 420,750  |                        |               |                          |
|         | Customers Affected                      | 2,659    |                        |               |                          |
|         | <b>Remedial Action Planned or Taken</b> |          |                        | <b>Status</b> | <b>Progress</b>          |
|         | Restore outage caused by lightning      |          |                        | Complete      | Apr-25                   |
|         | Overhead Circuit Inspection             |          |                        | Complete      | Apr-25                   |
|         | Underground circuit inspection          |          |                        | Complete      | Apr-25                   |
|         | Repair damage caused by tree            |          |                        | Complete      | May-25                   |
|         |   |          |                        |               |                          |
|         |   |          |                        |               |                          |

| <b>Penelec</b>   |                |                |                |                |               |
|--|----------------|----------------|----------------|----------------|---------------|
| <b>Unranked circuits appearing 2 or more quarters in the last 4 quarters</b> |                |                |                |                |               |
| <b>Substation</b>  | <b>Circuit</b> | <b>4Q 2024</b> | <b>1Q 2025</b> | <b>2Q 2025</b> | <b>Q32025</b> |
| Lowell Avenue  | 00518-31       | X              |                | X              |               |
| Madera   | 00166-22       | X              | X              | X              |               |
| Marienville  | 00328-51       | X              |                | X              |               |
| Meyersdale North   | 00022-12       | X              | X              | X              |               |
| Natl Forge Sw Sta  | 00577-41       | X              | X              | X              |               |
| North Towanda  | 00521-62       | X              |                | X              |               |
| Oxbow  | 00555-65       | X              | X              | X              |               |
| Russell Hill   | 00282-65       | X              | X              | X              |               |
| Salix  | 00070-11       | X              | X              |                |               |
| Saxton   | 00624-73       | X              | X              |                |               |
| Shippensburg 1   | 00630-83       | X              | X              | X              |               |
| Union City   | 00208-43       | X              | X              | X              |               |
| Union City   | 00239-43       | X              | X              |                |               |
| Buckeye Blaine   | 00136-83       | X              | X              |                |               |
| Walnut Street  | 00522-31       | X              | X              |                |               |
| East Pike  | 00094-13       | X              | X              | X              |               |
| Ansonia  | 00740-63       | X              | X              | X              |               |
| Osceola  | 00318-63       | X              | X              | X              |               |
| Osceola  | 00562-63       | X              | X              | X              |               |
| Eagles Mere  | 00686-62       | X              | X              | X              |               |
| Brookville West  | 00121-23       | X              | X              | X              |               |
| Dushore  | 00528-62       | X              | X              | X              |               |
| Laporte  | 00772-62       | X              | X              |                |               |
| Franklin Forks   | 00737-65       | X              | X              |                |               |

| <b>Penelec</b>   |                |   |  |  |
|--|----------------|---|--|--|
| <b>Unranked circuits with remedial actions scheduled to be or recently completed</b> |                |   |  |  |
| <b>Substation</b>  | <b>Circuit</b> | <b>Remedial Action Planned or Taken</b> | <b>Status of Remedial Work Completed</b> | <b>Progress of Remedial Work or Date Completed</b> |
| Shippensburg 1   | 00630-83       | Underground circuit inspection          | Complete                                 | Aug-25   |
| Eagles Mere  | 00686-62       | On cycle tree trimming                  | To be completed 2025                     | 99%  |
| Ansonia  | 00740-63       | LTIIIP - line rehab                     | To be completed 2025                     | 50%  |
| Laporte  | 00772-62       | PARC pole replacement                   | Complete                                 | Sep-25   |
| Meyersdale   | 00022-12       | PARC tripsaver installation             | To be completed 2025                     | 50%  |
| Salix  | 00070-11       | PARC tripsaver installation             | Complete                                 | Sep-25   |
| Brookville West  | 00121-23       | PARC tripsaver installation             | Complete                                 | Sep-25   |
| Madera   | 00166-22       | PARC tripsaver installation             | To be completed 2025                     | 50%  |
| Madera   | 00166-22       | LTIIIP - remote sectionalizing          | To be completed 2025                     | 50%  |
| Blossburg  | 00310-63       | LTIIIP - line rehab                     | To be completed 2025                     | 50%  |
| Natl Forge Sw Sta  | 00577-41       | LTIIIP - replace recloser               | To be completed 2025                     | 75%  |
| Saxton   | 00624-73       | LTIIIP - circuit protection             | To be completed 2025                     | 50%  |
| Curryville   | 00644-71       | LTIIIP - remote sectionalizing          | To be completed 2025                     | 75%  |
| Benton Af Sub  | 00775-62       | On cycle tree trimming                  | Complete                                 | Jul-25   |
| Dubois   | 00124-23       | PARC tripsaver installation             | To be completed 2025                     | 99%  |
| Dubois   | 00137-23       | LTIIIP - circuit protection             | To be completed 2025                     | 50%  |
| Utica Junction   | 00318-52       | Underground circuit inspection          | Complete                                 | Jul-25   |
| Osceola  | 00318-63       | LTIIIP - line rehab                     | To be completed 2025                     | 50%  |
| Eagles Mere  | 00686-62       | PARC tripsaver installation             | To be completed 2025                     | 50%  |

| Penn Power  |   |                |                        |                      |                          |
|-------------|---|----------------|------------------------|----------------------|--------------------------|
| Rank        | Substation                              | Circuit        | District               | Customers            | Outages                  |
| 1           | Hartstown                               | W-126          | Clark                  | 2,298                | 75                       |
|             | <b>Reliability</b>                      |                | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|             | SAIDI Impact                            | 5.25           | Trees Off Row-Tree     | 65%                  | Q4 2024                  |
|             | SAIDI                                   | 401.74         | Bird                   | 18%                  | Q1 2025                  |
|             | SAIFI                                   | 1.23           | Equipment Failure      | 9%                   | Q2 2025                  |
|             | CAIDI                                   | 326            | All Other              | 8%                   | Q3 2025                  |
|             | Customer Minutes                        | 923,210        |                        |                      |                          |
|             | Customers Affected                      | 2,829          |                        |                      |                          |
|             | <b>Remedial Action Planned or Taken</b> |                |                        | <b>Status</b>        | <b>Progress</b>          |
|             | PARC tripsaver installation             |                |                        | To be completed 2025 | 75%                      |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
| <b>Rank</b> | <b>Substation</b>                       | <b>Circuit</b> | <b>District</b>        | <b>Customers</b>     | <b>Outages</b>           |
| 2           | Darlington                              | D-536          | Zelienople             | 1,179                | 42                       |
|             | <b>Reliability</b>                      |                | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|             | SAIDI Impact                            | 4.83           | Trees Off Row-Tree     | 93%                  | Q4 2024                  |
|             | SAIDI                                   | 719.37         | Trees On Row           | 3%                   | Q1 2025                  |
|             | SAIFI                                   | 2.84           | Unknown                | 2%                   | Q2 2025                  |
|             | CAIDI                                   | 253            | All Other              | 2%                   | Q3 2025                  |
|             | Customer Minutes                        | 848,142        |                        |                      |                          |
|             | Customers Affected                      | 3,351          |                        |                      |                          |
|             | <b>Remedial Action Planned or Taken</b> |                |                        | <b>Status</b>        | <b>Progress</b>          |
|             | LTIIP - Circuit Improvement             |                |                        | To be completed 2025 | 75%                      |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
| <b>Rank</b> | <b>Substation</b>                       | <b>Circuit</b> | <b>District</b>        | <b>Customers</b>     | <b>Outages</b>           |
| 3           | Canal                                   | W-101          | Clark                  | 1,596                | 46                       |
|             | <b>Reliability</b>                      |                | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|             | SAIDI Impact                            | 3.84           | Trees Off Row-Tree     | 50%                  | Q2 2025                  |
|             | SAIDI                                   | 422.27         | Equipment Failure      | 40%                  | Q3 2025                  |
|             | SAIFI                                   | 4.31           | Animal                 | 3%                   |                          |
|             | CAIDI                                   | 98             | All Other              | 7%                   |                          |
|             | Customer Minutes                        | 673,948        |                        |                      |                          |
|             | Customers Affected                      | 6,877          |                        |                      |                          |
|             | <b>Remedial Action Planned or Taken</b> |                |                        | <b>Status</b>        | <b>Progress</b>          |
|             | LTIIP - Circuit Improvement             |                |                        | Complete             | Sep-25                   |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |
|             |   |                |                        |                      |                          |

| Penn Power |   |         |                        |                      |                          |
|------------|---|---------|------------------------|----------------------|--------------------------|
| Rank       | Substation                              | Circuit | District               | Customers            | Outages                  |
| 4          | Ray Street                              | D-389   | New Castle             | 1,218                | 6                        |
|            | <b>Reliability</b>                      |         | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|            | SAIDI Impact                            | 3.69    | Vehicle                | 100%                 | Q4 2024                  |
|            | SAIDI                                   | 532.88  | Forced Outage          | 0%                   | Q2 2025                  |
|            | SAIFI                                   | 2.23    | Trees - Sec/Service    | 0%                   | Q3 2025                  |
|            | CAIDI                                   | 239     | All Other              | 0%                   |                          |
|            | Customer Minutes                        | 649,046 |                        |                      |                          |
|            | Customers Affected                      | 2,717   |                        |                      |                          |
|            | <b>Remedial Action Planned or Taken</b> |         |                        | <b>Status</b>        | <b>Progress</b>          |
|            | Repair damage caused by a vehicle       |         |                        | Complete             | Apr-25                   |
|            |   |         |                        |                      |                          |
|            |   |         |                        |                      |                          |
| Rank       | Substation                              | Circuit | District               | Customers            | Outages                  |
| 5          | Mercer                                  | W-129   | Clark                  | 1,167                | 47                       |
|            | <b>Reliability</b>                      |         | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|            | SAIDI Impact                            | 3.38    | Trees Off Row-Tree     | 57%                  | Q4 2024                  |
|            | SAIDI                                   | 509.18  | Trees Off Row-Limb     | 17%                  | Q1 2025                  |
|            | SAIFI                                   | 1.71    | Forced Outage          | 8%                   | Q2 2025                  |
|            | CAIDI                                   | 298     | All Other              | 18%                  | Q3 2025                  |
|            | Customer Minutes                        | 594,215 |                        |                      |                          |
|            | Customers Affected                      | 1,994   |                        |                      |                          |
|            | <b>Remedial Action Planned or Taken</b> |         |                        | <b>Status</b>        | <b>Progress</b>          |
|            | PARC tripsaver installation             |         |                        | To be completed 2025 | 50%                      |
|            |   |         |                        |                      |                          |
|            |   |         |                        |                      |                          |
| Rank       | Substation                              | Circuit | District               | Customers            | Outages                  |
| 6          | Seneca                                  | W700    | Zelienople             | 930                  | 51                       |
|            | <b>Reliability</b>                      |         | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|            | SAIDI Impact                            | 3.24    | Trees Off Row-Tree     | 68%                  | Q2 2025                  |
|            | SAIDI                                   | 611.97  | Trees Off Row-Limb     | 18%                  | Q3 2025                  |
|            | SAIFI                                   | 3.14    | Line Failure           | 6%                   |                          |
|            | CAIDI                                   | 195     | All Other              | 9%                   |                          |
|            | Customer Minutes                        | 569,131 |                        |                      |                          |
|            | Customers Affected                      | 2,919   |                        |                      |                          |
|            | <b>Remedial Action Planned or Taken</b> |         |                        | <b>Status</b>        | <b>Progress</b>          |
|            | Overhead circuit inspection             |         |                        | Complete             | Apr-25                   |
|            |   |         |                        |                      |                          |
|            |   |         |                        |                      |                          |

| Penn Power |   |         |                        |               |                          |
|------------|---|---------|------------------------|---------------|--------------------------|
| Rank       | Substation                              | Circuit | District               | Customers     | Outages                  |
| 7          | Castlewood                              | D-325   | New Castle             | 1,129         | 37                       |
|            | <b>Reliability</b>                      |         | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|            | SAIDI Impact                            | 3.02    | Trees Off Row-Tree     | 77%           | Q4 2024                  |
|            | SAIDI                                   | 469.51  | Forced Outage          | 8%            | Q1 2025                  |
|            | SAIFI                                   | 2.31    | Vehicle                | 6%            | Q2 2025                  |
|            | CAIDI                                   | 204     | All Other              | 9%            | Q3 2025                  |
|            | Customer Minutes                        | 530,074 |                        |               |                          |
|            | Customers Affected                      | 2,603   |                        |               |                          |
|            | <b>Remedial Action Planned or Taken</b> |         |                        | <b>Status</b> | <b>Progress</b>          |
|            | Repair damage caused by a tree          |         |                        | Complete      | Jun-25                   |
|            |   |         |                        |               |                          |
|            |   |         |                        |               |                          |
|            |   |         |                        |               |                          |
| Rank       | Substation                              | Circuit | District               | Customers     | Outages                  |
| 8          | Hartstown                               | W-125   | Clark                  | 625           | 22                       |
|            | <b>Reliability</b>                      |         | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|            | SAIDI Impact                            | 3.01    | Unknown                | 85%           | Q2 2025                  |
|            | SAIDI                                   | 847.04  | Trees Off Row-Tree     | 13%           | Q3 2025                  |
|            | SAIFI                                   | 11.98   | Equipment Failure      | 1%            |                          |
|            | CAIDI                                   | 71      | All Other              | 2%            |                          |
|            | Customer Minutes                        | 529,399 |                        |               |                          |
|            | Customers Affected                      | 7,485   |                        |               |                          |
|            | <b>Remedial Action Planned or Taken</b> |         |                        | <b>Status</b> | <b>Progress</b>          |
|            | Cycle Tree Trimming                     |         |                        | Complete      | Jan-25                   |
|            |   |         |                        |               |                          |
|            |   |         |                        |               |                          |
|            |   |         |                        |               |                          |
| Rank       | Substation                              | Circuit | District               | Customers     | Outages                  |
| 9          | Mercer                                  | W-128   | Clark                  | 1,249         | 45                       |
|            | <b>Reliability</b>                      |         | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|            | SAIDI Impact                            | 2.76    | Trees Off Row-Tree     | 70%           | Q3 2025                  |
|            | SAIDI                                   | 388.34  | Line Failure           | 14%           |                          |
|            | SAIFI                                   | 1.13    | Trees Off Row-Limb     | 7%            |                          |
|            | CAIDI                                   | 344     | All Other              | 8%            |                          |
|            | Customer Minutes                        | 485,033 |                        |               |                          |
|            | Customers Affected                      | 1,410   |                        |               |                          |
|            | <b>Remedial Action Planned or Taken</b> |         |                        | <b>Status</b> | <b>Progress</b>          |
|            | LTIIP - Circuit Improvement             |         |                        | Complete      | Sep-25                   |
|            |   |         |                        |               |                          |
|            |   |         |                        |               |                          |
|            |   |         |                        |               |                          |
|            |   |         |                        |               |                          |

| Penn Power |                                  |         |                    |                      |                   |
|------------|----------------------------------|---------|--------------------|----------------------|-------------------|
| Rank       | Substation                       | Circuit | District           | Customers            | Outages           |
| 10         | Jamestown                        | W-161   | Clark              | 758                  | 29                |
|            | Reliability                      |         | Outage by Cause    |                      | Previously Ranked |
|            | SAIDI Impact                     | 2.63    | Trees Off Row-Tree | 70%                  | Q1 2025           |
|            | SAIDI                            | 610.08  | Line Failure       | 11%                  | Q2 2025           |
|            | SAIFI                            | 4.94    | Bird               | 8%                   | Q3 2025           |
|            | CAIDI                            | 123     | All Other          | 11%                  |                   |
|            | Customer Minutes                 | 462,441 |                    |                      |                   |
|            | Customers Affected               | 3,748   |                    |                      |                   |
|            | Remedial Action Planned or Taken |         |                    | Status               | Progress          |
|            | Cycle tree trimming              |         |                    | Complete             | May-25            |
|            | PARC tripsaver installation      |         |                    | To be completed 2025 | 50%               |
|            |                                  |         |                    |                      |                   |
|            |                                  |         |                    |                      |                   |

| <b>Penn Power</b>  |                |                |                |                |               |
|--|----------------|----------------|----------------|----------------|---------------|
| <b>Unranked circuits appearing 2 or more quarters in the last 4 quarters</b> |                |                |                |                |               |
| <b>Substation</b>  | <b>Circuit</b> | <b>4Q 2024</b> | <b>1Q 2025</b> | <b>2Q 2025</b> | <b>Q32025</b> |
| Stoneboro  | W-131          | X              | X              |                |               |
| Mercer   | W-167          | X              | X              |                |               |
| Sharpsville  | W-218          | X              | X              |                |               |
| Chippewa   | D-557          | X              | X              | X              |               |

| <b>Penn Power</b>  |                |   |  |  |
|--|----------------|---|--|--|
| <b>Unranked circuits with remedial actions scheduled to be or recently completed</b> |                |   |  |  |
| <b>Substation</b>  | <b>Circuit</b> | <b>Remedial Action Planned or Taken</b> | <b>Status of Remedial Work Completed</b> | <b>Progress of Remedial Work or Date Completed</b> |
| Koppel   | D-531          | On cycle tree trimming                  | Complete                                 | May-25   |
| Stoneboro  | W-131          | Overhead circuit inspection             | Complete                                 | Aug-25   |
| Mercer   | W-167          | PARC tripsaver installation             | To be completed 2025                     | 50%  |
| Mercer   | W-167          | LTIIIP - circuit improvement            | To be completed 2025                     | 50%  |

| West Penn |   |              |                        |                      |                          |
|-----------|---|--------------|------------------------|----------------------|--------------------------|
| Rank      | Substation                              | Circuit      | District               | Customers            | Outages                  |
| 1         | Rutan                                   | New Freeport | Jefferson              | 736                  | 66                       |
|           | <b>Reliability</b>                      |              | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|           | SAIDI Impact                            | 3.04         | Tree OFF Row- Tree     | 97%                  | Q4 2024                  |
|           | SAIDI                                   | 3,010.96     | Equipment Failure      | 2%                   | Q1 2025                  |
|           | SAIFI                                   | 4.69         | Line Failure           | 0%                   | Q2 2025                  |
|           | CAIDI                                   | 642          | All Other              | 1%                   | Q3 2025                  |
|           | Customer Minutes                        | 2,216,064    |                        |                      |                          |
|           | Customers Affected                      | 3,453        |                        |                      |                          |
|           | <b>Remedial Action Planned or Taken</b> |              |                        | <b>Status</b>        | <b>Progress</b>          |
|           | Cycle tree trimming                     |              |                        | Complete             | Jul-24                   |
|           | Overhead circuit inspection             |              |                        | Complete             | Feb-25                   |
|           |   |              |                        |                      |                          |
|           |   |              |                        |                      |                          |
|           |   |              |                        |                      |                          |
| Rank      | Substation                              | Circuit      | District               | Customers            | Outages                  |
| 2         | Warfordsburg                            | Big Cove     | Mcconnellsburg         | 688                  | 41                       |
|           | <b>Reliability</b>                      |              | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|           | SAIDI Impact                            | 2.39         | Trees Off Row-Tree     | 80%                  | Q2 2025                  |
|           | SAIDI                                   | 2,534.48     | Wind                   | 11%                  | Q3 2025                  |
|           | SAIFI                                   | 2.79         | Bird                   | 4%                   |                          |
|           | CAIDI                                   | 909          | All Other              | 5%                   |                          |
|           | Customer Minutes                        | 1,743,724    |                        |                      |                          |
|           | Customers Affected                      | 1,918        |                        |                      |                          |
|           | <b>Remedial Action Planned or Taken</b> |              |                        | <b>Status</b>        | <b>Progress</b>          |
|           | Overhead circuit inspection             |              |                        | Complete             | Sep-25                   |
|           |   |              |                        |                      |                          |
|           |   |              |                        |                      |                          |
|           |   |              |                        |                      |                          |
|           |   |              |                        |                      |                          |
| Rank      | Substation                              | Circuit      | District               | Customers            | Outages                  |
| 3         | Robbins                                 | Mt Vernon    | Jeannette              | 1,032                | 19                       |
|           | <b>Reliability</b>                      |              | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|           | SAIDI Impact                            | 2.05         | Unknown                | 89%                  | Q2 2025                  |
|           | SAIDI                                   | 1,449.51     | Trees Off Row-Tree     | 6%                   | Q3 2025                  |
|           | SAIFI                                   | 1.52         | Line Failure           | 3%                   |                          |
|           | CAIDI                                   | 955          | All Other              | 2%                   |                          |
|           | Customer Minutes                        | 1,495,897    |                        |                      |                          |
|           | Customers Affected                      | 1,566        |                        |                      |                          |
|           | <b>Remedial Action Planned or Taken</b> |              |                        | <b>Status</b>        | <b>Progress</b>          |
|           | Underground Circuit inspection          |              |                        | To be completed 2025 | 83%                      |
|           |   |              |                        |                      |                          |
|           |   |              |                        |                      |                          |
|           |   |              |                        |                      |                          |
|           |   |              |                        |                      |                          |
|           |   |              |                        |                      |                          |

| West Penn |   |              |                        |           |                          |                 |
|-----------|---|--------------|------------------------|-----------|--------------------------|-----------------|
| Rank      | Substation                              | Circuit      | District               | Customers | Outages                  |                 |
| 4         | Driftwood                               | Driftwood    | St Marys               | 973       | 30                       |                 |
|           | <b>Reliability</b>                      |              | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|           | SAIDI Impact                            | 1.97         | Trees Off Row-Tree     | 89%       | Q1 2025                  |                 |
|           | SAIDI                                   | 1,473.98     | Trees Off Row-Limb     | 10%       | Q2 2025                  |                 |
|           | SAIFI                                   | 2.58         | Trees On Row           | 1%        | Q3 2025                  |                 |
|           | CAIDI                                   | 571          | All Other              | 0%        |                          |                 |
|           | Customer Minutes                        | 1,434,184    |                        |           |                          |                 |
|           | Customers Affected                      | 2,513        |                        |           |                          |                 |
|           | <b>Remedial Action Planned or Taken</b> |              |                        |           | <b>Status</b>            | <b>Progress</b> |
|           | Overhead circuit inspection             |              |                        |           | Complete                 | Mar-25          |
|           | Repair damage caused by trees           |              |                        |           | Complete                 | Mar-25          |
|           |   |              |                        |           |                          |                 |
|           |   |              |                        |           |                          |                 |
| Rank      | Substation                              | Circuit      | District               | Customers | Outages                  |                 |
| 5         | Emmaville                               | Stoney Break | Mcconnellsburg         | 380       | 10                       |                 |
|           | <b>Reliability</b>                      |              | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|           | SAIDI Impact                            | 1.89         | Trees Off Row-Tree     | 100%      | Q2 2025                  |                 |
|           | SAIDI                                   | 3,630.29     | Unknown                | 0%        | Q3 2025                  |                 |
|           | SAIFI                                   | 2.37         | Equipment Failure      | 0%        |                          |                 |
|           | CAIDI                                   | 1,534        | All Other              | 0%        |                          |                 |
|           | Customer Minutes                        | 1,379,509    |                        |           |                          |                 |
|           | Customers Affected                      | 899          |                        |           |                          |                 |
|           | <b>Remedial Action Planned or Taken</b> |              |                        |           | <b>Status</b>            | <b>Progress</b> |
|           | Overhead circuit inspection             |              |                        |           | Complete                 | Aug-25          |
|           |   |              |                        |           |                          |                 |
|           |   |              |                        |           |                          |                 |
|           |   |              |                        |           |                          |                 |
| Rank      | Substation                              | Circuit      | District               | Customers | Outages                  |                 |
| 6         | Buena Vista                             | Chicora      | Butler                 | 1,149     | 32                       |                 |
|           | <b>Reliability</b>                      |              | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|           | SAIDI Impact                            | 1.78         | Trees Off Row-Tree     | 96%       | Q4 2024                  |                 |
|           | SAIDI                                   | 1,129.96     | Unknown                | 2%        | Q1 2025                  |                 |
|           | SAIFI                                   | 1.69         | Trees Off Row-Limb     | 1%        | Q2 2025                  |                 |
|           | CAIDI                                   | 668          | All Other              | 1%        | Q3 2025                  |                 |
|           | Customer Minutes                        | 1,298,324    |                        |           |                          |                 |
|           | Customers Affected                      | 1,944        |                        |           |                          |                 |
|           | <b>Remedial Action Planned or Taken</b> |              |                        |           | <b>Status</b>            | <b>Progress</b> |
|           | Cycle tree trimming                     |              |                        |           | Complete                 | Jul-24          |
|           | Overhead circuit inspection             |              |                        |           | Complete                 | Feb-25          |
|           |   |              |                        |           |                          |                 |
|           |   |              |                        |           |                          |                 |
|           |   |              |                        |           |                          |                 |

| West Penn   |   |                  |                        |                      |                          |
|-------------|---|------------------|------------------------|----------------------|--------------------------|
| Rank        | Substation                              | Circuit          | District               | Customers            | Outages                  |
| 7           | Flintstone                              | Chaneyville      | Hyndman                | 575                  | 47                       |
|             | <b>Reliability</b>                      |                  | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|             | SAIDI Impact                            | 1.75             | Trees Off Row-Tree     | 96%                  | Q2 2025                  |
|             | SAIDI                                   | 2,214.61         | Trees Off Row-Limb     | 1%                   | Q3 2025                  |
|             | SAIFI                                   | 2.37             | Equipment Failure      | 1%                   |                          |
|             | CAIDI                                   | 936              | All Other              | 3%                   |                          |
|             | Customer Minutes                        | 1,273,402        |                        |                      |                          |
|             | Customers Affected                      | 1,361            |                        |                      |                          |
|             | <b>Remedial Action Planned or Taken</b> |                  |                        | <b>Status</b>        | <b>Progress</b>          |
|             | Repair damage caused by a tree          |                  |                        | Complete             | Apr-25                   |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |
| <b>Rank</b> | <b>Substation</b>                       | <b>Circuit</b>   | <b>District</b>        | <b>Customers</b>     | <b>Outages</b>           |
| 8           | Franklin (Wpp)                          | South Waynesburg | Jefferson              | 2,059                | 43                       |
|             | <b>Reliability</b>                      |                  | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|             | SAIDI Impact                            | 1.69             | Trees Off Row-Tree     | 56%                  | Q4 2024                  |
|             | SAIDI                                   | 598.82           | Unknown                | 22%                  | Q2 2025                  |
|             | SAIFI                                   | 3.13             | Equipment Failure      | 18%                  | Q3 2025                  |
|             | CAIDI                                   | 191              | All Other              | 4%                   |                          |
|             | Customer Minutes                        | 1,232,969        |                        |                      |                          |
|             | Customers Affected                      | 6,447            |                        |                      |                          |
|             | <b>Remedial Action Planned or Taken</b> |                  |                        | <b>Status</b>        | <b>Progress</b>          |
|             | ESSS work requests                      |                  |                        | Complete             | Nov-24                   |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |
| <b>Rank</b> | <b>Substation</b>                       | <b>Circuit</b>   | <b>District</b>        | <b>Customers</b>     | <b>Outages</b>           |
| 9           | Houston                                 | Weavertown       | Washington Pa          | 2,347                | 36                       |
|             | <b>Reliability</b>                      |                  | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|             | SAIDI Impact                            | 1.67             | Unknown                | 53%                  | Q4 2024                  |
|             | SAIDI                                   | 517.10           | Trees Off Row-Tree     | 34%                  | Q1 2025                  |
|             | SAIFI                                   | 2.83             | Forced Outage          | 7%                   | Q2 2025                  |
|             | CAIDI                                   | 183              | All Other              | 6%                   | Q3 2025                  |
|             | Customer Minutes                        | 1,213,628        |                        |                      |                          |
|             | Customers Affected                      | 6,647            |                        |                      |                          |
|             | <b>Remedial Action Planned or Taken</b> |                  |                        | <b>Status</b>        | <b>Progress</b>          |
|             | On cycle tree trimming                  |                  |                        | To be completed 2025 | 60%                      |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |
|             |   |                  |                        |                      |                          |

| West Penn   |   |                |                        |                  |                          |
|-------------|---|----------------|------------------------|------------------|--------------------------|
| Rank        | Substation  | Circuit        | District               | Customers        | Outages                  |
| 10          | Dutch Fork  | Claysville     | Washington Pa          | 1,642            | 59                       |
|             | <b>Reliability</b>  |                | <b>Outage by Cause</b> |                  | <b>Previously Ranked</b> |
|             | SAIDI Impact  | 1.55           | Line Failure           | 36%              | Q4 2024                  |
|             | SAIDI   | 688.80         | Trees Off Row-Tree     | 28%              | Q1 2025                  |
|             | SAIFI   | 2.89           | Unknown                | 25%              | Q2 2025                  |
|             | CAIDI   | 239            | All Other              | 11%              | Q3 2025                  |
|             | Customer Minutes  | 1,131,013      |                        |                  |                          |
|             | Customers Affected  | 4,738          |                        |                  |                          |
|             | <b>Remedial Action Planned or Taken</b>                   |                |                        | <b>Status</b>    | <b>Progress</b>          |
|             | PAIR pole replacement                                     |                |                        | Complete         | Nov-24                   |
|             |   |                |                        |                  |                          |
|             |   |                |                        |                  |                          |
|             |   |                |                        |                  |                          |
|             |   |                |                        |                  |                          |
|             |   |                |                        |                  |                          |
| <b>Rank</b> | <b>Substation</b>   | <b>Circuit</b> | <b>District</b>        | <b>Customers</b> | <b>Outages</b>           |
| 11          | Purcell   | Artemas        | Hyndman                | 622              | 38                       |
|             | <b>Reliability</b>  |                | <b>Outage by Cause</b> |                  | <b>Previously Ranked</b> |
|             | SAIDI Impact  | 1.51           | Wind                   | 56%              | Q2 2025                  |
|             | SAIDI   | 1,771.57       | Trees Off Row-Tree     | 25%              | Q3 2025                  |
|             | SAIFI   | 1.65           | Trees On Row           | 11%              |                          |
|             | CAIDI   | 1,073          | All Other              | 7%               |                          |
|             | Customer Minutes  | 1,101,916      |                        |                  |                          |
|             | Customers Affected  | 1,027          |                        |                  |                          |
|             | <b>Remedial Action Planned or Taken</b>                   |                |                        | <b>Status</b>    | <b>Progress</b>          |
|             | On cycle tree trimming                                    |                |                        | Complete         | Sep-24                   |
|             | Overhead Circuit Inspection                               |                |                        | Complete         | Apr-25                   |
|             |   |                |                        |                  |                          |
|             |   |                |                        |                  |                          |
|             |   |                |                        |                  |                          |
|             |   |                |                        |                  |                          |
|             |   |                |                        |                  |                          |
| <b>Rank</b> | <b>Substation</b>   | <b>Circuit</b> | <b>District</b>        | <b>Customers</b> | <b>Outages</b>           |
| 12          | Bethlen   | Laurel Valley  | Latrobe                | 1,420            | 55                       |
|             | <b>Reliability</b>  |                | <b>Outage by Cause</b> |                  | <b>Previously Ranked</b> |
|             | SAIDI Impact  | 1.45           | Trees Off Row-Tree     | 56%              | Q2 2025                  |
|             | SAIDI   | 745.70         | Line Failure           | 19%              | Q3 2025                  |
|             | SAIFI   | 3.56           | Trees On Row           | 8%               |                          |
|             | CAIDI   | 210            | All Other              | 17%              |                          |
|             | Customer Minutes  | 1,058,889      |                        |                  |                          |
|             | Customers Affected  | 5,051          |                        |                  |                          |
|             | <b>Remedial Action Planned or Taken</b>                   |                |                        | <b>Status</b>    | <b>Progress</b>          |
|             | Forestry patrolled and removed 10 potential problem trees |                |                        | Complete         | Jun-25                   |
|             |   |                |                        |                  |                          |
|             |   |                |                        |                  |                          |
|             |   |                |                        |                  |                          |
|             |   |                |                        |                  |                          |
|             |   |                |                        |                  |                          |
|             |   |                |                        |                  |                          |

| West Penn              |   |            |                        |                      |                          |
|------------------------|---|------------|------------------------|----------------------|--------------------------|
| Rank                   | Substation                              | Circuit    | District               | Customers            | Outages                  |
| 13                     | Krendale                                | Prospect   | Butler                 | 1,487                | 28                       |
|                        | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                        | SAIDI Impact                            | 1.42       | Trees Off Row-Tree     | 70%                  | Q1 2025                  |
|                        | SAIDI                                   | 696.24     | Vehicle                | 27%                  | Q2 2025                  |
|                        | SAIFI                                   | 1.93       | Forced Outage          | 2%                   | Q3 2025                  |
|                        | CAIDI                                   | 361        | All Other              | 1%                   |                          |
|                        | Customer Minutes                        | 1,035,302  |                        |                      |                          |
|                        | Customers Affected                      | 2,871      |                        |                      |                          |
|                        | <b>Remedial Action Planned or Taken</b> |            |                        | <b>Status</b>        | <b>Progress</b>          |
|                        | Repair damage caused by a tree          |            |                        | Complete             | Dec-24                   |
|                        | ESSS work requests                      |            |                        | Complete             | Mar-25                   |
|                        | Zone 2 A phase patrol                   |            |                        | To be completed 2025 | 99%                      |
|                        |   |            |                        |                      |                          |
|                        |   |            |                        |                      |                          |
| Rank                   | Substation                              | Circuit    | District               | Customers            | Outages                  |
| 14                     | Rutan                                   | Bristoria  | Jefferson              | 409                  | 31                       |
|                        | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                        | SAIDI Impact                            | 1.40       | Trees Off Row-Tree     | 72%                  | Q4 2024                  |
|                        | SAIDI                                   | 2,491.21   | Trees - Sec/Service    | 14%                  | Q2 2025                  |
|                        | SAIFI                                   | 3.63       | Equipment Failure      | 9%                   | Q3 2025                  |
|                        | CAIDI                                   | 686        | All Other              | 5%                   |                          |
|                        | Customer Minutes                        | 1,018,903  |                        |                      |                          |
|                        | Customers Affected                      | 1,486      |                        |                      |                          |
|                        | <b>Remedial Action Planned or Taken</b> |            |                        | <b>Status</b>        | <b>Progress</b>          |
|                        | Overhead circuit inspection             |            |                        | Complete             | Apr-25                   |
|                        |   |            |                        |                      |                          |
|                        |   |            |                        |                      |                          |
|                        |   |            |                        |                      |                          |
| Rank                   | Substation                              | Circuit    | District               | Customers            | Outages                  |
| 15                     | Levelgreen                              | Levelgreen | Jeannette              | 1,562                | 31                       |
|                        | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                        | SAIDI Impact                            | 1.37       | Trees Off Row-Tree     | 91%                  | Q4 2024                  |
|                        | SAIDI                                   | 640.65     | Forced Outage          | 7%                   | Q1 2025                  |
|                        | SAIFI                                   | 3.06       | Equipment Failure      | 1%                   | Q2 2025                  |
|                        | CAIDI                                   | 209        | All Other              | 2%                   | Q3 2025                  |
|                        | Customer Minutes                        | 1,000,691  |                        |                      |                          |
|                        | Customers Affected                      | 4,777      |                        |                      |                          |
|                        | <b>Remedial Action Planned or Taken</b> |            |                        | <b>Status</b>        | <b>Progress</b>          |
|                        | Removed dead trees                      |            |                        | Complete             | Jul-24                   |
|                        | Underground inspection                  |            |                        | Complete             | May-25                   |
|                        | Repaired wire down caused by tree       |            |                        | Complete             | Jun-25                   |
|                        | LTIP - CP - adding phases for loading   |            |                        | Complete             | Jul-25                   |
| On cycle tree trimming |   |            | Complete               | Jul-25               |                          |
|                        |   |            |                        |                      |                          |

| West Penn |   |            |                        |           |                          |                 |
|-----------|---|------------|------------------------|-----------|--------------------------|-----------------|
| Rank      | Substation                              | Circuit    | District               | Customers | Outages                  |                 |
| 16        | North Fayette                           | Tyre       | Boyce                  | 1,929     | 45                       |                 |
|           | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|           | SAIDI Impact                            | 1.30       | Trees Off Row-Tree     | 65%       | Q4 2024                  |                 |
|           | SAIDI                                   | 489.73     | Unknown                | 17%       | Q1 2025                  |                 |
|           | SAIFI                                   | 4.63       | Forced Outage          | 10%       | Q3 2025                  |                 |
|           | CAIDI                                   | 106        | All Other              | 9%        |                          |                 |
|           | Customer Minutes                        | 944,685    |                        |           |                          |                 |
|           | Customers Affected                      | 8,927      |                        |           |                          |                 |
|           | <b>Remedial Action Planned or Taken</b> |            |                        |           | <b>Status</b>            | <b>Progress</b> |
|           | Overhead circuit inspection             |            |                        |           | Complete                 | Nov-24          |
|           | LTHIP - targeted pole replacmenets      |            |                        |           | Complete                 | Mar-25          |
|           |   |            |                        |           |                          |                 |
|           |   |            |                        |           |                          |                 |
| Rank      | Substation                              | Circuit    | District               | Customers | Outages                  |                 |
| 17        | Vanceville                              | Vanceville | Charleroi              | 1,395     | 57                       |                 |
|           | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|           | SAIDI Impact                            | 1.27       | Trees Off Row-Tree     | 60%       | Q2 2025                  |                 |
|           | SAIDI                                   | 664.81     | Equipment Failure      | 17%       | Q3 2025                  |                 |
|           | SAIFI                                   | 1.86       | Line Failure           | 15%       |                          |                 |
|           | CAIDI                                   | 358        | All Other              | 9%        |                          |                 |
|           | Customer Minutes                        | 927,414    |                        |           |                          |                 |
|           | Customers Affected                      | 2,594      |                        |           |                          |                 |
|           | <b>Remedial Action Planned or Taken</b> |            |                        |           | <b>Status</b>            | <b>Progress</b> |
|           | Repair damage caused by a tree          |            |                        |           | Complete                 | May-25          |
|           |   |            |                        |           |                          |                 |
|           |   |            |                        |           |                          |                 |
|           |   |            |                        |           |                          |                 |
| Rank      | Substation                              | Circuit    | District               | Customers | Outages                  |                 |
| 18        | Saltsburg                               | Avonmore   | Arnold                 | 797       | 30                       |                 |
|           | <b>Reliability</b>                      |            | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|           | SAIDI Impact                            | 1.26       | Trees Off Row-Tree     | 86%       | Q2 2025                  |                 |
|           | SAIDI                                   | 1,152.31   | Equipment Failure      | 12%       | Q3 2025                  |                 |
|           | SAIFI                                   | 4.63       | Unknown                | 2%        |                          |                 |
|           | CAIDI                                   | 249        | All Other              | 1%        |                          |                 |
|           | Customer Minutes                        | 918,390    |                        |           |                          |                 |
|           | Customers Affected                      | 3,693      |                        |           |                          |                 |
|           | <b>Remedial Action Planned or Taken</b> |            |                        |           | <b>Status</b>            | <b>Progress</b> |
|           | Overhead circuit inspection             |            |                        |           | Complete                 | Jan-25          |
|           |   |            |                        |           |                          |                 |
|           |   |            |                        |           |                          |                 |
|           |   |            |                        |           |                          |                 |
|           |   |            |                        |           |                          |                 |

| West Penn         |   |              |                        |                      |                          |
|-------------------|---|--------------|------------------------|----------------------|--------------------------|
| Rank              | Substation                              | Circuit      | District               | Customers            | Outages                  |
| 19                | Dutch Fork                              | W Alexander  | Washington Pa          | 1,167                | 56                       |
|                   | <b>Reliability</b>                      |              | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                   | SAIDI Impact                            | 1.26         | Trees Off Row-Tree     | 52%                  | Q2 2025                  |
|                   | SAIDI                                   | 786.07       | Unknown                | 23%                  | Q3 2025                  |
|                   | SAIFI                                   | 2.84         | Line Failure           | 9%                   |                          |
|                   | CAIDI                                   | 276          | All Other              | 16%                  |                          |
|                   | Customer Minutes                        | 917,341      |                        |                      |                          |
|                   | Customers Affected                      | 3,318        |                        |                      |                          |
|                   | <b>Remedial Action Planned or Taken</b> |              |                        | <b>Status</b>        | <b>Progress</b>          |
|                   | UG Circuit Inspection                   |              |                        | Complete             | Mar-25                   |
|                   |   |              |                        |                      |                          |
|                   |   |              |                        |                      |                          |
|                   |   |              |                        |                      |                          |
| Rank              | Substation                              | Circuit      | District               | Customers            | Outages                  |
| 20                | Necessity                               | Ohiopyle     | Uniontown              | 881                  | 50                       |
|                   | <b>Reliability</b>                      |              | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                   | SAIDI Impact                            | 1.22         | Trees Off Row-Tree     | 56%                  | Q3 2025                  |
|                   | SAIDI                                   | 1,009.25     | Wind                   | 22%                  |                          |
|                   | SAIFI                                   | 2.82         | Trees On Row           | 9%                   |                          |
|                   | CAIDI                                   | 358          | All Other              | 12%                  |                          |
|                   | Customer Minutes                        | 889,148      |                        |                      |                          |
|                   | Customers Affected                      | 2,486        |                        |                      |                          |
|                   | <b>Remedial Action Planned or Taken</b> |              |                        | <b>Status</b>        | <b>Progress</b>          |
|                   | Overhead circuit inspection             |              |                        | To be completed 2025 | 98%                      |
|                   |   |              |                        |                      |                          |
|                   |   |              |                        |                      |                          |
|                   |   |              |                        |                      |                          |
| Rank              | Substation                              | Circuit      | District               | Customers            | Outages                  |
| 21                | Necessity                               | Gibbon Glade | Uniontown              | 541                  | 27                       |
|                   | <b>Reliability</b>                      |              | <b>Outage by Cause</b> |                      | <b>Previously Ranked</b> |
|                   | SAIDI Impact                            | 1.20         | Trees Off Row-Tree     | 95%                  | Q2 2025                  |
|                   | SAIDI                                   | 1,620.28     | Equipment Failure      | 2%                   | Q3 2025                  |
|                   | SAIFI                                   | 2.80         | Wind                   | 2%                   |                          |
|                   | CAIDI                                   | 578          | All Other              | 1%                   |                          |
|                   | Customer Minutes                        | 876,570      |                        |                      |                          |
|                   | Customers Affected                      | 1,517        |                        |                      |                          |
|                   | <b>Remedial Action Planned or Taken</b> |              |                        | <b>Status</b>        | <b>Progress</b>          |
|                   | Repaired down primary                   |              |                        | Complete             | Apr-25                   |
|                   | Overhead circuit inspection             |              |                        | Complete             | May-25                   |
| Pole replacements |   |              | To be completed 2025   | 50%                  |                          |
|                   |   |              |                        |                      |                          |
|                   |   |              |                        |                      |                          |
|                   |   |              |                        |                      |                          |
|                   |   |              |                        |                      |                          |

| West Penn |   |             |                        |           |                          |                 |
|-----------|---|-------------|------------------------|-----------|--------------------------|-----------------|
| Rank      | Substation                              | Circuit     | District               | Customers | Outages                  |                 |
| 22        | Franklin (Wpp)                          | Rogersville | Jefferson              | 831       | 46                       |                 |
|           | <b>Reliability</b>                      |             | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|           | SAIDI Impact                            | 1.18        | Trees Off Row-Tree     | 41%       | Q2 2025                  |                 |
|           | SAIDI                                   | 1,032.40    | Trees On Row           | 35%       | Q3 2025                  |                 |
|           | SAIFI                                   | 2.07        | Vehicle                | 9%        |                          |                 |
|           | CAIDI                                   | 500         | All Other              | 15%       |                          |                 |
|           | Customer Minutes                        | 857,927     |                        |           |                          |                 |
|           | Customers Affected                      | 1,717       |                        |           |                          |                 |
|           | <b>Remedial Action Planned or Taken</b> |             |                        |           | <b>Status</b>            | <b>Progress</b> |
|           | Repair damage caused by a tree          |             |                        |           | Complete                 | Apr-25          |
|           |   |             |                        |           |                          |                 |
|           |   |             |                        |           |                          |                 |
|           |   |             |                        |           |                          |                 |
| Rank      | Substation                              | Circuit     | District               | Customers | Outages                  |                 |
| 23        | Donegal                                 | Champion    | Pleasant Valley        | 1,187     | 29                       |                 |
|           | <b>Reliability</b>                      |             | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|           | SAIDI Impact                            | 1.18        | Vehicle                | 49%       | Q4 2024                  |                 |
|           | SAIDI                                   | 722.26      | Trees Off Row-Tree     | 48%       | Q3 2025                  |                 |
|           | SAIFI                                   | 2.73        | Unknown                | 2%        |                          |                 |
|           | CAIDI                                   | 265         | All Other              | 2%        |                          |                 |
|           | Customer Minutes                        | 857,321     |                        |           |                          |                 |
|           | Customers Affected                      | 3,239       |                        |           |                          |                 |
|           | <b>Remedial Action Planned or Taken</b> |             |                        |           | <b>Status</b>            | <b>Progress</b> |
|           | Overhead circuit inspection             |             |                        |           | Complete                 | Aug-25          |
|           |   |             |                        |           |                          |                 |
|           |   |             |                        |           |                          |                 |
|           |   |             |                        |           |                          |                 |
| Rank      | Substation                              | Circuit     | District               | Customers | Outages                  |                 |
| 24        | Charleroi                               | Speers      | Charleroi              | 1,436     | 39                       |                 |
|           | <b>Reliability</b>                      |             | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|           | SAIDI Impact                            | 1.15        | Vehicle                | 49%       | Q2 2025                  |                 |
|           | SAIDI                                   | 582.36      | Trees Off Row-Tree     | 35%       | Q3 2025                  |                 |
|           | SAIFI                                   | 3.21        | Line Failure           | 8%        |                          |                 |
|           | CAIDI                                   | 182         | All Other              | 8%        |                          |                 |
|           | Customer Minutes                        | 836,263     |                        |           |                          |                 |
|           | Customers Affected                      | 4,606       |                        |           |                          |                 |
|           | <b>Remedial Action Planned or Taken</b> |             |                        |           | <b>Status</b>            | <b>Progress</b> |
|           | Repair damage caused by a tree          |             |                        |           | Complete                 | Jun-25          |
|           | Overhead circuit inspection             |             |                        |           | Complete                 | Mar-25          |
|           |   |             |                        |           |                          |                 |
|           |   |             |                        |           |                          |                 |

| West Penn                      |   |           |                        |           |                          |                 |
|--------------------------------|---|-----------|------------------------|-----------|--------------------------|-----------------|
| Rank                           | Substation                              | Circuit   | District               | Customers | Outages                  |                 |
| 25                             | Saltsburg                               | Saltsburg | Arnold                 | 1,396     | 44                       |                 |
|                                | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|                                | SAIDI Impact                            | 1.11      | Trees Off Row-Tree     | 45%       | Q3 2025                  |                 |
|                                | SAIDI                                   | 578.98    | Unknown                | 38%       |                          |                 |
|                                | SAIFI                                   | 2.58      | Line Failure           | 16%       |                          |                 |
|                                | CAIDI                                   | 225       | All Other              | 2%        |                          |                 |
|                                | Customer Minutes                        | 808,263   |                        |           |                          |                 |
|                                | Customers Affected                      | 3,595     |                        |           |                          |                 |
|                                | <b>Remedial Action Planned or Taken</b> |           |                        |           | <b>Status</b>            | <b>Progress</b> |
|                                | Overhead circuit inspection             |           |                        |           | Complete                 | Jan-25          |
|                                |   |           |                        |           |                          |                 |
|                                |   |           |                        |           |                          |                 |
|                                |   |           |                        |           |                          |                 |
| Rank                           | Substation                              | Circuit   | District               | Customers | Outages                  |                 |
| 26                             | Howard                                  | Town      | State College          | 1,155     | 58                       |                 |
|                                | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|                                | SAIDI Impact                            | 1.09      | Trees Off Row-Tree     | 93%       | Q2 2025                  |                 |
|                                | SAIDI                                   | 687.00    | Line Failure           | 2%        | Q3 2025                  |                 |
|                                | SAIFI                                   | 2.84      | Unknown                | 2%        |                          |                 |
|                                | CAIDI                                   | 242       | All Other              | 3%        |                          |                 |
|                                | Customer Minutes                        | 793,486   |                        |           |                          |                 |
|                                | Customers Affected                      | 3,276     |                        |           |                          |                 |
|                                | <b>Remedial Action Planned or Taken</b> |           |                        |           | <b>Status</b>            | <b>Progress</b> |
|                                | Repair damage caused by a tree          |           |                        |           | Complete                 | Feb-25          |
|                                | Repair damage caused by a tree          |           |                        |           | Complete                 | Apr-25          |
| Repair damage caused by a tree |   |           |                        | Complete  | Apr-25                   |                 |
| Pole replacements              |   |           |                        | Complete  | Sep-25                   |                 |
|                                |   |           |                        |           |                          |                 |
|                                |   |           |                        |           |                          |                 |
|                                |   |           |                        |           |                          |                 |
| Rank                           | Substation                              | Circuit   | District               | Customers | Outages                  |                 |
| 27                             | Smith                                   | Florence  | Washington Pa          | 806       | 59                       |                 |
|                                | <b>Reliability</b>                      |           | <b>Outage by Cause</b> |           | <b>Previously Ranked</b> |                 |
|                                | SAIDI Impact                            | 1.09      | Trees Off Row-Tree     | 74%       | Q2 2025                  |                 |
|                                | SAIDI                                   | 983.93    | Equipment Failure      | 5%        | Q3 2025                  |                 |
|                                | SAIFI                                   | 2.39      | Forced Outage          | 5%        |                          |                 |
|                                | CAIDI                                   | 412       | All Other              | 16%       |                          |                 |
|                                | Customer Minutes                        | 793,045   |                        |           |                          |                 |
|                                | Customers Affected                      | 1,923     |                        |           |                          |                 |
|                                | <b>Remedial Action Planned or Taken</b> |           |                        |           | <b>Status</b>            | <b>Progress</b> |
|                                | Overhead circuit inspection             |           |                        |           | Complete                 | Mar-25          |
|                                |   |           |                        |           |                          |                 |
|                                |   |           |                        |           |                          |                 |
|                                |   |           |                        |           |                          |                 |

| West Penn |   |           |                        |               |                          |
|-----------|---|-----------|------------------------|---------------|--------------------------|
| Rank      | Substation  | Circuit   | District               | Customers     | Outages                  |
| 28        | Hickory   | Hickory   | Washington Pa          | 956           | 31                       |
|           | <b>Reliability</b>                                |           | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|           | SAIDI Impact                                      | 1.05      | Equipment Failure      | 53%           | Q2 2025                  |
|           | SAIDI   | 799.42    | Trees Off Row-Tree     | 19%           | Q3 2025                  |
|           | SAIFI   | 2.24      | Line Failure           | 11%           |                          |
|           | CAIDI   | 357       | All Other              | 17%           |                          |
|           | Customer Minutes                                  | 764,241   |                        |               |                          |
|           | Customers Affected                                | 2,140     |                        |               |                          |
|           | <b>Remedial Action Planned or Taken</b>           |           |                        | <b>Status</b> | <b>Progress</b>          |
|           | LTIIP - Targeted porcelain equipment replacements |           |                        | Complete      | Aug-25                   |
|           |   |           |                        |               |                          |
|           |   |           |                        |               |                          |
|           |   |           |                        |               |                          |
|           |   |           |                        |               |                          |
|           |   |           |                        |               |                          |
| Rank      | Substation  | Circuit   | District               | Customers     | Outages                  |
| 29        | Huntingdon (Wpp)                                  | Shawtown  | Jeannette              | 1,798         | 21                       |
|           | <b>Reliability</b>                                |           | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|           | SAIDI Impact                                      | 1.03      | Equipment Failure      | 31%           | Q2 2025                  |
|           | SAIDI   | 416.67    | Forced Outage          | 30%           | Q3 2025                  |
|           | SAIFI   | 2.51      | Trees Off Row-Tree     | 21%           |                          |
|           | CAIDI   | 166       | All Other              | 18%           |                          |
|           | Customer Minutes                                  | 749,180   |                        |               |                          |
|           | Customers Affected                                | 4,509     |                        |               |                          |
|           | <b>Remedial Action Planned or Taken</b>           |           |                        | <b>Status</b> | <b>Progress</b>          |
|           | Repaired bad underground                          |           |                        | Complete      | Oct-24                   |
|           | Overhead circuit inspection                       |           |                        | Complete      | Aug-25                   |
|           |   |           |                        |               |                          |
|           |   |           |                        |               |                          |
|           |   |           |                        |               |                          |
|           |   |           |                        |               |                          |
|           |   |           |                        |               |                          |
| Rank      | Substation  | Circuit   | District               | Customers     | Outages                  |
| 30        | Roundhill   | Roundhill | Charleroi              | 953           | 35                       |
|           | <b>Reliability</b>                                |           | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|           | SAIDI Impact                                      | 1.03      | Trees Off Row-Tree     | 31%           | Q4 2024                  |
|           | SAIDI   | 785.43    | Wind                   | 27%           | Q1 2025                  |
|           | SAIFI   | 4.26      | Line Failure           | 24%           | Q2 2025                  |
|           | CAIDI   | 184       | All Other              | 19%           | Q3 2025                  |
|           | Customer Minutes                                  | 748,515   |                        |               |                          |
|           | Customers Affected                                | 4,061     |                        |               |                          |
|           | <b>Remedial Action Planned or Taken</b>           |           |                        | <b>Status</b> | <b>Progress</b>          |
|           | On cycle tree trimming                            |           |                        | Complete      | Mar-25                   |
|           |   |           |                        |               |                          |
|           |   |           |                        |               |                          |
|           |   |           |                        |               |                          |
|           |   |           |                        |               |                          |
|           |   |           |                        |               |                          |
|           |   |           |                        |               |                          |

| West Penn                               |   |                        |                        |                          |                          |
|---|---|------------------------|------------------------|--------------------------|--------------------------|
| Rank                                    | Substation                                      | Circuit                | District               | Customers                | Outages                  |
| 31                                      | Kiski Valley Distrib                            | Kittanning Rd          | Arnold                 | 1,759                    | 42                       |
|   | <b>Reliability</b>                              |                        | <b>Outage by Cause</b> |                          | <b>Previously Ranked</b> |
|   | SAIDI Impact                                    | 1.00                   | Trees Off Row-Tree     | 71%                      | Q1 2025                  |
|   | SAIDI   | 416.12                 | Trees Off Row-Limb     | 14%                      | Q2 2025                  |
|   | SAIFI   | 1.55                   | Unknown                | 8%                       | Q3 2025                  |
|   | CAIDI   | 269                    | All Other              | 7%                       |                          |
|   | Customer Minutes                                | 731,952                |                        |                          |                          |
|   | Customers Affected                              | 2,722                  |                        |                          |                          |
|   | <b>Remedial Action Planned or Taken</b>         |                        |                        | <b>Status</b>            | <b>Progress</b>          |
|   | Repair damage caused by a tree                  |                        |                        | Complete                 | Dec-24                   |
|   | Repair damage caused by a tree                  |                        |                        | Complete                 | Mar-25                   |
|   | ESSS work request                               |                        |                        | Complete                 | Mar-25                   |
|   |   |                        |                        |                          |                          |
|   | 32  | Lardin                 | Edenborn               | Uniontown                | 1,394                    |
| <b>Reliability</b>                      |   | <b>Outage by Cause</b> |                        | <b>Previously Ranked</b> |                          |
| SAIDI Impact                            |   | 0.98                   | Line Failure           | 59%                      | Q4 2024                  |
| SAIDI                                   |   | 512.11                 | Unknown                | 33%                      | Q1 2025                  |
| SAIFI                                   |   | 2.30                   | Trees Off Row-Tree     | 4%                       | Q2 2025                  |
| CAIDI                                   |   | 222                    | All Other              | 4%                       | Q3 2025                  |
| Customer Minutes                        |   | 713,888                |                        |                          |                          |
| Customers Affected                      |   | 3,209                  |                        |                          |                          |
| <b>Remedial Action Planned or Taken</b> |   |                        | <b>Status</b>          | <b>Progress</b>          |                          |
| Overhead circuit inspection             |   |                        | Complete               | Oct-24                   |                          |
| ESSS work requests                      |   |                        | Complete               | Feb-25                   |                          |
| On cycle tree trimming                  |   |                        | To Be Completed 2025   | 95%                      |                          |
| Underground inspection                  |   |                        | To Be Completed 2025   | 0%                       |                          |
|   |   |                        |                        |                          |                          |
| 33                                      | Waterville                                      | Waterville             | State College          | 364                      | 19                       |
|   | <b>Reliability</b>                              |                        | <b>Outage by Cause</b> |                          | <b>Previously Ranked</b> |
|   | SAIDI Impact                                    | 0.96                   | Other Electric Utility | 51%                      | Q4 2024                  |
|   | SAIDI   | 1,915.80               | Trees Off Row-Tree     | 41%                      | Q2 2025                  |
|   | SAIFI   | 5.67                   | Line Failure           | 7%                       | Q3 2025                  |
|   | CAIDI   | 338                    | All Other              | 1%                       |                          |
|   | Customer Minutes                                | 697,351                |                        |                          |                          |
|   | Customers Affected                              | 2,063                  |                        |                          |                          |
|   | <b>Remedial Action Planned or Taken</b>         |                        |                        | <b>Status</b>            | <b>Progress</b>          |
|   | Restore outage caused by other electric utility |                        |                        | Complete                 | May-25                   |
|   | Repair damage caused by trees                   |                        |                        | Complete                 | May-25                   |
|   | ESS work request                                |                        |                        | Complete                 | Apr-25                   |
|   | Restore outage caused by other electric utility |                        |                        | Complete                 | Jun-25                   |
|   | On cycle tree trimming                          |                        |                        | Complete                 | Sep-25                   |
|   |   |                        |                        |                          |                          |

| West Penn |   |              |                        |               |                          |
|-----------|---|--------------|------------------------|---------------|--------------------------|
| Rank      | Substation                              | Circuit      | District               | Customers     | Outages                  |
| 34        | Lagonda                                 | Lagonda      | Washington Pa          | 1,472         | 45                       |
|           | <b>Reliability</b>                      |              | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|           | SAIDI Impact                            | 0.95         | Trees Off Row-Tree     | 69%           | Q2 2025                  |
|           | SAIDI                                   | 472.25       | Equipment Failure      | 20%           | Q3 2025                  |
|           | SAIFI                                   | 3.13         | Forced Outage          | 4%            |                          |
|           | CAIDI                                   | 151          | All Other              | 7%            |                          |
|           | Customer Minutes                        | 695,157      |                        |               |                          |
|           | Customers Affected                      | 4,610        |                        |               |                          |
|           | <b>Remedial Action Planned or Taken</b> |              |                        | <b>Status</b> | <b>Progress</b>          |
|           | Underground inspection                  |              |                        | Complete      | Mar-25                   |
|           |   |              |                        |               |                          |
|           |   |              |                        |               |                          |
|           |   |              |                        |               |                          |
| Rank      | Substation                              | Circuit      | District               | Customers     | Outages                  |
| 35        | Donegal                                 | Bear Rocks   | Pleasant Valley        | 1,281         | 44                       |
|           | <b>Reliability</b>                      |              | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|           | SAIDI Impact                            | 0.93         | Trees Off Row-Tree     | 70%           | Q4 2024                  |
|           | SAIDI                                   | 531.13       | Trees Off Row-Limb     | 13%           | Q1 2025                  |
|           | SAIFI                                   | 2.14         | Unknown                | 9%            | Q3 2025                  |
|           | CAIDI                                   | 248          | All Other              | 8%            |                          |
|           | Customer Minutes                        | 680,380      |                        |               |                          |
|           | Customers Affected                      | 2,746        |                        |               |                          |
|           | <b>Remedial Action Planned or Taken</b> |              |                        | <b>Status</b> | <b>Progress</b>          |
|           | UG Circuit Inspection                   |              |                        | Complete      | Mar-25                   |
|           | Install voltage regulators              |              |                        | Complete      | Jun-25                   |
|           |   |              |                        |               |                          |
|           |   |              |                        |               |                          |
|           |   |              |                        |               |                          |
| Rank      | Substation                              | Circuit      | District               | Customers     | Outages                  |
| 36        | Thompson Farm                           | Village 12Kv | State College          | 1,397         | 3                        |
|           | <b>Reliability</b>                      |              | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|           | SAIDI Impact                            | 0.93         | Wind                   | 66%           | Q3 2025                  |
|           | SAIDI                                   | 486.84       | Animal                 | 34%           |                          |
|           | SAIFI                                   | 2.18         |                        |               |                          |
|           | CAIDI                                   | 223          | All Other              | 0%            |                          |
|           | Customer Minutes                        | 680,121      |                        |               |                          |
|           | Customers Affected                      | 3,051        |                        |               |                          |
|           | <b>Remedial Action Planned or Taken</b> |              |                        | <b>Status</b> | <b>Progress</b>          |
|           | Underground inspection                  |              |                        | Complete      | May-25                   |
|           |   |              |                        |               |                          |
|           |   |              |                        |               |                          |
|           |   |              |                        |               |                          |

| West Penn                  |   |             |                        |               |                          |
|----------------------------|---|-------------|------------------------|---------------|--------------------------|
| Rank                       | Substation                              | Circuit     | District               | Customers     | Outages                  |
| 37                         | Piney Fork                              | Stoltz      | Charleroi              | 2,088         | 29                       |
|                            | <b>Reliability</b>                      |             | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|                            | SAIDI Impact                            | 0.92        | Trees Off Row-Tree     | 34%           | Q4 2024                  |
|                            | SAIDI                                   | 319.37      | Trees Off Row-Limb     | 26%           | Q1 2025                  |
|                            | SAIFI                                   | 3.39        | Lightning              | 24%           | Q2 2025                  |
|                            | CAIDI                                   | 94          | All Other              | 16%           | Q3 2025                  |
|                            | Customer Minutes                        | 666,835     |                        |               |                          |
|                            | Customers Affected                      | 7,076       |                        |               |                          |
|                            | <b>Remedial Action Planned or Taken</b> |             |                        | <b>Status</b> | <b>Progress</b>          |
|                            | LTIIP - line rehab                      |             |                        | Complete      | Aug-25                   |
|                            |   |             |                        |               |                          |
|                            |   |             |                        |               |                          |
|                            |   |             |                        |               |                          |
| Rank                       | Substation                              | Circuit     | District               | Customers     | Outages                  |
| 38                         | Hempfield                               | Cool Valley | Jeannette              | 1,202         | 14                       |
|                            | <b>Reliability</b>                      |             | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|                            | SAIDI Impact                            | 0.91        | Equipment Failure      | 58%           | Q4 2024                  |
|                            | SAIDI                                   | 549.45      | Trees Off Row-Tree     | 18%           | Q1 2025                  |
|                            | SAIFI                                   | 3.22        | Line Failure           | 11%           | Q3 2025                  |
|                            | CAIDI                                   | 171         | All Other              | 13%           |                          |
|                            | Customer Minutes                        | 660,440     |                        |               |                          |
|                            | Customers Affected                      | 3,871       |                        |               |                          |
|                            | <b>Remedial Action Planned or Taken</b> |             |                        | <b>Status</b> | <b>Progress</b>          |
|                            | Repair equipment failure                |             |                        | Complete      | Dec-24                   |
|                            | Overhead circuit inspection             |             |                        | Complete      | Jan-25                   |
| Underground inspection     |   |             | Complete               | Apr-24        |                          |
| LTIIP - switch replacement |   |             | Complete               | Jun-25        |                          |
|                            |   |             |                        |               |                          |
|                            |   |             |                        |               |                          |
| Rank                       | Substation                              | Circuit     | District               | Customers     | Outages                  |
| 39                         | Westraver                               | West Newton | Charleroi              | 1,710         | 21                       |
|                            | <b>Reliability</b>                      |             | <b>Outage by Cause</b> |               | <b>Previously Ranked</b> |
|                            | SAIDI Impact                            | 0.89        | Wind                   | 53%           | Q2 2025                  |
|                            | SAIDI                                   | 378.19      | Trees Off Row-Tree     | 22%           | Q3 2025                  |
|                            | SAIFI                                   | 2.41        | Equipment Failure      | 16%           |                          |
|                            | CAIDI                                   | 157         | All Other              | 9%            |                          |
|                            | Customer Minutes                        | 646,701     |                        |               |                          |
|                            | Customers Affected                      | 4,122       |                        |               |                          |
|                            | <b>Remedial Action Planned or Taken</b> |             |                        | <b>Status</b> | <b>Progress</b>          |
|                            | Overhead circuit inspection             |             |                        | Complete      | Mar-25                   |
|                            |   |             |                        |               |                          |
|                            |   |             |                        |               |                          |
|                            |   |             |                        |               |                          |

| West Penn |                                  |                |                    |           |                   |
|-----------|----------------------------------|----------------|--------------------|-----------|-------------------|
| Rank      | Substation                       | Circuit        | District           | Customers | Outages           |
| 40        | Cecil                            | Hendersonville | Boyce              | 2,034     | 21                |
|           | Reliability                      |                | Outage by Cause    |           | Previously Ranked |
|           | SAIDI Impact                     | 0.88           | Trees Off Row-Tree | 60%       | Q3 2025           |
|           | SAIDI                            | 314.01         | Equipment Failure  | 24%       |                   |
|           | SAIFI                            | 2.41           | Line Failure       | 9%        |                   |
|           | CAIDI                            | 131            | All Other          | 7%        |                   |
|           | Customer Minutes                 | 638,688        |                    |           |                   |
|           | Customers Affected               | 4,894          |                    |           |                   |
|           | Remedial Action Planned or Taken |                |                    | Status    | Progress          |
|           | Repair equipment failure         |                |                    | Complete  | Dec-25            |
|           |                                  |                |                    |           |                   |
|           |                                  |                |                    |           |                   |
|           |                                  |                |                    |           |                   |
| Rank      | Substation                       | Circuit        | District           | Customers | Outages           |
| 41        | Guilford                         | Dixie          | Waynesboro         | 1,604     | 37                |
|           | Reliability                      |                | Outage by Cause    |           | Previously Ranked |
|           | SAIDI Impact                     | 0.87           | Wind               | 65%       | Q3 2025           |
|           | SAIDI                            | 1.66           | Line Failure       | 16%       |                   |
|           | SAIFI                            | 1.66           | Trees Off Row-Tree | 13%       |                   |
|           | CAIDI                            | 239            | All Other          | 7%        |                   |
|           | Customer Minutes                 | 636,845        |                    |           |                   |
|           | Customers Affected               | 2,662          |                    |           |                   |
|           | Remedial Action Planned or Taken |                |                    | Status    | Progress          |
|           | ESS work request                 |                |                    | Complete  | Aug-25            |
|           |                                  |                |                    |           |                   |
|           |                                  |                |                    |           |                   |
|           |                                  |                |                    |           |                   |

| <b>West Penn</b>   |                 |                |                |                |               |
|--|-----------------|----------------|----------------|----------------|---------------|
| <b>Unranked circuits appearing 2 or more quarters in the last 4 quarters</b> |                 |                |                |                |               |
| <b>Substation</b>  | <b>Circuit</b>  | <b>4Q 2024</b> | <b>1Q 2025</b> | <b>2Q 2025</b> | <b>Q32025</b> |
| Saltsburg  | Bell Township   | X              | X              | X              |               |
| Shaffers Corner  | Braeburn        | X              | X              |                |               |
| White Valley   | Borlands Rd     | X              | X              |                |               |
| White Valley   | Cloverleaf      | X              | X              |                |               |
| White Valley   | Congruity       | X              | X              |                |               |
| Finleyville  | Gastonville     | X              | X              |                |               |
| North Washington   | Poke Run        | X              | X              |                |               |
| Penn Trafford  | Pleasant Valley | X              | X              |                |               |
| Weedville  | Weedville       | X              | X              | X              |               |
| Lake Lynn-Unio   | Fancy Hill      | X              | X              | X              |               |
| Dry Run  | Town            | X              | X              |                |               |
| Parker   | Parker          | X              | X              | X              |               |
| Lardin   | Grays Landing   | X              | X              |                |               |
| Mackeyville  | Salona          | X              | X              |                |               |
| Smithton   | Smithton        | X              | X              |                |               |
| Harrison City  | Claridge        | X              | X              |                |               |

| <b>West Penn</b>   |                |   |  |  |
|--|----------------|---|--|--|
| <b>Unranked circuits with remedial actions scheduled to be or recently completed</b> |                |   |  |  |
| <b>Substation</b>  | <b>Circuit</b> | <b>Remedial Action Planned or Taken</b>             | <b>Status of Remedial Work Completed</b> | <b>Progress of Remedial Work or Date Completed</b> |
| Lake Lynn-Unio   | Fancy Hill     | On cycle tree trimming                              | To Be Completed 2025                     | 20%  |
| Dry Run  | Town           | On cycle tree trimming                              | To Be Completed 2025                     | 89%  |
| Newtown  | Bobtown        | On cycle tree trimming                              | To Be Completed 2025                     | 82%  |
| White Valley   | Cloverleaf     | LTIP - Circuit Protection                           | Complete                                 | Aug-25   |
| Footedale  | Footedale      | Overhead circuit inspection                         | Complete                                 | Jul-25   |
| Lardin   | Grays Landing  | Underground Inspection                              | To Be Completed 2025                     | 82%  |
| Milesburg  | Unionville     | LTIP - Circuit Improvement                          | To Be Completed 2025                     | 50%  |
| South Union  | York Run       | Overhead circuit inspection                         | Complete                                 | Sep-25   |
| Henry Clay   | Markleysburg   | Overhead circuit inspection                         | Complete                                 | Sep-25   |
| Saltsburg  | Bell Township  | Overvoltage Pilot                                   | Complete                                 | Sep-25   |
| Upton  | Church Hill    | Replace priority items identified during inspection | Complete                                 | Sep-25   |
| Iron Bridge  | Bridgeport     | Overhead circuit inspection                         | Complete                                 | Apr-25   |
| Normalville  | Mill Run       | Overhead circuit inspection                         | Complete                                 | Jul-25   |

*Pursuant to Docket Nos. D-2014-2365991, D-2014-2365992, D-2014-2365993, and D-2014-2365994, (Appendix A)(3): The Company is directed to track and measure line hit incidents, causes of line hits, and damage recovery amounts for all third-party line hit incidents for each Rate District.*

| <b>Met-Ed – Third Party Line Hit Incidents</b>      |                            |                            |                             |
|---|----------------------------|----------------------------|-----------------------------|
| <b>3<sup>rd</sup> Quarter 2025 12-Month Rolling</b> |                            |                            |                             |
| <b>Cause of Line Hit</b>                            | <b>Number of Incidents</b> | <b>Invoice Amount (\$)</b> | <b>Recovery Amount (\$)</b> |
| Dig In - Other                                      | 22                         | \$12,410.30                | \$0.00                      |
| Excavated in Tolerance                              | 32                         | \$183,520.08               | \$1,539.97                  |
| Excavation Inconsistent with Ticket Scope           | 1                          | \$7,557.18                 | \$0.00                      |
| Excavation Prior to Lawful Start Date               | 0                          | \$0.00                     | \$0.00                      |
| Expired Ticket                                      | 1                          | \$3,825.39                 | \$3,825.39                  |
| Hand Digging  | 0                          | \$0.00                     | \$0.00                      |
| Marked Improperly                                   | 7                          | \$34,234.85                | \$11,416.45                 |
| No Ticket   | 12                         | \$24,812.56                | \$4,491.98                  |
| <b>Total</b>  | <b>75</b>                  | <b>\$266,360.36</b>        | <b>\$21,273.79</b>          |

| <b>Penelec – Third Party Line Hit Incidents</b>     |                            |                            |                             |
|---|----------------------------|----------------------------|-----------------------------|
| <b>3<sup>rd</sup> Quarter 2025 12-Month Rolling</b> |                            |                            |                             |
| <b>Cause of Line Hit</b>                            | <b>Number of Incidents</b> | <b>Invoice Amount (\$)</b> | <b>Recovery Amount (\$)</b> |
| Dig In - Other                                      | 150                        | \$193,360.47               | \$19,171.34                 |
| Excavated in Tolerance                              | 35                         | \$99,868.69                | \$13,657.43                 |
| Excavation Inconsistent with Ticket Scope           | 1                          | \$1,335.28                 | \$1,335.28                  |
| Excavation Prior to Lawful Start Date               | 2                          | \$1,731.04                 | \$0.00                      |
| Expired Ticket                                      | 2                          | \$9,634.32                 | \$0.00                      |
| Hand Digging  | 0                          | \$0.00                     | \$0.00                      |
| Marked Improperly                                   | 14                         | \$17,116.25                | \$9,339.68                  |
| No Ticket   | 33                         | \$43,673.11                | \$4,249.41                  |
| <b>Total</b>  | <b>237</b>                 | <b>\$366,719.16</b>        | <b>\$47,753.14</b>          |

| <b>Penn Power – Third Party Line Hit Incidents</b>  |                            |                            |                             |
|---|----------------------------|----------------------------|-----------------------------|
| <b>3<sup>rd</sup> Quarter 2025 12-Month Rolling</b> |                            |                            |                             |
| <b>Cause of Line Hit</b>                            | <b>Number of Incidents</b> | <b>Invoice Amount (\$)</b> | <b>Recovery Amount (\$)</b> |
| Dig In - Other                                      | 6                          | \$0.00                     | \$0.00                      |
| Excavated in Tolerance                              | 13                         | \$59,125.74                | \$12,885.75                 |
| Excavation Inconsistent with Ticket Scope           | 0                          | \$0.00                     | \$0.00                      |
| Excavation Prior to Lawful Start Date               | 0                          | \$0.00                     | \$0.00                      |
| Expired Ticket                                      | 0                          | \$0.00                     | \$0.00                      |
| Hand Digging  | 0                          | \$0.00                     | \$0.00                      |
| Marked Improperly                                   | 5                          | \$18,623.88                | \$8,664.24                  |
| No Ticket   | 3                          | \$4,294.81                 | \$2,100.01                  |
| <b>Total</b>  | <b>27</b>                  | <b>\$82,044.43</b>         | <b>\$23,650.00</b>          |

| <b>West Penn – Third Party Line Hit Incidents</b>   |                            |                            |                             |
|---|----------------------------|----------------------------|-----------------------------|
| <b>3<sup>rd</sup> Quarter 2025 12-Month Rolling</b> |                            |                            |                             |
| <b>Cause of Line Hit</b>                            | <b>Number of Incidents</b> | <b>Invoice Amount (\$)</b> | <b>Recovery Amount (\$)</b> |
| Dig In - Other                                      | 59                         | \$151,612.50               | \$63,232.96                 |
| Excavated in Tolerance                              | 7                          | \$19,917.55                | \$1,476.14                  |
| Excavation Inconsistent with Ticket Scope           | 1                          | \$0.00                     | \$0.00                      |
| Excavation Prior to Lawful Start Date               | 1                          | \$2,505.04                 | \$0.00                      |
| Expired Ticket                                      | 1                          | \$5,700.20                 | \$0.00                      |
| Hand Digging  | 2                          | \$5,215.12                 | \$0.00                      |
| Marked Improperly                                   | 3                          | \$7,859.42                 | \$6,053.43                  |
| No Ticket   | 6                          | \$27,269.31                | \$22,361.32                 |
| <b>Total</b>  | <b>80</b>                  | <b>\$220,079.14</b>        | <b>\$93,123.85</b>          |

| <b>Cause of Line Hit</b>                  | <b>Definition</b>   |
|---|---|
| Dig In - Other                            | Still under investigation   |
| Excavated in Tolerance                    | Excavator did not use prudent digging techniques within the Tolerance Zone                  |
| Excavation Inconsistent with Ticket Scope | Excavation outside dig box and/or scope of ticket   |
| Excavation Prior to Lawful Start Date     | Three business days prior to start of excavation from when the ticket was called in to mark |
| Expired Ticket                            | After ten business days have passed, the ticket is considered expired                       |
| Hand Digging                              | Excavator was hand digging within the Tolerance Zone, however the facility was still hit    |
| Marked Improperly                         | Ticket called in, facility and/or equipment was not marked properly                         |
| No Ticket                                 | No contact was made to create a dig-request ticket  |