

M-2026-3059557

## PUC Notification – Major Construction Report

PECO Gas Projects Exceeding \$300,000

Notification Date:1/21/2026

PA §59.38	Information Requested by PUC	Data Provided by PECO
1	<b>Description of Proposed Work</b> (e.g., replace 700' of 4" cast iron, new regulator station, etc.)	Install 1164ft of 8" plastic, 1000ft of 4" plastic, 21ft of 6" plastic and 10ft of 2" plastic Retire 1085ft of 12" cast iron, 150ft of 2" plastic, 46ft of 6" plastic, 8ft of 6" coated steel, 655ft of 4" cast iron and 18ft of 4" plastic Transfer 6 services Renew 14 services
	<b>City/Borough/Township and County</b>	Springfield Township, Montgomery County
	<b>Extents of Project</b> (e.g., Main St. from 4th to 7th)	CHURCH RD FROM HEATHER RD TO SANDY HILL RD AND E HEATHER RD FROM CHURCH RD TO W HEATHER RD
2	<b>Type of Facility</b> (if other, please describe)	<input checked="" type="checkbox"/> Distribution Main/Services <input type="checkbox"/> Transmission Main <input type="checkbox"/> Regulator/Gate Station <input type="checkbox"/> Other: Click or tap here to enter text.
3	<b>Estimated Starting Date</b>	6/26/2026
4	<b>Estimated Completion Date</b>	9/29/2026
5	<b>Design Pressure</b>	MP-17
6	<b>Estimated Cost</b>	\$1,039,462
7	<b>Reporting Company</b> (name and address)	PECO, an Exelon Company 2301 Market St Philadelphia, PA 19103
8	<b>Project Contact</b> (name, address and phone number)	Evan DiPillo 300 Front St, Conshohocken, PA 19428 445-240-2104
9	<b>Actual Completion Date</b> (to be sent after project complete)	Click or tap to enter a date.