



PUC Notification of Proposed Major Expenditure

Submit reports to the PA PUC Secretary's Bureau through eFiling at

efiling.puc.pa.gov

Include case: Docket number ~~M-2025-305957~~ in the notification

M-2026-3059557- jbs 2/3/26

Also Email To: Safety Division

Email To The Following Addresses: RA-PC-Pipelinesafety@pa.gov & TCSmith@pa.gov

Regional Engineering Office	One UGI Center, Wilkes Barre, PA 18711
Description of Proposed Work	Install 6,365 LF of 6" PE4710 (MP) G.M. via HDD (Flat Trajectory), 1,140 LF of 6" PE4710 (MP) G.M. via HDD, and 630 LF of 6" PE4710 (MP) G.M. via direct burial. Project will renew (2) gas services, test and connect (1) gas service, and abandon (1) gas service. The work will be performed in public and private right-of-way along Route 6 (SR 0006) and Open Brook Road (T-418) in Liberty Township and Keating Township, McKean County.
Location of Proposed Work	Open Brook Road, Liberty Township, McKean County
Type of Facility	Natural Gas Distribution Main and Services.
Estimated Starting Date	Estimated Starting Date: 3/5/2026
Design Pressure (MAOP, psi)	60.00
Estimated Cost	Estimated Cost: \$1,588,000
Reporting Gas Company for Project	UGI Central
Project Contact Person(s)	Slowey, Kelsey E
Project Contact Person(s) Address & Phone	Project Contact Person(s) Address & Phone: One UGI Center, Wilkes-Barre, PA 18711; 570-899-1302
Estimated Completion Date	Estimated Completion Date: 5/15/2026
Actual Completion Date	Actual Completion Date:
PA PUC Notification Documentation	
Notified By (Proposed)	Slowey, Kelsey E
Notifier's Title (Proposed)	Notifier's Title (Proposition): Senior Engineer
Notification Date (Proposed)	Notification Date (Proposition): 2/3/2026
Notified By (Actual Completion)	
Notifier's Title (Actual Completion)	Notifier's Title (Actual Completion):
Notification Date (Actual Completion)	Notification Date (Actual Completion):