

Submit reports to the PA PUC Secretary's Bureau through eFiling at efiling.puc.pa.gov
Include case: Docket number M-2026-3059557 in the notification
Also Email To: Safety Division
Email To The Following Addresses: RA-PC-Pipelinesafety@pa.gov & TCSmith@pa.gov

Regional Engineering Office

One UGI Center, Wilkes Barre, PA 18711

Description of Proposed Work

To install 200 feet of six (6) inch coated steel gas main by direct burial and via hanger supports along the Harris Hill bridge after it's completion. This replacement project will eliminate 145 feet of existing coated steel gas main and 10 feet of existing plastic gas main. The work will be performed

Location of Proposed Work

Kingston Township, Luzerne County, PA.

Type of Facility

Natural Gas Distribution Main and Services.

Estimated Starting Date

September 1, 2026

Design Pressure (MAOP)

60

Estimated Cost

\$407,400.00

Reporting Gas Company for Project

UGI North

Project Contact Person(s)

Miller, Nicholas E

Project Contact Person(s) Address & Phone

150 Power Blvd, Archbald, PA 18403; 570-829-994

Estimated Completion Date

September 30, 2026